



May 3, 2016

FOUNDATION INVESTIGATION REPORT

**OSKONDAGA RIVER TRIBUTARY #1 AND TRIBUTARY #2 CULVERTS
SITE NOS. 48W-185/C AND 48W-186/C
HIGHWAY 17, DISTRICT OF THUNDER BAY
GOLDIE TOWNSHIP AND SOPER TOWNSHIP
MINISTRY OF TRANSPORTATION, ONTARIO
GWP 6943-10-00, WP 6905-12-01 & 6906-12-01**

Submitted to:

Hatch Ltd.
200 S. Syndicate Ave., Suite 301
Thunder Bay, ON
P7E 1C9



GEOCRES NO.: 52A-220

Report Number: 1533879-R03

Distribution:

- 1 PDF Copy - Ministry of Transportation, Ontario, Thunder Bay, ON (Northwestern Region)
- 1 PDF Copy - Ministry of Transportation, Ontario, Downsview, ON (Foundations Section)
- 1 Copy – Hatch Ltd., Thunder Bay, ON
- 1 PDF Copy - Golder Associates Ltd., Sudbury, ON

REPORT





Table of Contents

PART A – FOUNDATION INVESTIGATION REPORT

1.0 INTRODUCTION.....	1
2.0 SITE DESCRIPTION.....	1
2.1 Oskondaga River Tributary #1 Culvert.....	1
2.2 Oskondaga River Tributary #2 Culvert.....	1
3.0 INVESTIGATION PROCEDURES	2
4.0 SITE GEOLOGY AND SUBSURFACE CONDITIONS	3
4.1 Regional Geology	3
4.2 Subsurface Conditions.....	3
4.2.1 Oskondaga River Tributary #1 Culvert.....	4
4.2.2 Oskondaga River Tributary #2 Culvert.....	6
5.0 CLOSURE.....	8

TABLES

Table 1	Summary Details of Existing Culverts
Table 2	Summary of Analytical Testing of Oskondaga River Tributary Water Samples

FIGURES

Figure 1	Location Plan
----------	---------------

LIST OF SYMBOLS AND ABBREVIATIONS

LITHOLOGICAL AND GEOTECHNICAL ROCK DESCRIPTION TERMINOLOGY

APPENDICES

Appendix A	Oskondaga River Tributary #1 Culvert, Site No. 48W-185/C (Goldie Township)
Drawing A1	Borehole Locations and Soil Strata
Photographs	A-1 to A-4
Record of Boreholes	OS1-1 and OS1-2
Record of Drillhole	OS1-1
Figure A1	Grain Size Distribution – Sand to Sand and Gravel (Fill)
Figure A2	Plasticity Chart – Clay (Fill)
Figure A3	Grain Size Distribution – Sandy Clayey Silt and Sandy Silty Clay
Figure A4	Plasticity Chart – Sandy Clayey Silt and Sandy Silty Clay
Figure A5	Grain Size Distribution – Gravelly Silty Sand
Figure A6	Bedrock Core Photograph
Appendix B	Oskondaga River Tributary #2 Culvert, Site No. 48W-186/C (Soper Township)
Drawing B1	Borehole Locations and Soil Strata
Photographs	B-1 to B-4



**FOUNDATION REPORT - HIGHWAY 17 CULVERT REPLACEMENTS
OSKONDAGA RIVER TRIBUTARY #1 AND #2 CULVERTS,
GWP 6943-10-00, WP 6905-12-01 & 6906-12-01**

Record of Boreholes	OS2-1 to OS2-6
Figure B1	Grain Size Distribution – Sand to Sand and Gravel (Fill)
Figure B2	Grain Size Distribution – Clayey Silt (Fill)
Figure B3	Plasticity Chart – Clayey Silt (Fill)
Figure B4	Plasticity Chart – Organic Silt
Figure B5	Plasticity Chart – Silty Clay to Clay
Figure B6	Grain Size Distribution – Clay
Figure B7	Grain Size Distribution – Sand to Sand and Gravel
Figure B8	Grain Size Distribution – Gravelly Silt and Sand (Till)



PART A

**FOUNDATION INVESTIGATION REPORT
OSKONDAGA RIVER TRIBUTARY #1 & #2 CULVERTS (48W-185/C & 48W-186/C)
HIGHWAY 17, DISTRICT OF THUNDER BAY
TOWNSHIPS OF GOLDIE AND SOPER
MINISTRY OF TRANSPORTATION, ONTARIO
GWP 6943-10-00, WP 6905-12-01 & 6906-12-01**



1.0 INTRODUCTION

Golder Associates Ltd. (Golder) has been retained by Hatch on behalf of Ministry of Transportation, Ontario (MTO) to provide foundation engineering services for the temporary roadway protection associated with the rehabilitation of the Oskondaga River Tributary #1 and #2 culverts, Sites 48W-185/C and 48W-186/C, respectively. The Oskondaga River Tributary #1 and #2 culverts are located in the District of Thunder Bay in the Townships of Goldie and Soper, respectively, on Highway 17. The key plan showing the general locations of the culverts are shown on Figure 1.

2.0 SITE DESCRIPTION

The existing Oskondaga River Tributary #1 and #2 culverts consist of Concrete Boxes, the details of which (size, length, type, etc.) are summarized in Table 1 following the text of this report.

It should be noted that the orientation (i.e., north, south, east, west) stated in the text of the report is typically referenced to project north and therefore may differ from magnetic north shown on the drawings. For the purposes of this report, Highway 17 is oriented in a north-south direction for this section of roadway with the culvert perpendicular to the highway in an east-west orientation.

The Oskondaga River Tributaries generally flow southeast, discharging into the Shebandowan River. The Shebandowan River drains into the Matawin River, which ultimately flows into Lake Superior.

2.1 Oskondaga River Tributary #1 Culvert

The Oskondaga River Tributary #1 culvert is located in the District of Thunder Bay in the Township of Goldie on Highway 17 at about STA 12+939, approximately 190 m north of the Highway 17-Ivar Road junction in Shebandowan, Ontario.

In general, the topography in the area is relatively level to gently undulating with the exception of the steep roadway embankments at the creek location. There is dense tree cover beyond the highway right-of-way at the culvert location. At Oskondaga River Tributary #1 culvert, the highway grade is at Elevation 415.2 m. The existing culvert invert is at Elevation 406.75 m at the inlet (west end) and at Elevation 406.7 m at the outlet (east end). The inlet water level was at Elevation 406.9 m and the outlet water level was at Elevation 406.5 m, measured by others in December 2015. Ground surface conditions at the culvert location are shown on Photographs A-1 to A-4 in Appendix A.

2.2 Oskondaga River Tributary #2 Culvert

The Oskondaga River Tributary #2 culvert is located the District of Thunder Bay in the Township of Soper on Highway 17 at approximately STA 13+458, about 10 km generally south of Raith, Ontario.

In general, the topography in the area is relatively level to gently undulating with the exception of the steep roadway embankments at the creek location. There is dense tree cover beyond the highway right-of-way at the culvert location. At Oskondaga River Tributary #2 culvert, the highway grade is at Elevation 432.4 m. The existing culvert invert, is at Elevation 426.3 m at the inlet (east end) and at about Elevation 426.2 m at the outlet (west end). The inlet water level was at Elevation 427.0 m and the outlet water level was at Elevation 426.9 m, measured by others in December 2015. Ground surface conditions at the culvert location are shown on Photographs B-1 to B-4 in Appendix B.



3.0 INVESTIGATION PROCEDURES

The fieldwork for the investigation at the Oskondaga River Tributary #1 and #2 culvert sites was carried out between December 12 and 19, 2015, and January 13 and 21, 2016, during which period a total of eight boreholes were drilled at the two culvert sites. Two boreholes were drilled at Tributary #1 culvert (Boreholes OS1-1 and OS1-2) and six boreholes were advanced at Tributary #2 culvert (Boreholes OS2-1 to OS2-6). A dynamic cone penetration test (DCPT) was driven from the bottom of Borehole OS-2-2 at Tributary #2 culvert. A summary of the boreholes advanced at each culvert site is presented in Table 1 and the locations of the boreholes and culvert sites are shown on Drawings A1 and B1 in Appendices A and B, respectively.

The field investigation was carried out using truck-mounted and track-mounted CME-55 drill rigs supplied and operated by Cartwright Drilling Ltd. of Thunder Bay, Ontario, and truck-mounted buggy CME-75 and portable equipment supplied and operated by RPM Drilling Ltd. of Thunder Bay, Ontario.

The boreholes were advanced using a combination of 108 mm inside diameter hollow stem augers, NW casing, wash boring techniques, and NQ coring techniques. Soil samples were obtained in the boreholes at 0.75 m and 1.5 m intervals of depth using 50 mm outer diameter split-spoon samplers driven by an automatic hammer, in accordance with the Standard Penetration Test (SPT) procedures (ASTM D1586). At the borehole location where portable equipment was used, as noted on the applicable Record of Borehole sheet, a half weight hammer was used and the SPT 'N'-values were corrected, as appropriate. Field vane shear tests were conducted in cohesive soils for determination of undrained shear strengths (ASTM D2573, Standard Test Method for Field Vane Shear Strength Test) using MTO Standard 'N'-size vanes. The groundwater conditions and water levels in the open boreholes were observed during the drilling operations and are described on the Record of Borehole sheets in Appendices A and B.

All open boreholes were backfilled upon completion in accordance with Ontario Regulation 903 Wells (as amended).

The boreholes were advanced to depths ranging from 7.4 m to 18.3 m below existing ground surface to refusal or penetrating up to about 3 m into competent material, which is defined as material that will provide resistance to settlement or instability of the embankment, or into bedrock. Bedrock was cored in Borehole OS1-1.

The field work was supervised on a full-time basis by members of Golder's technical staff who: located the boreholes in the field; arranged for the clearance of underground services; supervised the drilling and sampling operations; logged the boreholes; and examined and cared for the soil and bedrock samples. The soil and bedrock samples were identified in the field, placed in labelled containers and transported to Golder's geotechnical laboratory in Sudbury for further examination and laboratory testing. Index and classification testing consisting of water content determinations, Atterberg limits and grain size distributions were carried out on selected soil samples. In addition, unconfined compressive strength tests were carried out on selected specimens of the bedrock core recovered from one borehole. The geotechnical laboratory testing was completed according to MTO LS standards.

A sample of the Tributary (creek) water was obtained during the field investigation at each culvert location, using appropriate sampling protocols and submitted to a specialist analytical laboratory under chain of custody procedures for testing for a suite of parameters.

The as-drilled borehole locations and elevations were measured and surveyed by members of our technical staff, referenced to the highway centreline and existing culvert. The locations were subsequently converted into MTM NAD 83 coordinates in AutoCAD. The borehole elevations converted to Geodetic datum using the highway



FOUNDATION REPORT - HIGHWAY 17 CULVERT REPLACEMENTS OSKONDAGA RIVER TRIBUTARY #1 AND #2 CULVERTS, GWP 6943-10-00, WP 6905-12-01 & 6906-12-01

centreline elevation provided by MTO in Drawings BC-1071-17-3 and E-1038-17-1. Borehole locations given on the Record of Borehole sheets and shown on Drawings A1 and B1 are positioned relative to MTM NAD 83 northing and easting coordinates and the ground surface elevations are referenced to Geodetic datum. The borehole locations and ground surface elevations are as follows:

Culvert Location (Township)	Borehole	MTM NAD 83 Coordinates (m)		Ground Surface Elevation (m)	Borehole/DCPT Depth (m)
		Northing	Easting		
Oskondaga River Tributary #1 Culvert Site 48W-185/C, STA 12+939 (Goldie)	OS1-1	5,389,962.9	312,678.1	415.1	18.3
	OS1-2	5,389,944.7	312,684.2	415.2	16.3
Oskondaga River Tributary #2 Culvert Site 48W-186/C, STA 13+458 (Soper)	OS2-1	5,399,145.9	313,353.1	427.6	7.4
	OS2-2*	5,399,133.0	313,350.6	427.6	5.9/7.5
	OS2-3	5,399,151.9	313,330.0	432.4	15.7
	OS2-4	5,399,132.4	313,332.6	432.4	11.0
	OS2-5	5,399,151.9	313,311.7	427.4	9.7
	OS2-6	5,399,136.5	313,311.1	427.5	9.3

Note: *DCPT driven from the bottom of the borehole.

4.0 SITE GEOLOGY AND SUBSURFACE CONDITIONS

4.1 Regional Geology

Based on Northern Ontario Engineering Geology Terrain (NOEGTS)¹ mapping, the subsoils in the vicinity of the Oskondaga River Tributary #1 and #2 culvert sites consists of esker glaciolacustrine plain deposits comprised primarily of sand and gravel bordered by bedrock outcrops and a ground moraine deposits comprised mainly of till.

Based on geological mapping by the Ministry of Northern Development and Mines (MNDM)², the Tributary #1 culvert site is underlain by metasedimentary rocks, comprised of wacke arkose, argillite, slate, marble, chert and iron formations, and contains minor metavolcanic rocks. The site is bordered by muscovite-bearing granitic rocks. The Tributary #2 culvert site is underlain by muscovite-bearing granitic rocks, comprised of muscovite-biotite, cordierite-biotite granite and granodiorite-tonalite. The site is bordered by metasedimentary rock formation.

4.2 Subsurface Conditions

The detailed subsurface soil and groundwater conditions encountered in the boreholes and the results of in situ and laboratory testing are given on the Record of Borehole sheets contained in Appendix A and Appendix B for Tributary #1 and #2 culvert sites, respectively. The results of the in situ field tests (i.e., SPT 'N'-values and undrained shear strengths from field vanes) as presented on the Record of Borehole sheets and in Section 4 are

¹ Northern Ontario Engineering Geology Terrain Study. Ontario Geological Society Electronic Mapping.

² Ministry of Northern Development of Mines. Bedrock Geology of Ontario – West Central Sheet, Ontario Geological Survey – Map 2542



uncorrected, except that the 'N'-values obtained by the use of the half-weight hammer have been corrected as noted in Section 3.0. The stratigraphic boundaries shown on the Record of Borehole sheets and on the interpreted cross-section and stratigraphic profile on Drawings A1 and B1, respectively, are inferred from non-continuous sampling and, therefore, represent transitions between soil types rather than exact planes of geological change. The subsoil conditions will vary between and beyond the borehole locations.

4.2.1 Oskondaga River Tributary #1 Culvert

A total of two boreholes, Boreholes OS1-1 and OS1-2, were advanced at the Tributary #1 culvert site. In addition, bedrock coring was completed in Borehole OS1-1. The borehole locations, ground surface elevations and interpreted stratigraphic conditions are shown on Drawing A1.

In summary, the subsoil conditions encountered at the site consist of asphalt, granular fill and clay fill, underlain by deposits of clayey silt to silty clay and gravelly silty sand, further underlain by greywacke bedrock. A more detailed description of the soil deposits, bedrock and groundwater conditions encountered in the boreholes is presented below.

Deposit/Layer Description	Boreholes	Deposit Thickness (m)	Deposit Surface Elevation (m)	N Values (blows)/ S_u Shear Strength (kPa)	Laboratory Testing
				Relative Density or Consistency	
Asphalt	OS1-1, OS1-2	0.2, 0.3	415.1, 415.2	n/a	n/a
(FILL) Sand^{1,2} , some gravel to Sand and Gravel , trace to some silt; brown; moist to wet	OS1-1, OS1-2	3.5, 8.4	414.9	N = 11 - 46 ²	w = 2% - 10% 3 - M (Fig. A1)
				Compact to Very Dense	
(FILL) Clay ; reddish brown; wet	OS1-1	3.5	411.4	N = 3 - 6 S_u = 67 S = 7	w = 50% w_p = 26% w_L = 70% I_p = 44% 1 - AL (Fig. A2)
				Firm to Stiff	
Sandy Clayey Silt to Sandy Silty Clay , trace gravel, trace to some organics; grey; wet	OS1-1, OS1-2	1.5, 2.9	407.9, 406.5	N = 4 - 18 S_u > 100	w = 24%, 30% w_p = 17%, 18% w_L = 29%, 41% I_p = 13%, 24% 2 - MH (Fig. A3) 2 - AL (Fig. A4)
				Firm to Very Stiff	
Gravelly Silty Sand³ , trace clay; grey; wet	OS1-1, OS1-2	6.5, >4.7	406.4, 403.6	N = 8 - 34 and 100 / 0.13	w = 10%, 12% 2 - MH (Fig. A5)
				Compact to Very Dense	

Notes:

N = SPT 'N'-value; number of blows for 0.3 m of penetration

S_u = Undrained Shear Strength (kPa)

S = Sensitivity

M = Sieve analysis



FOUNDATION REPORT - HIGHWAY 17 CULVERT REPLACEMENTS OSKONDAGA RIVER TRIBUTARY #1 AND #2 CULVERTS, GWP 6943-10-00, WP 6905-12-01 & 6906-12-01

MH = Combined Sieve and Hydrometer analysis

w = Natural Moisture Content (%)

w_p = Plastic Limit (%)

w_l = Liquid Limit (%)

I_p = Plasticity Index (%)

AL = Atterberg Limits Test

¹ 300 mm to 400 mm size boulders were encountered within the sand fill in both boreholes.

² SPT "N"-values of 105 blows for 0.15 m of penetration and 101 blows for 0.28 m of penetration were recorded on inferred cobbles/boulder.

³ Cobbles were encountered from 12.8 m to 13.7 m in depth in Borehole OS1-1.

Bedrock

Bedrock was encountered at a depth of 15.2 m (Elevation 399.9 m) in Borehole OS1-1 and cored for a length of 3.1 m.

The retrieved bedrock core is described as a fine to medium grained, moderately foliated, grey, greywacke as presented in the Record of Drillhole sheet in Appendix A. A photograph of the retrieved bedrock core samples is shown on Figure A6.

Borehole No.	Total Core Recovery	Rock Quality Designation	Quality Classification Table 3.10 of CFEM 2006 ³	Uniaxial Compressive Strength (MPa)	Strength Classification Table 3.5 of CFEM 2006 ³
OS1-1	92% - 100%	78% - 100%	Good to Excellent	31	(R3) Medium Strong

Groundwater Conditions

Unstabilized groundwater levels measured in the open boreholes upon completion of drilling are summarized below. The water levels at the inlet (west end) and outlet (east end) at the culvert were surveyed at Elevations 406.9 m and 406.5 m, respectively, measured by others in December 2015, respectively. Groundwater and creek water levels in the area are subject to seasonal fluctuations and variations due to precipitation events.

Borehole No.	Depth to Groundwater Level (m)	Groundwater Elevation (m)
OS1-1	7.7	407.4
OS1-2	11.6	403.6

Analytical Testing of Tributary Water

The results of an analytical test on a sample of tributary water taken at the culvert site are presented in Table 2. The suite of parameters tested include pH, sulphate, chloride, resistivity and conductivity.

³ Canadian Geological Society, 2006. Canadian Foundation Engineering Manual, 4th Edition.



4.2.2 Oskondaga River Tributary #2 Culvert

A total of six boreholes, Boreholes OS2-1 to OS2-6, were advanced at the Tributary #2 culvert site. In addition, a DCPT was driven from the bottom of Borehole OS2-2. The borehole locations, ground surface elevations and interpreted stratigraphic conditions are shown on Drawing B1.

In summary, the subsoil conditions encountered at the site consist of asphalt and embankment granular fill and clay fill for those boreholes drilled on the existing highway platform, topsoil and an organic silt deposit in those boreholes drilled on the south of the existing culvert, and a silty clay deposit at ground surface in those boreholes drilled on the north side of the existing culvert, underlain by a deposit of silty clay to clay, layers of sand and silt, sand to sand and gravel, all underlain by a deposit of silt and sand till. A more detailed description of the soil deposits, bedrock and groundwater conditions encountered in the boreholes is below.

Deposit/Layer Description	Boreholes	Deposit Thickness (m)	Deposit Surface Elevation (m)	N Values (blows)/ S_u Shear Strength (kPa)	Laboratory Testing
				Relative Density or Consistency	
Asphalt	OS2-3, OS2-4	0.3	432.4	n/a	n/a
(FILL) Sand , some gravel to Sand and Gravel , trace to some silt; brown; frozen to wet	OS2-3, OS2-4	1.8, 2.8	432.1	N = 7 - 22	w = 3% 2 - M (Fig. B1)
				Loose to Compact	
(FILL) Silty Clay to Clay ; trace to some sand, trace to some gravel; reddish brown; frozen to wet		1.3, 2.6	430.3, 429.4	N = 4 - 7	w = 17%
				Firm	
(FILL) Clayey Silt , trace organics; brown to grey; wet	OS2-3	2.2	429.0	N = 6 - 7	w = 26% w _p = 22% w _L = 31% I _p = 9% 1 - MH (Fig. B2) 1 - AL (Fig. B3)
				Firm	
Topsoil , trace sand to sand, trace silt to silty; brown-black; moist	OS2-2, OS2-6	0.8, 1.4	427.6, 427.5	N = 4, 14*	n/a
				Loose	
Organic Silt , trace to some sand, trace to some gravel; dark brown to black; wet		0.7, 0.8	426.8, 426.1	N = 2, 5	w = 57%, 72% w _p = 44% w _L = 92% I _p = 48% 1 - AL (Fig. B4)
				Soft to Firm	
Clayey Silt , some organics; grey; wet	OS2-3	0.7	426.8	n/a	n/a
Silty Clay , trace sand, trace to some organics; brown to grey; wet	OS2-1, OS2-5	2.2, 1.4	427.6, 427.4	N = 2 - 4	w = 44%, 72% w _p = 23%, 26% w _L = 43%, 48% I _p = 20%, 22% 2 - AL (Fig. B5)
				Soft to Firm	



**FOUNDATION REPORT - HIGHWAY 17 CULVERT REPLACEMENTS
OSKONDAGA RIVER TRIBUTARY #1 AND #2 CULVERTS,
GWP 6943-10-00, WP 6905-12-01 & 6906-12-01**

Deposit/Layer Description	Boreholes	Deposit Thickness (m)	Deposit Surface Elevation (m)	N Values (blows)/ s_u Shear Strength (kPa)	Laboratory Testing
				Relative Density or Consistency	
Clay¹ , trace sand; reddish brown; wet	OS2-1 to OS2-6	1.1 - 3.2	426.8 - 425.3	N = WH - 12 s_u = 34 - 72 S = 2 - 3 Firm to Stiff	w = 67% - 81% w_p = 27% - 32% w_l = 58% - 93% I_p = 35% - 67% 4 - MH (Fig. B6) 8 - AL (Fig. B5)
Silt , trace clay; grey; wet	OS2-2	0.6	422.9	N = 24 Compact	n/a
Sand , trace gravel to Sand and Gravel , trace to some silt; grey; wet	OS2-1 to OS2-3, OS2-5 to OS2-6	0.6 - 1.4	424.5 - 421.9	N = 9 - 41 and 112/0.23 Loose to Very Dense	w = 7% - 15% 4 - MH (Fig. B7)
(TILL) Silt and Sand to Silty Sand^{2,3,4} , trace gravel to and gravel	OS2-1, OS2-3 to OS2-6	0.9 - 5.6	423.7 - 420.5	N = 13 to 75/0.08 Compact to Very Dense	w = 8% - 10% 2 - MH (Fig. B8)

Notes:

N = SPT 'N'-value; number of blows for 0.3 m of penetration

s_u = Undrained Shear Strength (kPa)

S = Sensitivity

M = Sieve analysis

MH = Combined Sieve and Hydrometer analysis

w = Natural Moisture Content (%)

w_p = Plastic Limit (%)

w_l = Liquid Limit (%)

I_p = Plasticity Index (%)

AL = Atterberg Limits Test

* Frozen

¹ Trace organics noted between 5.6 m and 7.2 m in Borehole OS2-4.

² 60 mm to 230 mm cobbles encountered in Boreholes OS2-3 from depths of 11.0 to 12.5 m, in Borehole OS2-4 from depths of 9.4 m to 10.5 m, in Borehole OS2-5 from depths of 5.4 m to 7.6 m, and in Borehole OS2-6 from depths of 7.0 m to 9.1 m.

³ SPT "N"-values for various drives for less than 0.3 m of penetration inferred to be indicative of the split-spoon refusing on an obstruction, likely cobbles.

⁴ A 0.4 m size boulder was encountered underlying the till deposit in Borehole OS2-5 at Elevation 418.1 m.

Groundwater Conditions

Unstabilized groundwater levels measured in the open boreholes upon completion of drilling are summarized below. The water level at the inlet (east end) and outlet (west end) at the culvert was surveyed at Elevations 427.0 m and 426.9 m, respectively, measured by others in December 2015. Groundwater and creek water levels in the area are subject to seasonal fluctuations and variations due to precipitation events.



Borehole No.	Depth to Groundwater Level (m)	Groundwater Elevation (m)
OS2-1	0.4	427.2
OS2-2	0.4	427.2
OS2-3	3.8	428.6
OS2-4	3.5	428.9
OS2-5	0.0	427.4
OS2-6	0.1	427.4

Analytical Testing of Tributary Water

The results of an analytical test on a sample of tributary water taken at the culvert site are presented in Table 2. The suite of parameters tested include pH, sulphate, chloride, resistivity and conductivity.

5.0 CLOSURE

The drilling program was supervised by Mr. Mathew Riopelle, Mr. Randy Axford and Mr. Mike Arthur under the direction of Mr. David Muldowney, P.Eng. This report was prepared by Ms. Sarah Nhan, E.I.T. The technical aspects were reviewed by Ms. Nikol Kochmanová, P.Eng., and Mr. Jorge M. A. Costa, P.Eng., Principal and Golder's Designated MTO Foundations Contact for this project, carried out a quality control review of the report.



Report Signature Page

GOLDER ASSOCIATES LTD.

Sarah Nhan, E.I.T.

Geotechnical Engineer-in-Training



Nikol Kochmanová, Ph.D., P.Eng., PMP
Geotechnical Engineer



Jorge M. A. Costa, P.Eng.
Designated MTO Foundations Contact, Principal

SN/NK/JMAC/kp/ls

Golder, Golder Associates and the GA globe design are trademarks of Golder Associates Corporation.

n:\active\2015\3 proj\1533879 hmm_5014-e-0054_hwy 17 11 lb\reporting\foundations\r03 - oskondaga river trib 1 and 2\final\1533879 rpt r03 18may3 oskondaga trib 1 and 2 fir.docx



**FOUNDATION REPORT - HIGHWAY 17 CULVERT REPLACEMENTS
OSKONDAGA RIVER TRIBUTARY #1 AND #2 CULVERTS,
GWP 6943-10-00, WP 6905-12-01 & 6906-12-01**

Table 1: Summary Details of Existing Culverts

Culvert Location Highway 17 (Township)	Approximate Existing Embankment Height ¹ (m)	Existing Culvert			Approximate Inlet/Outlet Invert Elevation (m)	Boreholes	Reference Appendix
		Type	Height x Span (m)	Length (m)			
Oskondaga River Tributary #1 Culvert, Site 48W-185/C, STA 12+939 (Goldie)	7.5 (4 m over culvert)	Cast-in-Place Reinforced Concrete Box	3.6 x 6.1	45.7	406.9/406.5	2 Boreholes	A
Oskondaga River Tributary #2 Culvert, Site 48W-186/C, STA 13+458 (Soper)	5.5 (3 m over culvert)	Cast-in-Place Reinforced Concrete Box	2.5 x 6.1	36	427.0/426.9	6 Boreholes 1 DCPT (OS2-2)	B

Note: 1. Embankment height is relative to existing ground surface level near toe of embankment adjacent to culvert.

Prepared by: SN
Reviewed by: NK




**FOUNDATION REPORT - HIGHWAY 17 CULVERT REPLACEMENTS
OSKONDAGA RIVER TRIBUTARY #1 AND #2 CULVERTS,
GWP 6943-10-00, WP 6905-12-01 & 6906-12-01**

Table 2: Summary of Analytical Testing of Oskondaga River Tributary Surface Water Samples

Culvert Location Highway 17 (Township)	Parameter (Units, Detection Limit)				
	Chloride (mg/L, 0.1)	Sulphate (mg/L, 0.3)	Conductivity (μ S/cm, 3)	Resistivity (ohm-cm, 0.33)	pH (0.1)
Oskondaga River Tributary #1 Culvert, Site 48W-185/C, STA 12+939 (Goldie)	1.6	2.3	50	20,040	7.01
Oskondaga River Tributary #2 Culvert, Site 48W-186/C, STA 13+458 (Soper)	2.0	2.3	55	18,292	6.97

Notes: 1. Samples obtained December 17, 2015.
2. Analytical testing carried out by ALS Environmental.

Prepared by: SN
Reviewed by: NK




INDEX MAP



Legend

- ★ Site Location
- Highway
- Waterbodies



NOTE(S)

THIS FIGURE IS TO BE READ IN CONJUNCTION WITH THE ACCOMPANYING GOLDER ASSOCIATES LTD. REPORT NO. 1533879/1000

REFERENCE(S)

SERVICE LAYER CREDITS: ESRI, DELORME, GEBCO, NOAA NGDC, AND OTHER CONTRIBUTORS CONTAINS INFORMATION LICENSED UNDER THE OPEN GOVERNMENT LICENCE – ONTARIO.
[HTTPS://WWW.ONTARIO.CA/GOVERNMENT/OPEN-GOVERNMENT-LICENCE-ONTARIO](https://www.ontario.ca/government/open-government-licence-ontario)
 PROJECTION: TRANSVERSE MERCATOR DATUM: NAD 83
 COORDINATE SYSTEM: UTM ZONE 17 VERTICAL DATUM: CGVD28

CLIENT

ONTARIO MINISTRY OF TRANSPORTATION

PROJECT

OSKONDAGA RIVER TRIBUTARY #1 AND #2
 CULVERTS REHABILITATION

TITLE

LOCATION PLAN

CONSULTANT



YYYY-MM-DD 2016-03-24

DESIGNED RRD

PREPARED RRD

REVIEWED AC

APPROVED JMAC

PROJECT NO.
1533879

CONTROL
1000

REV.
A

FIGURE
1

1 in IF THIS MEASUREMENT DOES NOT MATCH WHAT IS SHOWN, THE SHEET SIZE HAS BEEN MODIFIED FROM:



LIST OF SYMBOLS

Unless otherwise stated, the symbols employed in the report are as follows:

I. GENERAL

π	3.1416
$\ln x$,	natural logarithm of x
\log_{10}	x or log x, logarithm of x to base 10
g	acceleration due to gravity
t	time
FoS	factor of safety

II. STRESS AND STRAIN

γ	shear strain
Δ	change in, e.g. in stress: $\Delta \sigma$
ε	linear strain
ε_v	volumetric strain
η	coefficient of viscosity
ν	Poisson's ratio
σ	total stress
σ'	effective stress ($\sigma' = \sigma - u$)
σ'_{vo}	initial effective overburden stress
$\sigma_1, \sigma_2, \sigma_3$	principal stress (major, intermediate, minor)
σ_{oct}	mean stress or octahedral stress $= (\sigma_1 + \sigma_2 + \sigma_3)/3$
τ	shear stress
u	porewater pressure
E	modulus of deformation
G	shear modulus of deformation
K	bulk modulus of compressibility

III. SOIL PROPERTIES

(a)	Index Properties
$\rho(\gamma)$	bulk density (bulk unit weight)*
$\rho_d(\gamma_d)$	dry density (dry unit weight)
$\rho_w(\gamma_w)$	density (unit weight) of water
$\rho_s(\gamma_s)$	density (unit weight) of solid particles
γ'	unit weight of submerged soil ($\gamma' = \gamma - \gamma_w$)
D_R	relative density (specific gravity) of solid particles ($D_R = \rho_s / \rho_w$) (formerly G_s)
e	void ratio
n	porosity
S	degree of saturation

(a) Index Properties (continued)

w	water content
w_l or LL	liquid limit
w_p or PL	plastic limit
I_p or PI	plasticity index = $(w_l - w_p)$
w_s	shrinkage limit
I_L	liquidity index = $(w - w_p) / I_p$
I_C	consistency index = $(w_l - w) / I_p$
e_{max}	void ratio in loosest state
e_{min}	void ratio in densest state
I_D	density index = $(e_{max} - e) / (e_{max} - e_{min})$ (formerly relative density)

(b) Hydraulic Properties

h	hydraulic head or potential
q	rate of flow
v	velocity of flow
i	hydraulic gradient
k	hydraulic conductivity (coefficient of permeability)
j	seepage force per unit volume

(c) Consolidation (one-dimensional)

C_c	compression index (normally consolidated range)
C_r	recompression index (over-consolidated range)
C_s	swelling index
C_α	secondary compression index
m_v	coefficient of volume change
C_v	coefficient of consolidation (vertical direction)
C_h	coefficient of consolidation (horizontal direction)
T_v	time factor (vertical direction)
U	degree of consolidation
σ'_p	pre-consolidation stress
OCR	over-consolidation ratio = σ'_p / σ'_{vo}

(d) Shear Strength

τ_p, τ_r	peak and residual shear strength
ϕ'	effective angle of internal friction
δ	angle of interface friction
μ	coefficient of friction = $\tan \delta$
c'	effective cohesion
c_u, s_u	undrained shear strength ($\phi = 0$ analysis)
p	mean total stress $(\sigma_1 + \sigma_3)/2$
p'	mean effective stress $(\sigma'_1 + \sigma'_3)/2$
q	$(\sigma_1 - \sigma_3)/2$ or $(\sigma'_1 - \sigma'_3)/2$
q_u	compressive strength $(\sigma_1 - \sigma_3)$
S_t	sensitivity

* Density symbol is ρ . Unit weight symbol is γ where $\gamma = \rho g$ (i.e. mass density multiplied by acceleration due to gravity)

Notes: 1
2

$$\tau = c' + \sigma' \tan \phi'$$

$$\text{shear strength} = (\text{compressive strength})/2$$



LIST OF ABBREVIATIONS

The abbreviations commonly employed on Records of Boreholes, on figures and in the text of the report are as follows:

I. SAMPLE TYPE

AS	Auger sample
BS	Block sample
CS	Chunk sample
DS	Denison type sample
FS	Foil sample
RC	Rock core
SC	Soil core
SS	Split-spoon
ST	Slotted tube
TO	Thin-walled, open
TP	Thin-walled, piston
WS	Wash sample

II. PENETRATION RESISTANCE

Standard Penetration Resistance (SPT), N:

The number of blows by a 63.5 kg. (140 lb.) hammer dropped 760 mm (30 in.) required to drive a 50 mm (2 in.) drive open sampler for a distance of 300 mm (12 in.)

Dynamic Cone Penetration Resistance; N_d :

The number of blows by a 63.5 kg (140 lb.) hammer dropped 760 mm (30 in.) to drive uncased a 50 mm (2 in.) diameter, 60° cone attached to "A" size drill rods for a distance of 300 mm (12 in.).

PH: Sampler advanced by hydraulic pressure

PM: Sampler advanced by manual pressure

WH: Sampler advanced by static weight of hammer

WR: Sampler advanced by weight of sampler and rod

Piezo-Cone Penetration Test (CPT)

A electronic cone penetrometer with a 60° conical tip and a project end area of 10 cm² pushed through ground at a penetration rate of 2 cm/s. Measurements of tip resistance (Q_t), porewater pressure (PWP) and friction along a sleeve are recorded electronically at 25 mm penetration intervals.

III. SOIL DESCRIPTION

(a) Non-Cohesive (Cohesionless) Soils

Density Index	N
Relative Density	Blows/300 mm or Blows/ft
Very loose	0 to 4
Loose	4 to 10
Compact	10 to 30
Dense	30 to 50
Very dense	over 50

(b) Cohesive Soils Consistency

	C_u, S_u	
	kPa	psf
Very soft	0 to 12	0 to 250
Soft	12 to 25	250 to 500
Firm	25 to 50	500 to 1,000
Stiff	50 to 100	1,000 to 2,000
Very stiff	100 to 200	2,000 to 4,000
Hard	over 200	over 4,000

IV. SOIL TESTS

w	water content
w_p	plastic limit
w_l	liquid limit
C	consolidation (oedometer) test
CHEM	chemical analysis (refer to text)
CID	consolidated isotropically drained triaxial test ¹
CIU	consolidated isotropically undrained triaxial test with porewater pressure measurement ¹
D_R	relative density (specific gravity, G_s)
DS	direct shear test
M	sieve analysis for particle size
MH	combined sieve and hydrometer (H) analysis
MPC	Modified Proctor compaction test
SPC	Standard Proctor compaction test
OC	organic content test
SO_4	concentration of water-soluble sulphates
UC	unconfined compression test
UU	unconsolidated undrained triaxial test
V	field vane (LV-laboratory vane test)
γ	unit weight

Note: 1 Tests which are anisotropically consolidated prior to shear are shown as CAD, CAU.

V. MINOR SOIL CONSTITUENTS

Per cent by Weight	Modifier	Example
0 to 5	Trace	Trace sand
5 to 12	Trace to Some (or Little)	Trace to some sand
12 to 20	Some	Some sand
20 to 30	(ey) or (y)	Sandy
over 30	And (non-cohesive (cohesionless)) or With (cohesive)	Sand and Gravel Silty Clay with sand / Clayey Silt with sand



LITHOLOGICAL AND GEOTECHNICAL ROCK DESCRIPTION TERMINOLOGY

WEATHERINGS STATE

Fresh: no visible sign of weathering

Faintly weathered: weathering limited to the surface of major discontinuities.

Slightly weathered: penetrative weathering developed on open discontinuity surfaces but only slight weathering of rock material.

Moderately weathered: weathering extends throughout the rock mass but the rock material is not friable.

Highly weathered: weathering extends throughout rock mass and the rock material is partly friable.

Completely weathered: rock is wholly decomposed and in a friable condition but the rock and structure are preserved.

BEDDING THICKNESS

Description	Bedding Plane Spacing
Very thickly bedded	Greater than 2 m
Thickly bedded	0.6 m to 2 m
Medium bedded	0.2 m to 0.6 m
Thinly bedded	60 mm to 0.2 m
Very thinly bedded	20 mm to 60 mm
Laminated	6 mm to 20 mm
Thinly laminated	Less than 6 mm

JOINT OR FOLIATION SPACING

Description	Spacing
Very wide	Greater than 3 m
Wide	1 m to 3 m
Moderately close	0.3 m to 1 m
Close	50 mm to 300 mm
Very close	Less than 50 mm

GRAIN SIZE

Term	Size*
Very Coarse Grained	Greater than 60 mm
Coarse Grained	2 mm to 60 mm
Medium Grained	60 microns to 2 mm
Fine Grained	2 microns to 60 microns
Very Fine Grained	Less than 2 microns

Note: * Grains greater than 60 microns diameter are visible to the naked eye.

CORE CONDITION

Total Core Recovery (TCR)

The percentage of solid drill core recovered regardless of quality or length, measured relative to the length of the total core run.

Solid Core Recovery (SCR)

The percentage of solid drill core, regardless of length, recovered at full diameter, measured relative to the length of the total core run.

Rock Quality Designation (RQD)

The percentage of solid drill core, greater than 100 mm length, recovered at full diameter, measured relative to the length of the total core run. RQD varied from 0% for completely broken core to 100% for core in solid sticks.

DISCONTINUITY DATA

Fracture Index

A count of the number of discontinuities (physical separations) in the rock core, including both naturally occurring fractures and mechanically induced breaks caused by drilling.

Dip with Respect to Core Axis

The angle of the discontinuity relative to the axis (length) of the core. In a vertical borehole a discontinuity with a 90° angle is horizontal.

Description and Notes

An abbreviation description of the discontinuities, whether naturally occurring separations such as fractures, bedding planes and foliation planes or mechanically induced features caused by drilling such as ground or shattered core and mechanically separated bedding or foliation surfaces. Additional information concerning the nature of fracture surfaces and infillings are also noted.




Abbreviations

JN Joint	PL Planar
FLT Fault	CU Curved
SH Shear	UN Undulating
VN Vein	IR Irregular
FR Fracture	K Slickensided
SY Stylolite	PO Polished
BD Bedding	SM Smooth
FO Foliation	SR Slightly Rough
CO Contact	RO Rough
AXJ Axial Joint	VR Very Rough
KV Karstic Void	
MB Mechanical Break	



APPENDIX A

**Oskondaga River Tributary #1 Culvert, Site No. 48W-185/C
(Goldie Township)**




METRIC
DIMENSIONS ARE IN METRES AND/OR
MILLIMETRES UNLESS OTHERWISE SHOWN.
STATIONS IN KILOMETRES + METRES.

CONT No.
GWP No.6943-10-00



HIGHWAY 17
OSKONDAGA RIVER TRIBUTARY #1 CULVERT STA 12+939
BOREHOLE LOCATIONS AND
SOIL STRATA

SHEET



KEY PLAN
SCALE



LEGEND

- Borehole - Current Investigation
- N Standard Penetration Test Value
- 16 Blows/0.3m unless otherwise stated
(Std. Pen. Test, 475 j/blow)
- 100% Rock Quality Designation (RQD)
- R Refusal
- ▽ WL upon completion of drilling

BOREHOLE CO-ORDINATES			
No.	ELEVATION	NORTHING	EASTING
OS1-1	415.1	5389962.9	312678.1
OS1-2	415.2	5389944.7	312684.2

NOTES

This drawing is for subsurface information only. The proposed structure details/works are shown for illustration purposes only and may not be consistent with the final design configuration as shown elsewhere in the Contracts Documents.

The boundaries between soil strata have been established only at borehole locations. Between boreholes the boundaries are assumed from geological evidence.

The complete Foundation Investigation and Design Report for this project and other related documents may be examined at the Materials Engineering and Research Office, Downsview. Information contained in this report and related documents is specifically excluded in accordance with Section GC 2.01 of OPS General Conditions.

REFERENCE

Base plans provided in digital format by MTO, drawing file nos. BC1071173 received Dec. 11, 2015.



NO.	DATE	BY	REVISION
Geocres No. 52A-220			
HWY. 17	PROJECT NO. 1533879		DIST. .
SUBM'D. AC	CHKD. .	DATE: 4/28/2016	SITE: 48W-185
DRAWN: JJL	CHKD. NK	APPD. JMAC	DWG. A1



PHOTOGRAPHS

**Photograph A-1: Oskondaga River Tributary #1 Culvert
Looking North at Culvert Area (December 2015)**



**Photograph A-2: Oskondaga River Tributary #1 Culvert
Looking South at Culvert (December 2015)**





PHOTOGRAPHS

**Photograph A-3: Oskondaga River Tributary #1 Culvert
Looking East at West Side Inlet (December 2015)**



**Photograph A-4: Oskondaga River Tributary #1 Culvert
Looking West at East Side Outlet (December 2015)**



RECORD OF BOREHOLE No OS1-1

1 OF 3 **METRIC**





PROJECT 1533879
G.W.P. 6943-10-00 LOCATION N 5389962.9; E 312678.1 ORIGINATED BY MA
DIST HWY 17 BOREHOLE TYPE 108 mm I.D. Hollow Stem Augers, NW Casing, NQ Coring COMPILED BY AC
DATUM GEODETIC DATE January 20 and 21, 2016 CHECKED BY NK

SOIL PROFILE			SAMPLES			GROUND WATER CONDITIONS	ELEVATION SCALE	DYNAMIC CONE PENETRATION RESISTANCE PLOT					UNIT WEIGHT γ kN/m ³	REMARKS & GRAIN SIZE DISTRIBUTION (%)
ELEV DEPTH	DESCRIPTION	STRAT PLOT	NUMBER	TYPE	"N" VALUES			20	40	60	80	100		
415.1	GROUND SURFACE													
0.0	ASPHALT (200 mm)						415							
0.2	Gravelly sand, trace silt (FILL) Loose to dense Brown Moist Spoon refusal in Sample 2, no recovery. A 300 mm boulder was encountered at 1.8 m depth. Gravel and cobbles encountered between 2.1 m and 3.7 m depth.		1	SS	46		414							28 66 (6)
			2	SS	105/0.15		413							
			3	SS	101/0.28		412							
			4	SS	16		411							
411.4			5	SS	6		410							
3.7	Clay (FILL) Firm to stiff Reddish Brown Wet		6	SS	3		409							
			7	SS	3		408							
407.9			8	SS	4		407							1 29 42 28
7.2	Sandy CLAYEY SILT, trace to some organics (Rootlets) Firm to very stiff Grey Wet		9	SS	34		406							
406.4			10	SS	100/0.15		405							
8.7	Gravelly SILTY SAND Compact to very dense Grey Wet						404							

Continued Next Page

+³, ×³: Numbers refer to Sensitivity ○³% STRAIN AT FAILURE

SUD-MTO 001 1533879.GPJ GAL-MISS.GDT 28/03/16 DATA INPUT:

PROJECT 1533879		RECORD OF BOREHOLE No OS1-1				2 OF 3 METRIC												
G.W.P. 6943-10-00		LOCATION N 5389962.9; E 312678.1				ORIGINATED BY MA												
DIST _____ HWY 17		BOREHOLE TYPE 108 mm I.D. Hollow Stem Augers, NW Casing, NQ Coring				COMPILED BY AC												
DATUM GEODETIC		DATE January 20 and 21, 2016				CHECKED BY NK												
SOIL PROFILE		SAMPLES			GROUND WATER CONDITIONS	ELEVATION SCALE	DYNAMIC CONE PENETRATION RESISTANCE PLOT					PLASTIC LIMIT W _p	NATURAL MOISTURE CONTENT W	LIQUID LIMIT W _L	UNIT WEIGHT γ kN/m ³	REMARKS & GRAIN SIZE DISTRIBUTION (%) GR SA SI CL		
ELEV DEPTH	DESCRIPTION	STRAT PLOT	NUMBER	TYPE			"N" VALUES	SHEAR STRENGTH kPa										
	--- CONTINUED FROM PREVIOUS PAGE ---						20 40 60 80 100 ○ UNCONFINED + FIELD VANE ● QUICK TRIAXIAL × REMOULDED 20 40 60 80 100					WATER CONTENT (%) 20 40 60						
399.9	Gravelly SILTY SAND Compact to very dense Grey Wet		11	SS	32		403										27 45 27 1	
	Cobbles encountered from 12.8 m to 13.7 m depth.						402											
			12	SS	30		401											
							400											
399.9 15.2	GREYWACKE (BEDROCK) Bedrock cored from 15.2 m depth to 18.3 m depth. For coring details see Record of Drillhole OS1-1.		1	RC	REC 92%		399										RQD = 78%	
			2	RC	REC 100%		398										RQD = 100%	
			3	RC	REC 100%		397										RQD = 100%	
396.8 18.3	END OF BOREHOLE Note: 1. Water level at a depth of 7.7 m below ground surface (Elev. 407.4 m) upon completion of drilling.																	

SUD-MTO 001 1533879.GPJ GAL-MASS.GDT 28/03/16 DATA INPUT:

SHEET 3 OF 3

DATUM: GEODETIC

DRILLING CONTRACTOR: Cartwright Drilling

CHECKED: NK

SUD-RCK 1533879.GPJ GAL-MISS.GDT 28/03/16 DATA INPUT:

RECORD OF BOREHOLE No OS1-2

1 OF 2 **METRIC**

PROJECT 1533879
G.W.P. 6943-10-00 LOCATION N 5389944.7; E 312684.2 ORIGINATED BY MA
DIST HWY 17 BOREHOLE TYPE 108 mm I.D. Hollow Stem Augers, NW Casing and Wash Boring COMPILED BY AC
DATUM GEODETIC DATE January 13, 16, 17, 18 and 19, 2016 CHECKED BY NK

SOIL PROFILE			SAMPLES			GROUND WATER CONDITIONS	ELEVATION SCALE	DYNAMIC CONE PENETRATION RESISTANCE PLOT					UNIT WEIGHT γ kN/m ³	REMARKS & GRAIN SIZE DISTRIBUTION (%)
ELEV DEPTH	DESCRIPTION	STRAT PLOT	NUMBER	TYPE	"N" VALUES			20	40	60	80	100		
415.2	GROUND SURFACE													
0.0	ASPHALT (250 mm)						415							
414.9														
0.3	Sand some gravel to sand and gravel to sand, some gravel, trace to some silt (FILL) Compact Brown Moist to wet		1	AS	-									48 45 (7)
			2	SS	28									
							414							
			3	SS	16									
							413							
			4	SS	27									4 81 (15)
	A 400 mm boulder was encountered at 3.3 m depth.		5	SS			412							
	Gravel recovered in Sample 6.		6	SS	18		411							
			7	SS	11		410							
	A 330 mm boulder was encountered at 5.5 m depth.		8	SS	21		409							
	A 300 mm boulder was encountered at 7 m depth.		9	SS	17		408							
	A 300 mm boulder was encountered at 8.3 m depth.						407							
406.5	Sandy SILTY CLAY, trace gravel, trace organics Stiff to very stiff Grey Wet		10	SS	8		406							
8.7							405							
	Fine silty sand seams noted in Sample 11.		11	SS	18		404							3 31 33 33
403.6														
11.6														


Continued Next Page

+³, ×³: Numbers refer to Sensitivity ○ 3% STRAIN AT FAILURE

SUD-MTO 001 1533879.GPJ GAL-MISS.GDT 28/03/16 DATA INPUT:

PROJECT 1533879		RECORD OF BOREHOLE No OS1-2		2 OF 2 METRIC	
G.W.P. 6943-10-00		LOCATION N 5389944.7; E 312684.2		ORIGINATED BY MA	
DIST _____ HWY 17		BOREHOLE TYPE 108 mm I.D. Hollow Stem Augers, NW Casing and Wash Boring		COMPILED BY AC	
DATUM GEODETIC		DATE January 13, 16, 17, 18 and 19, 2016		CHECKED BY NK	

SOIL PROFILE			SAMPLES			GROUND WATER CONDITIONS	ELEVATION SCALE	DYNAMIC CONE PENETRATION RESISTANCE PLOT					PLASTIC LIMIT NATURAL MOISTURE CONTENT LIQUID LIMIT			UNIT WEIGHT γ kN/m³	REMARKS & GRAIN SIZE DISTRIBUTION (%)				
ELEV DEPTH	DESCRIPTION	STRAT PLOT	NUMBER	TYPE	"N" VALUES			SHEAR STRENGTH kPa					WATER CONTENT (%)				GR	SA	SI	CL	
								○ UNCONFINED + FIELD VANE	● QUICK TRIAXIAL × REMOULDED												
	--- CONTINUED FROM PREVIOUS PAGE ---																				
	Gravelly SILTY SAND, trace clay Compact Grey Wet		12	SS	10																
			13	SS	26								○			23	54				
																21	2				
			14	SS	27																
398.9																					
16.3	END OF BOREHOLE AUGER AND SPLIT SPOON REFUSAL Note: 1. Water level at a depth of 11.6 m below ground surface (Elev. 403.6 m) upon completion of drilling.																				




CLAY AND SILT	GRAVEL SIZE, mm					Cobble Size
	fine	medium	coarse	fine	coarse	
	SAND SIZE			GRAVEL SIZE		

LEGEND

SYMBOL	BOREHOLE	SAMPLE	ELEV (m)
●	OS1-1	1	414.0
■	OS1-2	1	414.7
▲	OS1-2	4	412.6

PROJECT						HIGHWAY 17 OSKONDAGA RIVER TRIBUTARY #1 CULVERT STA 12+939					
TITLE						GRAIN SIZE DISTRIBUTION SAND to SAND and GRAVEL (FILL)					
PROJECT No.			1533879			FILE No.			1533879.GPJ		
DRAWN	TB	Mar 2016	SCALE	N/A	REV.	FIGURE A1					
CHECK	NK	Mar 2016									
APPR	JMAC	Mar 2016									






LEGEND

SYMBOL	BOREHOLE	SAMPLE	LL(%)	PL(%)	PI
●	OS1-1	6	70.0	25.6	44.4

PROJECT		HIGHWAY 17 OSKONDAGA RIVER TRIBUTARY #1 CULVERT STA 12+939			
TITLE		PLASTICITY CHART CLAY (FILL)			
PROJECT No.		1533879		FILE No.	
DRAWN		TB	Mar 2016	SCALE N/A	
CHECK		NK	Mar 2016	REV.	
APPR		JMAC	Mar 2016	FIGURE A2	







GRAIN SIZE, mm						
CLAY AND SILT	fine	medium	coarse	fine	coarse	Cobble Size
	SAND SIZE			GRAVEL SIZE		

LEGEND

SYMBOL	BOREHOLE	SAMPLE	ELEV (m)
●	OS1-1	8	407.2
■	OS1-2	11	404.2

PROJECT						HIGHWAY 17 OSKONDAGA RIVER TRIBUTARY #1 CULVERT STA 12+939					
TITLE						GRAIN SIZE DISTRIBUTION SANDY CLAYEY SILT and SANDY SILTY CLAY					
PROJECT No.			1533879			FILE No.			1533879.GPJ		
DRAWN	TB	Mar 2016	SCALE	N/A	REV.						
CHECK	NK	Mar 2016									
APPR	JMAC	Mar 2016									
 Golder Associates SUDBURY, ONTARIO			FIGURE A3								




LEGEND

SYMBOL	BOREHOLE	SAMPLE	LL(%)	PL(%)	PI
●	OS1-1	8	29.2	16.5	12.7
■	OS1-2	11	41.3	17.8	23.5

PROJECT		HIGHWAY 17 OSKONDAGA RIVER TRIBUTARY #1 CULVERT STA 12+939			
TITLE		PLASTICITY CHART SANDY CLAYEY SILT and SANDY SILTY CLAY			
PROJECT No.		1533879		FILE No. 1533879.GPJ	
DRAWN	TB	Mar 2016		SCALE	N/A
CHECK	NK	Mar 2016		REV.	
APPR	JMAC	Mar 2016		FIGURE A4	






GRAIN SIZE, mm						
CLAY AND SILT	fine	medium	coarse	fine	coarse	Cobble Size
	SAND SIZE			GRAVEL SIZE		


LEGEND


SYMBOL	BOREHOLE	SAMPLE	ELEV (m)
●	OS1-1	11	402.6
■	OS1-2	13	401.2

PROJECT						HIGHWAY 17 OSKONDAGA RIVER TRIBUTARY #1 CULVERT STA 12+939					
TITLE						GRAIN SIZE DISTRIBUTION GRAVELLY SILTY SAND					
PROJECT No.				1533879		FILE No.				1533879.GPJ	
DRAWN	TB	Mar 2016		SCALE	N/A	REV.					
CHECK	NK	Mar 2016									
APPR	JMAC	Mar 2016									
 Golder Associates SUDBURY, ONTARIO				FIGURE A5							



Borehole OS1-1
Elevation 399.9 m to 396.8 m






PROJECT		HIGHWAY 17 OSKONDAGA RIVER TRIBUTARY #1 CULVERT STA 12+939			
TITLE		BEDROCK CORE PHOTOGRAPH			
		PROJECT No. 1533879		FILE No. ----	
		DESIGN	SN	Feb. 2016	SCALE AS SHOWN
		CADD	--		REV.
		CHECK	NK	Feb. 2016	FIGURE A6
		REVIEW	JMAC	Feb. 2016	



APPENDIX B

Oskondaga River Tributary #2 Culvert, Site No. 48W-186/C (Soper Township)




METRIC
DIMENSIONS ARE IN METRES AND/OR
MILLIMETRES UNLESS OTHERWISE SHOWN.
STATIONS IN KILOMETRES + METRES.

CONT No.
GWP No.6943-10-00

HIGHWAY 17
OSKONDAGA RIVER TRIBUTARY #2 CULVERT
STA 13+458
BOREHOLE LOCATIONS AND
SOIL STRATA

SHEET



LEGEND

- Borehole - Current Investigation
- N Standard Penetration Test Value
- 16 Blows/0.3m unless otherwise stated (Std. Pen. Test, 475 j/blow)
- R Refusal
- WL upon completion of drilling

BOREHOLE CO-ORDINATES			
No.	ELEVATION	NORTHING	EASTING
OS2-1	427.6	5399145.9	313353.1
OS2-2	427.6	5399133.0	313350.6
OS2-3	432.4	5399151.9	313330.0
OS2-4	432.4	5399132.4	313332.6
OS2-5	427.4	5399151.9	313311.7
OS2-6	427.5	5399136.5	313311.1

NOTES


This drawing is for subsurface information only. The proposed structure details/works are shown for illustration purposes only and may not be consistent with the final design configuration as shown elsewhere in the Contracts Documents.

The boundaries between soil strata have been established only at borehole locations. Between boreholes the boundaries are assumed from geological evidence.

The complete Foundation Investigation and Design Report for this project and other related documents may be examined at the Materials Engineering and Research Office, Downsview. Information contained in this report and related documents is specifically excluded in accordance with Section GC 2.01 of OPS General Conditions.

REFERENCE

Base plans provided in digital format by MTO, drawing file nos. E1038171 received Dec. 11, 2015.



NO.	DATE	BY	REVISION
Geocres No. 52A-220			
HWY. 17	PROJECT NO. 1533879		DIST. .
SUBM'D. AC	CHKD. .	DATE: 4/28/2016	SITE: 48W-186
DRAWN: JJL	CHKD. NK	APPD. JMAC	DWG. B1



PHOTOGRAPHS

**Photograph B-1: Oskondaga River Tributary #2 Culvert
Looking North at Culvert (December 2015)**



**Photograph B-2: Oskondaga River Tributary #2 Culvert
Looking South at Culvert (December 2015)**





PHOTOGRAPHS

**Photograph B-3: Oskondaga River Tributary #2 Culvert
Looking West at East Side Inlet (December 2015)**



**Photograph B-4: Oskondaga River Tributary #2 Culvert
Looking East at West Side Outlet (December 2015)**



PROJECT 1533879		RECORD OF BOREHOLE No OS2-1				1 OF 1 METRIC											
G.W.P. 6943-10-00		LOCATION N 5399145.9; E 313353.1				ORIGINATED BY MR											
DIST _____ HWY 17		BOREHOLE TYPE 108 mm I.D. Hollow Stem Augers				COMPILED BY AC											
DATUM GEODETIC		DATE January 14, 2016				CHECKED BY NK											
SOIL PROFILE			SAMPLES			GROUND WATER CONDITIONS	ELEVATION SCALE	DYNAMIC CONE PENETRATION RESISTANCE PLOT					PLASTIC LIMIT W _p	NATURAL MOISTURE CONTENT W	LIQUID LIMIT W _L	UNIT WEIGHT γ	REMARKS & GRAIN SIZE DISTRIBUTION (%)
ELEV DEPTH	DESCRIPTION	STRAT PLOT	NUMBER	TYPE	"N" VALUES			SHEAR STRENGTH kPa									
427.6	GROUND SURFACE							20	40	60	80	100					
0.0	SILTY CLAY, trace sand, trace organics Firm Brown - grey Frozen* to wet		1	AS	-*												
			2	SS	3*												
			3	SS	4												
425.4																	
2.2	CLAY Stiff Reddish Brown Wet		4	SS	WH												
			5	SS	WH												
422.3																	
5.3	SAND, some gravel Dense Grey Wet																
			6	SS	37/0.23												
421.1																	
6.5	Gravelly SILT and SAND (TILL) Augers grinding from 6.5 m to 7.4 m depth.																
420.2																	
7.4	END OF BOREHOLE AUGER AND SPLIT-SPOON REFUSAL Note: 1. Water level at a depth of 0.4 m below ground surface (Elev. 427.2 m) upon completion of drilling.																

SUD-MTO 001 1533879.GPJ GAL-MISS.GDT 28/03/16 DATA INPUT:

+³, ×³: Numbers refer to Sensitivity ○ 3% STRAIN AT FAILURE

PROJECT 1533879		RECORD OF BOREHOLE No OS2-2				1 OF 1 METRIC								
G.W.P. 6943-10-00		LOCATION N 5399133.0; E 313350.6		ORIGINATED BY RA										
DIST _____ HWY 17		BOREHOLE TYPE Portable Equipment		COMPILED BY AC										
DATUM GEODETIC		DATE December 12 and 13, 2015		CHECKED BY NK										
SOIL PROFILE			SAMPLES			GROUND WATER CONDITIONS	ELEVATION SCALE	DYNAMIC CONE PENETRATION RESISTANCE PLOT		PLASTIC LIMIT W _p	NATURAL MOISTURE CONTENT W	LIQUID LIMIT W _L	UNIT WEIGHT γ	REMARKS & GRAIN SIZE DISTRIBUTION (%)
ELEV DEPTH	DESCRIPTION	STRAT PLOT	NUMBER	TYPE	"N" VALUES			SHEAR STRENGTH kPa						
427.6	GROUND SURFACE													
0.0	Silty TOPSOIL, trace sand Brown to black Moist		1	AS	-									
426.8														
0.8	ORGANIC SILT, trace to some sand, trace to some gravel Firm Black Wet		2	SS	5									
426.1														
1.5	CLAY, trace sand Stiff Reddish brown Wet		3	SS	10									
			4	SS	9									
			5	SS	10									
			6	SS	10									
			7	SS	12									
422.9														
4.7	SILT, trace clay Compact Grey Wet		8	SS	24									
422.3														
5.3	Sandy GRAVEL Dense Grey Wet		9	SS	38									
421.7														
5.9	END OF BOREHOLE START OF DCPT													
420.1														
7.5	END OF DCPT REFUSAL TO FURTHER PENETRATION (HAMMER BOUNCING)													
	Note: 1. Water level at a depth of 0.4 m below ground surface (Elev. 427.2 m) upon completion of drilling. 2. Split Spoon samples obtained by driving with a 1/2 weight hammer. SPT 'N' values have been adjusted to the inferred values that would be obtained using a standard weight hammer.													

SUD-MTO 001 1533879.GPJ GAL-MISS.GDT 28/03/16 DATA INPUT:

PROJECT 1533879		RECORD OF BOREHOLE No OS2-3		1 OF 2 METRIC	
G.W.P. 6943-10-00		LOCATION N 5399151.9; E 313330.0		ORIGINATED BY MR	
DIST _____ HWY 17		BOREHOLE TYPE NW Casing, NQ Coring and Wash Boring		COMPILED BY AC	
DATUM GEODETIC		DATE December 15, 2015		CHECKED BY NK	

SOIL PROFILE			SAMPLES			GROUND WATER CONDITIONS	ELEVATION SCALE	DYNAMIC CONE PENETRATION RESISTANCE PLOT					PLASTIC LIMIT NATURAL MOISTURE CONTENT LIQUID LIMIT			UNIT WEIGHT γ kN/m ³	REMARKS & GRAIN SIZE DISTRIBUTION (%)			
ELEV DEPTH	DESCRIPTION	STRAT PLOT	NUMBER	TYPE	"N" VALUES			SHEAR STRENGTH kPa					WATER CONTENT (%)				GR	SA	SI	CL
								20	40	60	80	100	w _p	w	w _L					
432.4	GROUND SURFACE																			
0.0	ASPHALT (250 mm)																			
432.1																				
0.3	Sand and gravel, trace to some silt (FILL) Compact Brown Frozen* to moist		1	AS	-*															
			2	AS	-															
			3A	SS	22															
430.3			3B																	
2.1	Silty clay (FILL) Firm Reddish brown Wet		4	SS	4															
429.0			5	SS	7															
3.4	Clayey silt, trace organics (FILL) Firm Brown to grey Wet		6	SS	6															
			7	SS	6															
426.8																				
5.6	CLAYEY SILT, trace organics Firm Grey Wet		8A																	
426.1			8B	SS	6															
6.3	CLAY, trace sand Firm to stiff Reddish brown Wet																			
			9	SS	2															
423.6																				
8.8	SAND and GRAVEL, trace silt Compact Grey Wet		10	SS	15															
422.2																				
10.2	SILT and SAND, trace to some gravel, trace to some clay (TILL) Very dense Grey Wet Cobbles ranging from 60 mm to 230 mm diameter were encountered between 11.0 and 12.5 m depths.		11	SS	60															

Continued Next Page



+³, ×³: Numbers refer to Sensitivity ○ 3% STRAIN AT FAILURE

SUD-MTO 001 1533879.GPJ GAL-MISS.GDT 28/03/16 DATA INPUT:

PROJECT 1533879		RECORD OF BOREHOLE No OS2-3				2 OF 2 METRIC							
G.W.P. 6943-10-00		LOCATION N 5399151.9; E 313330.0				ORIGINATED BY MR							
DIST _____ HWY 17		BOREHOLE TYPE NW Casing, NQ Coring and Wash Boring				COMPILED BY AC							
DATUM GEODETIC		DATE December 15, 2015				CHECKED BY NK							
SOIL PROFILE			SAMPLES			DYNAMIC CONE PENETRATION RESISTANCE PLOT		PLASTIC LIMIT NATURAL MOISTURE CONTENT LIQUID LIMIT		UNIT WEIGHT		REMARKS & GRAIN SIZE DISTRIBUTION (%)	
ELEV DEPTH	DESCRIPTION	STRAT PLOT	NUMBER	TYPE	"N" VALUES	GROUND WATER CONDITIONS	ELEVATION SCALE	SHEAR STRENGTH kPa		WATER CONTENT (%)		γ kN/m³	GR SA SI CL
							20 40 60 80 100	○ UNCONFINED + FIELD VANE ● QUICK TRIAXIAL × REMOULDED	W _p W W _L	20 40 60			
	--- CONTINUED FROM PREVIOUS PAGE ---												
	SILT and SAND, trace to some gravel, trace to some clay (TILL) Very dense Grey Wet		12	SS	63/0.13		420						
							419						
			13	SS	65/0.08		418						
							417						
416.7 15.7	END OF BOREHOLE Note: 1. Water level at a depth of 3.8 m below ground surface (Elev. 428.6 m) upon completion of drilling.		14	SS	115/0.28								9 41 40 10

[illegible]


+³, ×³: Numbers refer to Sensitivity ○^{3%} STRAIN AT FAILURE

PROJECT 1533879		RECORD OF BOREHOLE No OS2-5				1 OF 1 METRIC								
G.W.P. 6943-10-00		LOCATION N 5399151.9; E 313311.7				ORIGINATED BY MR								
DIST _____ HWY 17		BOREHOLE TYPE 78 mm I.D. Continuous Flight Hollow Stem Augers				COMPILED BY AC								
DATUM GEODETIC		DATE December 13 and 14, 2015				CHECKED BY NK								
SOIL PROFILE			SAMPLES			GROUND WATER CONDITIONS	ELEVATION SCALE	DYNAMIC CONE PENETRATION RESISTANCE PLOT		PLASTIC NATURAL LIQUID LIMIT MOISTURE CONTENT LIMIT			UNIT WEIGHT γ kN/m ³	REMARKS & GRAIN SIZE DISTRIBUTION (%) GR SA SI CL
ELEV DEPTH	DESCRIPTION	STRAT PLOT	NUMBER	TYPE	"N" VALUES			SHEAR STRENGTH kPa		WATER CONTENT (%)				
427.4 0.0	GROUND SURFACE SILTY CLAY, trace to some organics Soft Brown to grey Wet		1	SS	2		20 40 60 80 100			20 40 60			26 35 32 7	
			2	SS	3									
426.0 1.4	CLAY Firm Reddish brown Wet		3	SS	4									
424.5 2.9	SAND, trace to some gravel Compact Brown Wet	4	SS	41										
423.7 3.7	Gravelly SILT and SAND, trace to some clay (TILL) Compact to very dense Grey Wet	5	SS	18										
		6	SS	37										
		7	SS	41										
		8	SS	62/0.08										
		9	SS	60/0.15										
418.1 9.3	BOULDER													
417.7 9.7	END OF BOREHOLE Note: 1. Water level at ground surface (Elev. 427.4 m) upon completion of drilling.													

SUD-MTO 001 1533879.GPJ GAL-MISS.GDT 28/03/16 DATA INPUT:


PROJECT 1533879		RECORD OF BOREHOLE No OS2-6				1 OF 1 METRIC										
G.W.P. 6943-10-00		LOCATION N 5399136.5; E 313311.1				ORIGINATED BY MR										
DIST _____ HWY 17		BOREHOLE TYPE Solid Stem Augers, NW Casing, NQ Coring and Wash Boring				COMPILED BY AC										
DATUM GEODETIC		DATE December 19, 2015				CHECKED BY NK										
SOIL PROFILE			SAMPLES			GROUND WATER CONDITIONS	ELEVATION SCALE	DYNAMIC CONE PENETRATION RESISTANCE PLOT				PLASTIC LIMIT W _p	NATURAL MOISTURE CONTENT W	LIQUID LIMIT W _L	UNIT WEIGHT γ	REMARKS & GRAIN SIZE DISTRIBUTION (%)
ELEV DEPTH	DESCRIPTION	STRAT PLOT	NUMBER	TYPE	"N" VALUES			SHEAR STRENGTH kPa								
427.5	GROUND SURFACE															
0.0	Sandy TOPSOIL Loose Brown to black Frozen* to wet		1	SS	14*											
			2	SS	4											
426.1																
1.4	ORGANIC SILT Soft Dark brown Wet		3	SS	2											
425.3																
2.2	CLAY Firm Reddish brown Wet		4	SS	4											
424.2																
3.3	SAND and GRAVEL, trace to some silt Loose to compact Grey Wet		5	SS	9											
			6	SS	14											
423.0																
4.5	Gravelly SILT and SAND to SAND and GRAVEL (TILL) Compact to very dense Grey Wet		7	SS	13											
421.9																
5.6	SAND and GRAVEL, trace silt Very dense Grey WET		8	SS	112/0.23											
420.5																
7.0	Gravelly SILT and SAND (TILL) Very dense Grey Wet Cobbles ranging from 120 mm to 250 mm diameter encountered between 7.0 m and 9.1 m depth.		9	SS	100/0.13											
418.2																
9.3	END OF BOREHOLE Note: 1. Water level at a depth of 0.1 m below ground surface (Elev. 427.4 m) upon completion of drilling.		10	SS	100/0.1											

SUD-MTO 001 1533879.GPJ GAL-MISS.GDT 28/03/16 DATA INPUT:




CLAY AND SILT	fine	medium	coarse	fine	coarse	Cobble Size
	SAND SIZE			GRAVEL SIZE		

LEGEND			
SYMBOL	BOREHOLE	SAMPLE	ELEV (m)
●	OS2-3	3A	430.6
■	OS2-4	2	431.3

PROJECT					HIGHWAY 17 OSKONDAGA RIVER TRIBUTARY #2 CULVERT STA 13+458				
TITLE					GRAIN SIZE DISTRIBUTION SAND to SAND and GRAVEL (FILL)				
 Golder Associates SUDBURY, ONTARIO		PROJECT No.		1533879		FILE No.		1533879.GPJ	
		DRAWN	JJL	Mar 2016		SCALE	N/A	REV.	
		CHECK	NK	Mar 2016		FIGURE B1			
		APPR	JMAC	Mar 2016					

SUD-MTO GSD (2016) GLDR_LDN.GDT




CLAY AND SILT	GRAVEL SIZE, mm					Cobble Size
	fine	medium	coarse	fine	coarse	
	SAND SIZE			GRAVEL SIZE		

LEGEND

SYMBOL	BOREHOLE	SAMPLE	ELEV (m)
●	OS2-3	6	428.3


PROJECT		HIGHWAY 17 OSKONDAGA RIVER TRIBUTARY #2 CULVERT STA 13+458			
TITLE		GRAIN SIZE DISTRIBUTION CLAYEY SILT (FILL)			
PROJECT No.		1533879		FILE No. 1533879.GPJ	
DRAWN	JJL	Mar 2016	SCALE	N/A	REV.
CHECK	NK	Mar 2016	FIGURE B2		
APPR	JMAC	Mar 2016			






LEGEND


SYMBOL	BOREHOLE	SAMPLE	LL(%)	PL(%)	PI
●	OS2-3	6	31.4	22.1	9.3


PROJECT		HIGHWAY 17 OSKONDAGA RIVER TRIBUTARY #2 CULVERT STA 13+458			
TITLE		PLASTICITY CHART CLAYEY SILT (FILL)			
PROJECT No.		1533879		FILE No. 1533879.GPJ	
DRAWN	JJL	Mar 2016	SCALE	N/A	REV.
CHECK	NK	Mar 2016			
APPR	JMAC	Mar 2016			
 Golder Associates SUDBURY, ONTARIO			FIGURE B3		



LEGEND


SYMBOL	BOREHOLE	SAMPLE	LL(%)	PL(%)	PI
●	OS2-6	3	92.1	43.8	48.3


PROJECT		HIGHWAY 17 OSKONDAGA RIVER TRIBUTARY #2 CULVERT STA 13+458			
TITLE		PLASTICITY CHART ORGANIC SILT			
PROJECT No.		1533879		FILE No. 1533879.GPJ	
DRAWN	JJL	Mar 2016	SCALE	N/A	REV.
CHECK	NK	Mar 2016			
APPR	JMAC	Mar 2016			
 Golder Associates SUDBURY, ONTARIO			FIGURE B4		




LEGEND


SYMBOL	BOREHOLE	SAMPLE	LL(%)	PL(%)	PI
●	OS2-1	3	42.6	22.9	19.7
■	OS2-1	4	93.0	26.5	66.5
▲	OS2-2	4	87.5	26.8	60.7
+	OS2-2	5	84.0	27.1	56.9
◆	OS2-2	7	83.8	28.1	55.7
◇	OS2-3	8B	57.6	22.3	35.3
○	OS2-4	9	88.3	31.7	56.6
△	OS2-5	1	48.4	26.1	22.3
⊗	OS2-5	3	80.0	27.2	52.8
⊕	OS2-6	4	84.5	30.4	54.1

PROJECT		HIGHWAY 17 OSKONDAGA RIVER TRIBUTARY #2 CULVERT STA 13+458		
TITLE		PLASTICITY CHART SILTY CLAY to CLAY		
PROJECT No. 1533879		FILE No. 1533879.GPJ		
DRAWN	JJL	Mar 2016	SCALE	N/A
CHECK	NK	Mar 2016	REV.	
APPR	JMAC	Mar 2016		
 Golder Associates SUDBURY, ONTARIO		FIGURE B5		




LEGEND			
SYMBOL	BOREHOLE	SAMPLE	ELEV (m)
●	OS2-1	4	425.0
■	OS2-2	7	423.2
▲	OS2-4	9	424.5
+	OS2-6	4	424.9


PROJECT						HIGHWAY 17 OSKONDAGA RIVER TRIBUTARY #2 CULVERT STA 13+458					
TITLE						GRAIN SIZE DISTRIBUTION CLAY					
PROJECT No.				1533879		FILE No.				1533879.GPJ	
DRAWN		J.J.L.		Mar 2016		SCALE		N/A		REV.	
CHECK		NK		Mar 2016							
APPR		JMAC		Mar 2016							
 Golder Associates SUDBURY, ONTARIO						FIGURE B6					



LEGEND


SYMBOL	BOREHOLE	SAMPLE	ELEV (m)
●	OS2-1	6	421.4
■	OS2-3	10	423.0
▲	OS2-6	6	423.4
+	OS2-6	8	421.2

PROJECT						HIGHWAY 17 OSKONDAGA RIVER TRIBUTARY #2 CULVERT STA 13+458					
TITLE						GRAIN SIZE DISTRIBUTION SAND to SAND and GRAVEL					
PROJECT No.				1533879		FILE No.				1533879.GPJ	
DRAWN		JUL		Apr 2016		SCALE		N/A		REV.	
CHECK		NK		Apr 2016							
APPR		JMAC		Apr 2016							
 Golder Associates SUDBURY, ONTARIO						FIGURE B7					



LEGEND

SYMBOL	BOREHOLE	SAMPLE	ELEV (m)
●	OS2-3	14	416.9
■	OS2-5	6	422.5

PROJECT						HIGHWAY 17 OSKONDAGA RIVER TRIBUTARY #2 CULVERT STA 13+458					
TITLE						GRAIN SIZE DISTRIBUTION GRAVELLY SILT and SAND to SAND and GRAVEL (TILL)					
PROJECT No.				1533879		FILE No.				1533879.GPJ	
DRAWN		JJL		Apr 2016		SCALE		N/A		REV.	
CHECK		NK		Apr 2016							
APPR		JMAC		Apr 2016							
 Golder Associates SUDBURY, ONTARIO						FIGURE B8					

At Golder Associates we strive to be the most respected global company providing consulting, design, and construction services in earth, environment, and related areas of energy. Employee owned since our formation in 1960, our focus, unique culture and operating environment offer opportunities and the freedom to excel, which attracts the leading specialists in our fields. Golder professionals take the time to build an understanding of client needs and of the specific environments in which they operate. We continue to expand our technical capabilities and have experienced steady growth with employees who operate from offices located throughout Africa, Asia, Australasia, Europe, North America, and South America.

Africa	+ 27 11 254 4800
Asia	+ 86 21 6258 5522
Australasia	+ 61 3 8862 3500
Europe	+ 356 21 42 30 20
North America	+ 1 800 275 3281
South America	+ 55 21 3095 9500

solutions@golder.com
www.golder.com

Golder Associates Ltd.
33 MacKenzie Street
Sudbury, Ontario, P3C 4Y1
Canada
T: +1 (705) 524 6861

