

## Foundation Investigation Report

*Sign Supports, High Mast Light and Closed Circuit Television (CCTV) Poles  
Highway 410, Eglinton Avenue to Mayfield Road - Contract 2*

*Mississauga and Brampton, Ontario*

*Assignment No. 2016-E-0040, G.W.P. 2369-15-00*

Submitted to:

**AECOM**

30 Leek Crescent, 4th Floor  
Richmond Hill, Ontario  
L4B 4N4

Submitted by:

**Golder Associates Ltd.**

6925 Century Avenue, Suite #100, Mississauga, Ontario, L5N 7K2, Canada  
+1 905 567 4444

**GEOCRES No.: 30M12-445**

Lat. 43.663616°, Long. -79.693213°

1669996-2-5

May 9, 2019



## Distribution List

3 Hard Copies, 1 E-Copy - MTO Central Region

1 Hard Copy, 1 E-Copy - MTO Foundations Section

1 E-Copy - AECOM

1 E-Copy - Golder Associates Ltd.

# Table of Contents

<b>1.0 INTRODUCTION</b>	<b>1</b>
<b>2.0 SITE DESCRIPTION</b>	<b>1</b>
<b>3.0 INVESTIGATION PROCEDURES</b>	<b>1</b>
3.1 1976 Investigation	1
3.2 2012 Investigation	2
3.3 2019 Investigation	2
<b>4.0 SITE GEOLOGY AND SUBSURFACE CONDITIONS</b>	<b>4</b>
4.1 Regional Geology	4
4.2 Subsurface Conditions	5
4.2.1 Topsoil	5
4.2.2 Asphalt	5
4.2.3 Fill	5
4.2.4 Silt to Gravelly Silty Sand	7
4.2.5 Clayey Silt	7
4.2.6 Clayey Silt Till to Silt and Sand Till	8
4.2.7 Residual Soil and Shale Bedrock	9
4.3 Groundwater Conditions	9
4.4 Analytical Testing Results	10
<b>5.0 CLOSURE</b>	<b>11</b>

## DRAWINGS

Drawing 1	Borehole Locations
Drawing 2	Borehole Locations

## APPENDICES

### APPENDIX A – Borehole Records and Laboratory Testing from 1976 and 2012 Investigations (GEOCRE No. 30M12-122 and 30M12-361)

Records of Borehole Nos. 122-3(2), C4-1

Laboratory Testing from 2012 Investigation (Borehole C4-1)

### APPENDIX B – Borehole Records from 2019 Investigation

Lists of Symbols and Abbreviations

Records of Borehole Nos. CCTV-1, CCTV-3 to CCTV-6, HML-1, OH-1 to OH-6, VMS-1 and VMS-2

### APPENDIX C – Geotechnical Laboratory Test Results from 2019 Investigation

Figure C-1	Grain Size Distribution – Gravelly Sandy Silty Clay Fill
Figure C-2	Plasticity Chart – Gravelly Sandy Silty Clay Fill
Figure C-3	Grain Size Distribution – Silt
Figure C-4	Grain Size Distribution – Clayey Silt
Figure C-5	Plasticity Chart – Clayey Silt
Figure C-6A	Grain Size Distribution – Clayey Silt to Clayey Silt with Sand Till
Figure C-6B	Grain Size Distribution – Silty Clay to Clayey Silt with Sand Till
Figure C-6C	Grain Size Distribution – Clayey Silt to Clayey Silt with Sand Till
Figure C-6D	Grain Size Distribution – Clayey Silt Till to Silt and Sand Till
Figure C-7A	Plasticity Chart – Clayey Silt to Clayey Silt with Sand Till
Figure C-7B	Plasticity Chart – Silty Clay to Clayey Silt with Sand Till
Figure C-7C	Plasticity Chart – Sandy Clayey Silt to Clayey Silt with Sand Till

### APPENDIX D – Analytical Chemical Test Results

## 1.0 INTRODUCTION

Golder Associates Ltd. (Golder) has been retained by AECOM on behalf of the Ministry of Transportation, Ontario (MTO) to provide foundation engineering services for the detailed design of the rehabilitation of Highway 410 from Eglinton Avenue to Mayfield Road in the Cities of Mississauga and Brampton, Ontario (MTO Agreement No. 2016-E-0040).

This report addresses the foundation investigation carried out for the proposed overhead and variable message sign supports, high mast light (HML) and closed circuit television (CCTV) poles for the section of Highway 410 extending from approximately Highway 401 to Queen Street East, as shown on the key plan on Drawings 1 and 2. This report was developed based on information from the 2019 (current) investigation, supplemented with information from 1976 and 2012 (previous) foundation investigations, reported as follows:

- **MTO GEOCRES No. 30M12-122:** “Foundation Investigation and Design Report, From Steeles Avenue Southerly to Derry Road Culverts, W.P. 103-69-08, Highway 410, District 6, Toronto,” by Ministry of Transportation, dated December 21, 1976.
- **MTO GEOCRES No. 30M12-361:** “Foundation Investigation Report for Culvert Extensions and Replacement, Highway 410 Widening From South of Highway 401 to Queen Street, Regional Municipality of Peel, G.W.P. 2144-07-00(i)” by Golder Associates, dated March 2013.

The Terms of Reference and Scope of Work for the foundation engineering services are outlined in MTO’s Request for Proposal, dated November 25, 2016, which forms part of the Consultant Agreement (No. 2016-E-0040) for this project. The Scope of Work for the overhead and variable message sign supports, HML and CCTV poles is outlined in Golder’s Change Request dated February 15, 2018. The work has been carried out in accordance with Golder’s Supplementary Specialty Plan for this project, dated May 2017.

## 2.0 SITE DESCRIPTION

The proposed sign supports, HML and CCTV poles are located within the Highway 410 corridor from approximately 630 m south of the Courtneypark Drive underpass, to approximately 30 m north of the Queen Street East underpass in the Cities of Mississauga and Brampton, respectively, within the Regional Municipality of Peel. The natural ground surface in the Highway 410 corridor rises from approximately Elevation 184 m near the south limit, to about Elevation 216 m near the north limit.

Highway 410 has generally been constructed on embankment fill, with the embankment height varying from less than 1 m to 2 m, to on the order of 6 m to 8 m adjacent to overpass structures. Highway 410 has been constructed in a cut in the vicinity of the Steeles Avenue overpass structure, extending northward to beyond the Queen Street East underpass.

## 3.0 INVESTIGATION PROCEDURES

### 3.1 1976 Investigation

One borehole from the 1976 investigation (designated as Borehole 3(2)) was advanced approximately 1 km north of the Highway 407 overpass as part of a culvert investigation (GEOCRES No. 30M12-122). The 1976 borehole has been renamed to show the MTO GEOCRES reference number followed by the original borehole designation.

The borehole record from the investigation (referenced herein as Borehole 122-3(2)) is presented in Appendix A. The borehole was advanced at the location shown on Drawing 1; this location has been developed based on plotting the station and offset as shown on the 1976 borehole records and drawings, adjusting based on the site features shown on the drawings and converting these to geographic coordinates based on MTM NAD83 (Zone 10). The borehole location, ground surface elevation (referenced to geodetic datum), and drilled depth are summarized below.

Borehole No.	MTM NAD 83 (Zone 10)		Borehole Elevation (m)	Borehole Depth (m)
	Northing (m)	Easting (m)		
122-3(2)	4,837,513.3	288,255.4	192.0	8.1

The Standard Penetration Test (SPT) “N” values in the 1976 investigation were obtained using a manual hammer, consisting of a 63.5 kg (140 pound) hammer falling over a distance of 760 mm (30 inches).

Geotechnical laboratory index and classification testing, consisting of water content, grain size distributions and Atterberg limits, was conducted on selected samples as part of the 1976 investigation. The test results are presented on the borehole record contained in Appendix A.

### 3.2 2012 Investigation

One borehole from the 2012 investigation (designated as Borehole C4-1) was advanced approximately 300 m north of the Courtenypark Drive underpass as part of a culvert rehabilitation investigation (GEOCRE No. 30M12-361). The borehole record from the 2012 investigation is presented in Appendix A. The borehole was advanced at the location shown on Drawing 2. The borehole location and ground surface elevation (referenced to geodetic datum) were obtained from the original borehole record, as summarized below.

Borehole No.	MTM NAD 83 (Zone 10)		Borehole Elevation (m)	Borehole Depth (m)
	Northing (m)	Easting (m)		
C4-1	4,834,903.6	290,226.0	185.1	10.9

Geotechnical laboratory index and classification testing, consisting of water content, grain size distributions and Atterberg limits was conducted on selected samples as part of the 2012 investigation. The grain size distribution and Atterberg limits test results from this investigation are presented in Appendix A.

### 3.3 2019 Investigation

The 2019 foundation investigation for the sign supports, HML and CCTV poles was carried out between March 5 and March 25, 2019, during which time 14 boreholes (designated as Boreholes CCTV1, CCTV-3 to CCTV-6, HML-1, OH-1 to OH-6, VMS-1 and VMS-2) were advanced near the proposed foundation elements, as shown on Drawings 1 and 2. The borehole records are contained in Appendix B.

The borehole investigation was carried out using a CME-55 track-mounted drill rig, supplied and operated by Geo-Environmental Drilling Inc. of Halton Hills, Ontario. The boreholes were advanced through the overburden using

152 mm or 203 mm outside diameter hollow stem augers. Soil samples were obtained at 0.75 m and 1.5 m intervals of depth using a 50 mm outer diameter split-spoon sampler driven by an automatic hammer in accordance with Standard Penetration Test (SPT) procedures (ASTM D1586)<sup>1</sup>. Considering the inside diameter of the split-spoon samplers, soil particles larger than 35 mm cannot be retrieved. The results of the in-situ field tests (i.e., SPT “N”-values) as presented on the borehole records and in Section 4.0 are uncorrected.

The groundwater conditions in the open boreholes were observed during and immediately following the drilling operations. The boreholes were backfilled to ground surface with bentonite, in accordance with Ontario Regulation 903 (Wells, as amended), and the boreholes advanced through asphalt were sealed at ground surface with cold patch asphalt.

The field work was monitored on a full-time basis by a member of Golder’s technical staff who located the boreholes in the field, directed the sampling and in situ testing operations, logged the boreholes and examined the soil samples. The soil samples were identified in the field, placed in labelled containers and transported to Golder’s laboratory in Mississauga for further visual review. Geotechnical laboratory index and classification testing, consisting of natural moisture contents, grain size distributions and Atterberg limits, was conducted on selected samples in accordance with MTO and / or ASTM Standards, as applicable. The geotechnical laboratory results are presented in Appendix C.

Seven selected soil samples, obtained using appropriate sampling protocols, were submitted to a specialist analytical laboratory under chain of custody procedures for testing of conductivity / resistivity, pH and chemical analysis of sulphate and chloride content, to assess the potential for the soil to cause deterioration to buried concrete and corrosion to steel. The analytical laboratory results are presented in Appendix D.

The as-drilled borehole locations were surveyed by Callon Dietz, Ontario Land Surveyors, or by Golder personnel using a handheld GPS device to a horizontal accuracy of 0.1 m and a vertical accuracy of 0.1 m. The locations provided on the borehole records and shown on Drawings 1 and 2 are positioned relative to MTM NAD 83 (Zone 10) coordinates and the ground surface elevations are referenced to geodetic datum. The borehole locations (including in geographic coordinates of latitude and longitude), ground surface elevations, and drilled depths are summarized below.

Borehole No.	MTM NAD83 (Zone 10)		Ground Surface Elevation (m)	Borehole Depth (m)
	Northing (m) (Latitude,°)	Easting (m) (Longitude,°)		
CCTV-1	4,840,702.0 (43.706029)	285,577.9 (-79.738523)	216.2	7.8
CCTV-3	4,836,539.6 (43.668635)	288,731.1 (-79.699269)	194.6	6.5
CCTV-4	4,835,152.1 (43.656178)	290,066.5 (-79.682667)	185.1	8.2
CCTV-5	4,834,657.9 (43.651737)	290,565.8 (-79.676462)	185.2	8.2

<sup>1</sup> ASTM D1586 – Standard Test Method for Standard Penetration Tests and Split Barrel Sampling of Soils.

Borehole No.	MTM NAD83 (Zone 10)		Ground Surface Elevation (m)	Borehole Depth (m)
	Northing (m) (Latitude,°)	Easting (m) (Longitude,°)		
CCTV-6	4,834,246.7 (43.648042)	290,957.8 (-79.671594 )	184.0	7.8
HML-1	4,834,776.0 (43.652794)	290,272.9 (-79.680096)	185.5	8.2
OH-1	4,836,154.2 (43.665173)	288,961.7 (-79.696392)	189.3	7.6
OH-2	4,835,887.2 (43.662774)	289,161.2 (-79.693910)	188.3	7.7
OH-3	4,835,459.0 (43.658930)	289,662.0 (-79.687689)	185.7	8.2
OH-4	4,835,139.5 (43.656061)	290,000.4 (-79.683485)	185.0	8.1
OH-5	4,834,600.2 (43.651211)	290,262.0 (-79.680227)	187.9	7.5
OH-6	4,834,615.7 (43.651351)	290,287.5 (-79.679911)	192.7	8.2
VMS-1	4,838,493.1 (43.686192)	287,654.8 (-79.712675)	196.4	8.0
VMS-2	4,834,872.8 (43.653668)	290,337.4 (-79.679306)	186.3	8.2

## 4.0 SITE GEOLOGY AND SUBSURFACE CONDITIONS

### 4.1 Regional Geology

This section of Highway 410 is located within the physiographic region known as the South Slope, according to *The Physiography of Southern Ontario* (Chapman and Putnam, 1984)<sup>2</sup>.

The South Slope region is comprised of calcareous clay till with lacustrine clay and silt reworked by glaciers, with numerous scattered drumlins and deep valley cuts caused by streams flowing towards Lake Ontario. The surface topography slopes gradually and uniformly southwards towards Lake Ontario. The overburden within the majority of the South Slope area is underlain by shale bedrock of the Queenston and Georgian Bay Formations, which contain limestone interlayers.

<sup>2</sup> Chapman, L.J. and Putman, D.F., 1984, *The Physiography of Southern Ontario*, Ontario Geological Society, Special Volume 2, Third Edition. Accompanied by Map p. 2715, Scale 1:600,000.)



## 4.2 Subsurface Conditions

The detailed subsurface soil and groundwater conditions as encountered in the boreholes advanced during the 1976 and 2012 investigations, and the 2019 investigation, are presented on the borehole records in Appendices A and B, respectively. The results of the geotechnical laboratory tests carried out as part of the 2019 investigation are presented in Appendices C. The results of the analytical laboratory tests carried out as part of 2019 investigation are presented in Appendix D.

The results of the in situ field tests (i.e., SPT “N”-values) as presented on the borehole records and in Section 4.2 are uncorrected. The stratigraphic boundaries shown on the borehole records are inferred from non-continuous sampling, observations of drilling progress and the results of Standard Penetration Tests. These boundaries, therefore, represent transitions between soil types rather than exact planes of geological change. Variation in the stratigraphic boundaries between and beyond boreholes exists and is to be expected.

In general, the subsurface conditions encountered at the site consist of a road pavement structure underlain by sand and gravel fill and variable embankment fill (for those boreholes drilled through the Highway 410 lanes or shoulder), or topsoil typically underlain by clayey silt fill (for those boreholes drilled outside of the embankment footprint). A till deposit, grading in composition from clayey silt to silt and sand, was encountered underlying the fill, and this represents the predominant soil deposit throughout the site. Clayey silt layers are present above the till or as interlayers within till in some of the boreholes. Residual soil / possible bedrock was encountered underlying the till deposit at some locations. At the north limit of the proposed installations, the subsurface conditions encountered in Borehole CCTV-1 differ and consist of a pavement structure and embankment fill material, underlain by deposits of silt and silty sand.

A more detailed description of the subsurface conditions throughout the site is provided in the following sections of this report. However, reference should be made to the closest borehole to any given sign support, HML or CCTV pole location to interpret the conditions at the applicable foundation element, recognizing the potential for variation between and beyond borehole locations.

### 4.2.1 Topsoil

An approximately 50 mm thick layer of topsoil was encountered at ground surface in Boreholes CCTV-5 and OH-5, and an approximately 200 mm thick layer of topsoil was encountered at ground surface in Borehole HML-1.

### 4.2.2 Asphalt

An approximately 130 mm to 330 mm thick layer of asphalt pavement was encountered at ground surface in Boreholes CCTV-1, CCTV-3, CCTV-4, CCTV-6, OH-1 through OH-4, OH-6, VMS-1 and VMS-2.

### 4.2.3 Fill

Fill was encountered in all the boreholes except Boreholes CCTV-5 and 122-3(2); in general, sand and gravel fill was encountered immediately below the asphalt, and cohesive fill was encountered below the granular fill, or below topsoil, as follows:

Borehole No.	Approximate Fill Thickness (m)	Elevation of Base of Fill (m)	Fill Description
C4-1	4.7	180.4	0.9 m of loose sand and gravel fill immediately below ground surface, underlain by firm to stiff clayey silt fill
CCTV-1	2.7	213.2	Stiff to hard sandy clayey silt fill below asphalt; plastic refuse was encountered within the fill at a depth of 2.3 m
CCTV-3	1.2	193.2	Dense sand and gravel fill below asphalt
CCTV-4	1.2	183.7	0.5 m of very dense sand and gravel fill below asphalt, underlain by 0.7 m of stiff sandy gravelling clayey silt fill
CCTV-6	0.9	182.8	Very dense sand and gravel fill below asphalt
HML-1	1.3	184.1	Very stiff clayey silt fill below topsoil
OH-1	0.5	188.7	Very dense sand and gravel fill below asphalt
OH-2	0.7	187.5	Very dense sand and gravel fill below asphalt
OH-3	0.7	184.8	Very dense sand and gravel fill below asphalt
OH-4	0.6	184.1	Compact sand and gravel fill below asphalt
OH-5	0.6	187.2	Firm clayey silt fill below topsoil
OH-6	4.2	188.2	0.6 m of very dense sand and gravel fill below asphalt, underlain by 3.6 m of stiff to very stiff gravelly sandy silty clay fill
VMS-1	0.9	195.2	Compact to dense sand and gravel fill below asphalt
VMS-2	1.9	184.1	1.0 m of compact to very dense sand and gravel fill, underlain by 0.9 m of stiff gravelly clayey silt

The Standard Penetration Test (SPT) “N”-values measured within the sand and gravel fill layers range from 13 blows to 110 blows per 0.3 m of penetration, indicating a compact to very dense level of compactness. The SPT “N”-values measured within the cohesive fill range from 4 blows to 38 blows per 0.3 m of penetration, suggesting a firm to hard consistency.

Grain size distribution testing was carried out on two samples of the cohesive fill as part of the 2019 investigation and the results are presented on Figure C-1 in Appendix C. Grain size distribution testing was carried out on one sample of the cohesive fill as part of the 2012 investigation and the results are presented in Appendix A.

Atterberg limits testing was carried out on one sample of the cohesive fill as part of the 2019 investigation and on one sample of the cohesive fill as part of the 2012 investigation. The testing measured liquid limits of 35 and

31 per cent, plastic limits of 21 and 17 per cent, and plasticity indices of about 14 per cent. The Atterberg limits testing results from the 2019 investigation are presented on Figure C-2 in Appendix C and indicate that the fill layer in this borehole is comprised of silty clay of intermediate plasticity. The Atterberg limits testing results from the 2012 investigation are contained in Appendix A and indicate that the fill layer in this borehole is comprised of clayey silt of low plasticity. The natural water content measured on selected samples of the cohesive fill range from about 2 per cent to about 17 per cent. The natural water content measured on selected samples of the non-cohesive fill range from about 3 per cent to about 6 per cent.

#### 4.2.4 Silt to Gravelly Silty Sand

A 2.6 m thick deposit of silt was encountered underlying the cohesive fill in Borehole CCTV-1 at a depth of 3.0 m, corresponding to Elevation 213.2 m. The silt is underlain in this borehole by a deposit of gravelly silty sand, the surface of which was encountered at a depth of 5.6 m, corresponding to Elevation 210.6 m. The borehole was terminated within the gravelly silty sand, penetrating it for a thickness of 2.2 m.

The SPT “N”-values measured within the silt deposit ranged from 21 blows to 121 blows per 0.3 m of penetration, increasing with depth, indicating a compact to very dense state of compactness. The SPT “N”-values measured within the gravelly silty sand deposit were 100 blows per 0.15 m of penetration and 100 blows per 0.05 m of penetration, indicating a very dense state of compactness. Auger grinding was observed during drilling in the gravelly silty sand deposit, suggesting the presence of cobbles and/or boulders.

Grain size distribution testing was carried out on a sample of the silt deposit; the results are presented on Figure C-3 in Appendix C. Atterberg limits testing was carried out on one sample silt deposit; the deposit was determined to be non-plastic. The water content measured on selected samples of the silt deposit ranges from about 18 per cent to about 23 per cent.

#### 4.2.5 Clayey Silt

Layers of clayey silt were encountered underlying the cohesive fill on top of the till deposit in Borehole CCTV-4, and interlayered within the till deposit in Boreholes C4-1, CCTV-5 and OH-4. The surface of the clayey silt layers was encountered between depths of 1.5 m and 10.2 m (Elevations 174.9 m and 183.7 m). Boreholes OH-4 and C4-1 were terminated within this layer, penetrating it for a thickness of 2.5 m and 0.7 m, respectively. The clayey silt layers are 1.5 m and 1.6 m thick in Boreholes CCTV-4 and CCTV-5, respectively, where they were fully penetrated.

The SPT “N”-values measured within the clayey silt layers range from 9 blows per 0.3 m of penetration to 60 blows per 0.08 m of penetration, suggesting a stiff to hard consistency.

Grain size distribution testing was carried out on three samples of the clayey silt deposit as part of the 2019 investigation; the results are presented on Figure C-4 in Appendix C. Grain size distribution testing was also carried out on one sample of the clayey silt as part of the 2012 investigation and the results are presented in Appendix A.

Atterberg limits testing was carried out on three samples of the clayey silt deposit as part of the 2019 investigation and one sample from the 2012 investigation, and measured liquid limits ranging from 20 per cent to 34 per cent, plastic limits ranging from 13 per cent to 19 per cent, and plasticity indices ranging from about 6 per cent to 15 per cent. The Atterberg limits testing results from the 2019 investigation are presented on Figure C-5 in Appendix C, and the results from the 2012 investigation are contained in Appendix A; these results indicate the deposit is comprised of clayey silt of low plasticity. The water content measured on selected samples of the clayey silt deposit range from approximately 11 per cent to 21 per cent, typically near the plastic limit for the material.

#### 4.2.6 Clayey Silt Till to Silt and Sand Till

A till deposit was encountered in all boreholes except Borehole CCTV-1, as follows:

- immediately below the then-existing ground surface in Borehole 122-3(2);
- underlying the topsoil in Borehole CCTV-5;
- underlying the sand and gravel fill in Boreholes CCTV-3, CCTV-6, OH-1 to OH-4, and VMS-1;
- underlying the cohesive fill in Boreholes C4-1, HML-1, OH-5, OH-6, and VMS-2; and
- underlying the surficial clayey silt in Borehole CCTV-4.

Boreholes OH-3, OH-5, OH-6, CCTV-4, CCTV-5, CCTV-6, VMS-1, VMS-2, HML-1 and 122-3(2) were terminated in this deposit, penetrating it for a thickness of 3.7 m to 8.1 m. Where fully penetrated, the till deposit is 4.7 m to 6.6 m thick.

The till deposit is generally comprised of clayey silt, some sand to clayey silt with sand, trace to some gravel. However, the till does vary in composition, and grades to a silt and sand till at depth in some of the boreholes (Boreholes CCTV-4, CCTV-6, OH-1, OH-4, and VMS-2). A 0.4 m thick layer of wet silt and sand was encountered within the till deposit in Borehole VMS-1 at a depth of 6.3 m (Elevation 190.1 m); although not specifically encountered in the samples in other boreholes, similar thin interlayers or lenses or water-bearing sand/silt/gravel soils should be expected within this deposit. Auger grinding was observed during drilling in the till deposit in the majority of the boreholes, and auger refusal was encountered in Boreholes HML-1 (at a depth of 8.2 m corresponding to Elevation 177.3 m), OH-2 (5.6 m/Elevation 182.7 m), OH-3 (5.2 m/Elevation 180.5 m) and OH-5 (7.5 m/Elevation 180.4 m), suggesting the presence of cobbles and/or boulders, which are commonly encountered in glacially derived materials and should be expected within this deposit. Shale fragments were encountered within the till deposit in Boreholes CCTV-1, CCTV-6, OH-1 and OH-3.

The SPT “N”-values measured within the cohesive portions of the till deposit range from 13 blows per 0.3 m of penetration to 100 blows per 0.1 m of penetration, suggesting a stiff to hard consistency. The SPT “N”-values measured within the non-cohesive portions of the till deposit range from 26 blows per 0.3 m of penetration to 100 blows per 0.15 m of penetration, indicating a compact to very dense state of compactness. In general, the SPT “N”-values increase with depth in both the cohesive and non-cohesive portions of the till deposit.

Grain size distribution testing was carried out on twenty-two samples of the cohesive till deposit and three samples of the non-cohesive till deposit as part of the 2019 investigation and the results are presented on Figures C-6A to C-6D in Appendix C. Grain size distribution testing was carried out on two samples of the till deposit as part of the 2012 investigation and the results are presented in Appendix A.

Atterberg limits testing was carried out on twenty samples of the cohesive till deposit and one sample of the non-cohesive till deposit as part of the 2019 investigation, as well as one sample of the cohesive fill as part of the 2012 investigation. The Atterberg limits tests on the cohesive till deposit measured liquid limits ranging from 17 per cent to 41 per cent, plastic limits ranging from 12 per cent to 22 per cent, and plasticity indices ranging from about 5 per cent to about 19 per cent. Atterberg limits testing was carried out on one sample silt deposit; the deposit was determined to be non-plastic. The Atterberg limits testing results from the 2019 investigation are presented on Figures C-7A to C-7C in Appendix C and the results from the 2012 investigation are contained in Appendix A; these results indicate the cohesive portion of the till deposit is comprised of clayey silt of low plasticity, although one

sample is classified as silty clay of intermediate plasticity. The water content measured on selected samples of the till deposit ranges from 7 per cent to 19 per cent, generally near or below the plastic limit for the material.

#### 4.2.7 Residual Soil and Shale Bedrock

A highly weathered shale, or residual soil, was encountered in Borehole OH-2 at a depth of 5.6 m (Elevation 182.7 m) and penetrated to a depth of 7.7 m (Elevation 180.6 m) before termination of the borehole. Fragments of highly weathered shale bedrock were found in Boreholes OH-1 and CCTV-3, encountering split-spoon refusal at a depth of 7.6 m (Elevation 181.7 m) and auger refusal at a depth of 6.5 m (Elevation 188.1 m), respectively.

### 4.3 Groundwater Conditions

Details of the groundwater levels measured in the open boreholes on completion of drilling are presented on the borehole records in Appendices A and B and presented below. It is emphasized that these water levels do not represent the stabilized groundwater level at the site; typically, the stabilized groundwater level will be higher than that encountered in open boreholes where cohesive till soils are present.

Borehole No.	Ground Surface Elevation (m)	Depth to Groundwater (m)	Groundwater Elevation (m)	Date
C4-1	185.1	Dry	-	August 22, 2012
122-3(2)	192.0	3.8	188.2	July 22, 1976
CCTV-1	216.2	2.6	213.6	March 18, 2019
CCTV-3	194.6	4.0	190.6	March 21, 2019
CCTV-4	185.1	Dry	-	March 25, 2019
CCTV-5	185.2	Dry	-	March 15, 2019
CCTV-6	184.0	7.8	176.2	March 21, 2019
HML-1	185.5	Dry	-	March 6, 2019
OH-1	189.3	Dry	-	March 12, 2019
OH-2	188.3	Dry	-	March 11, 2019
OH-3	185.7	Dry	-	March 10, 2019
OH-4	185.0	6.8	178.4	March 10, 2019
OH-5	187.9	Dry	-	March 6, 2019
OH-6	192.7	Dry	-	March 11, 2019
VMS-1	196.4	7.5	188.9	March 19, 2019
VMS-2	186.3	Dry	-	March 25, 2019

Based on the soil moisture contents and the observed oxidized zone (i.e. soil colour), together with measurements in piezometers for structure sites along this corridor, the groundwater level within the upper portion of the till deposit is inferred to be at about Elevation 181 m in the vicinity of Courtneypark Drive and Derry Road, rising to Elevation 213 m near Queen Street.

The groundwater level at the site will be subject to seasonal fluctuations and should be expected to be higher during the spring season or during and following periods of heavy precipitation. Further, perched groundwater levels should be expected within non-cohesive fill materials or interlayers.

#### 4.4 Analytical Testing Results

Seven soil samples were submitted for analysis of parameters used to assess the potential corrosivity of the site soil to steel and concrete. Detailed analytical test results are included in Appendix D and the test results are summarized below.

Borehole No. / Sample No.	pH	Resistivity (ohm-cm)	Electrical Conductivity (umho/cm)	Chlorides (ug/g)	Soluble Sulphates (ug/g)
OH-1 / 5	7.87	1,700	579	<20*	590
OH-2 / 2	7.84	480	2,100	770	1,100
OH-3 / 4	7.85	3,900	255	44	51
OH-4 / 3	7.85	1,200	869	430	61
OH-6 / 4	7.44	570	1,760	820	440
VMS-1 / 3	7.84	2,400	412	100	140
VMS-2 / 6	7.69	4,700	214	30	50

\* Reportable Detection Limit

## 5.0 CLOSURE

This Foundation Investigation Report was prepared by Mr. Eric Naylor, EIT, and reviewed by Ms. Nikol Kochmanová, P.Eng., a geotechnical engineer with Golder. Ms. Lisa Coyne, P.Eng., an MTO Foundations Designated Contact and Principal of Golder, conducted an independent technical and quality control review of the report.

### Golder Associates Ltd.



Eric Naylor, EIT  
*Geotechnical Engineer-in-Training*



Nikol Kochmanová, P.Eng.  
*Geotechnical Engineer*






Lisa Coyne, P.Eng.  
*Principal, MTO Designated Foundations Contact*

EN/NK/LCC/rb


Golder and the G logo are trademarks of Golder Associates Corporation

[https://golderassociates.sharepoint.com/sites/12504g/6.deliverables/fnds/2.phase 2 - site investigation/contract 2/5. ohs, vms, cctv and hml/3. final/1669996 fir2-5 2019may9 hwy 410 ohs, vms, cctv and hml.docx](https://golderassociates.sharepoint.com/sites/12504g/6.deliverables/fnds/2.phase2-site%20investigation/contract%202/5.ohs,vms,cctv%20and%20hml/3.final/1669996%20fir2-5%202019may9%20hwy%20410%20ohs,vms,cctv%20and%20hml.docx)





PLAN  
SCALE  
40 0 40 80 m



PLAN  
SCALE  
40 0 40 80 m


**METRIC**  
DIMENSIONS ARE IN METRES AND/OR  
MILLIMETRES UNLESS OTHERWISE SHOWN.  
STATIONS IN KILOMETRES + METRES.

CONT No. 2019-2014  
GWP No. 2369-15-00



HIGHWAY 410  
OHS, VMS, HML & CCTV POLES  
BOREHOLE LOCATIONS

SHEET



KEY PLAN  
SCALE  
40 0 40 80 m

#### LEGEND

- Borehole - Current Investigation
- ⊕ Borehole - Previous Investigation (GEOCRES. No. 30M12-122)

BOREHOLE CO-ORDINATES			
No.	ELEVATION	NORTHING	EASTING
122-3(2)	192.0	4837513.3	288255.4
CCTV-1	216.2	4840702.0	285577.9
CCTV-3	194.6	4836539.6	288731.1
OH-1	191.5	4836154.2	288961.7
OH-2	188.3	4835887.2	289161.2
OH-3	185.7	4835459.0	289662.0
VMS-1	196.4	4838493.1	287654.8

#### NOTES

This drawing is for subsurface information only. The proposed structure details/works are shown for illustration purposes only and may not be consistent with the final design configuration as shown elsewhere in the Contracts Documents.



#### REFERENCE

General arrangement plan provided in digital format by AECOM, drawing file nos. ACAD\_X-60543038-C-ALI-HWY 410.dwg, X-60543038-C-Courtneypark-NC - Addendum.dwg, received April 04, 2019 and ACAD-X-60543038-C-Base.dwg, received April, 12, 2019.

NO.	DATE	BY	REVISION
Geocres No. 30M12-445			
HWY. 410		PROJECT NO. 1669996	DIST. CENTRAL
SUBM'D. NK	CHKD. NK	DATE: 05/09/2019	SITE: .
DRAWN: DD	CHKD. NK	APPD. LCC	DWG. 1








CONT No. 2019-2014  
GWP No. 2369-15-00

HIGHWAY 410  
OHS, VMS, HML & CCTV POLES  
BOREHOLE LOCATIONS

SHEET



LEGEND

Borehole - Current Investigation

Borehole - Previous Investigation (GEOCRES. No. 30M12-361)

BOREHOLE CO-ORDINATES			
No.	ELEVATION	NORTHING	EASTING
C4-1	185.1	4834903.6	290226.0
CCTV-4	185.1	4835152.1	290066.5
CCTV-5	185.2	4834657.9	290565.8
CCTV-6	184.0	4834246.7	290957.8
HML-1	185.5	4834776.0	290272.9
OH-4	185.0	4835139.5	290000.4
OH-5	187.9	4834600.2	290262.0
OH-6	192.7	4834615.7	290287.5
VMS-2	186.3	4834872.8	290337.4

NOTES

This drawing is for subsurface information only. The proposed structure details/works are shown for illustration purposes only and may not be consistent with the final design configuration as shown elsewhere in the Contracts Documents.

REFERENCE

General arrangement plan provided in digital format by AECOM, drawing file nos. ACAD\_X-60543038-C-ALI-HWY 410.dwg, X-60543038-C-Courtneypark-NC - Addendum.dwg, received April 04, 2019 and ACAD-X-60543038-C-Base.dwg, received April, 12, 2019.



NO.	DATE	BY	REVISION
Geocres No. 30M12-445			
HWY. 410	PROJECT NO. 1669996		DIST. CENTRAL
SUBM'D. NK	CHKD. NK	DATE: 05/09/2019	SITE: .
DRAWN: DD	CHKD. NK	APPD. LCC	DWG. 2

**APPENDIX A**

**Borehole Records and Laboratory  
Testing from 1976 and 2012  
Investigations (GEOCRES No.  
30M12-122 and 30M12-361)**

ENGINEERING SERVICES BRANCH-GEOTECHNICAL OFFICE-SOIL MECHANICS SECTION

RECORD OF BOREHOLE NO 3(2) (Culvert 3)

WP 103-69-08

LOCATION Co-ords. N 15,870,376; E 945,660

ORIGINATED BY VK

DIST 6 HWY 410

BORING DATE July 22, 1976

COMPILED BY VK

DATUM Geodetic

BOREHOLE TYPE C.E. 5.1 (1) M.V.H.S.

CHECKED BY *CP*


SOIL PROFILE			SAMPLES			GROUND WATER ELEV	DYNAMIC CONE PENETRATION RESISTANCE PLOT				LIQUID LIMIT $W_L$ PLASTIC LIMIT $W_P$ WATER CONTENT $W$			UNIT WEIGHT $\gamma$	REMARKS
ELEV DEPTH	DESCRIPTION	STRAT. PLOT	NUMBER	TYPE	N' VALUES		20	40	60	80	100	$W_P$	$W$	$W_L$	
630.0	Ground Level														
0.0			1	SS	43										8 22 49 21
	Brown		2	SS	129										25 32 29 14
	Grey		3	SS	50	620									
	Ret. mixture of clayey silt, sand and gravel		4	SS	120										9 33 56 2
	(Glacial Till)		5	SS	137/6"										
	Hard		6	SS	100/6"	610									
603.5			7	SS	160										12 23 46 19
26.5	End of Borehole														

PROJECT		11-1111-0083		RECORD OF BOREHOLE No C4-1		SHEET 1 OF 1		METRIC								
G.W.P.		2144-07-00		LOCATION		N 4834903.6 ; E 290226.0		ORIGINATED BY								
DIST		Central HWY 410		BOREHOLE TYPE		CME-55 Track-mount, 152 mm Solid Stem Augers		COMPILED BY								
DATUM		Geodetic		DATE		August 22, 2012		CHECKED BY								
								LCC								
SOIL PROFILE			SAMPLES			GROUND WATER CONDITIONS	ELEVATION SCALE	DYNAMIC CONE PENETRATION RESISTANCE PLOT				PLASTIC LIMIT W <sub>p</sub>	NATURAL MOISTURE CONTENT W	LIQUID LIMIT W <sub>L</sub>	UNIT WEIGHT γ	REMARKS & GRAIN SIZE DISTRIBUTION (%)
ELEV DEPTH	DESCRIPTION	STRAT PLOT	NUMBER	TYPE	"N" VALUES			SHEAR STRENGTH kPa								
185.1	GROUND SURFACE															
0.0	Sand and gravel, some silt, trace clay (FILL) Loose Brown Moist															
184.2																
0.9	Clayey silt, with to some sand, trace gravel, containing rootlets (FILL) Firm to stiff Brown and grey with oxidation stains Moist		1	SS	7											
			2	SS	5											
			3	SS	8											
			4	SS	12											
			5	SS	6											
180.4			6	SS	18											
4.7	CLAYEY SILT, trace to some sand, trace gravel, containing cobbles and boulders (TILL) Very stiff to hard Brown with oxidation stains, becoming grey below 5.6 m Moist															
			7	SS	26											
			8	SS	64											
			9	SS	36											
174.9																
10.2	CLAYEY SILT, trace to some sand, trace gravel Hard Grey Moist		10	SS	60/0.08											
174.2																
10.9	END OF BOREHOLE															
NOTES:																
1. Borehole dry on completion of drilling.																

# GRAIN SIZE DISTRIBUTION TEST RESULTS

Culvert 4  
Clayey Silt Fill

FIGURE B1



## LEGEND


SYMBOL	BOREHOLE	SAMPLE	ELEVATION(m)
•	C4-1	4	181.7

Project Number: 11-1111-0083

Checked By: LCC

**Golder Associates**

Date: 12-Feb-13



Ministry of Transportation

Ontario

# PLASTICITY CHART Culvert 4 - Clayey Silt Fill

Figure No. B2


Project No. 11-1111-0083

Checked By: LCC

# GRAIN SIZE DISTRIBUTION TEST RESULTS

Culvert 4  
Clayey Silt to Silt Till

FIGURE B5




SILT AND CLAY SIZES	FINE	MEDIUM	COARSE	FINE	COARSE	COBBLE
FINE GRAINED	SAND SIZE			GRAVEL SIZE		SIZE

## LEGEND

SYMBOL	BOREHOLE	SAMPLE	ELEVATION(m)
●	C4-2	7	177.3
■	C4-1	8	177.2





Ministry of Transportation

Ontario

# PLASTICITY CHART Culvert 4 - Clayey Silt to Silt Till

Figure No. B6

Project No. 11-1111-0083


Checked By: LCC



# GRAIN SIZE DISTRIBUTION TEST RESULTS

Culvert 4  
Lower Clayey Silt


FIGURE B7



SILT AND CLAY SIZES	FINE	MEDIUM	COARSE	FINE	COARSE	COBBLE
FINE GRAINED	SAND SIZE			GRAVEL SIZE		SIZE

## LEGEND

SYMBOL	BOREHOLE	SAMPLE	ELEVATION(m)
•	C4-1	10	174.3



Ministry of Transportation

Ontario

# PLASTICITY CHART Culvert 4 - Lower Clayey Silt

Figure No. B8

Project No. 11-1111-0083

Checked By: LCC

**APPENDIX B**

**Borehole Records from 2019  
Investigation**

## LIST OF SYMBOLS

Unless otherwise stated, the symbols employed in the report are as follows:

### I. GENERAL

$\pi$	3.1416
$\ln x$ ,	natural logarithm of x
$\log_{10}$	x or log x, logarithm of x to base 10
g	acceleration due to gravity
t	time
FoS	factor of safety

### II. STRESS AND STRAIN

$\gamma$	shear strain
$\Delta$	change in, e.g. in stress: $\Delta \sigma$
$\varepsilon$	linear strain
$\varepsilon_v$	volumetric strain
$\eta$	coefficient of viscosity
$\nu$	Poisson's ratio
$\sigma$	total stress
$\sigma'$	effective stress ( $\sigma' = \sigma - u$ )
$\sigma'_{vo}$	initial effective overburden stress
$\sigma_1, \sigma_2, \sigma_3$	principal stress (major, intermediate, minor)
$\sigma_{oct}$	mean stress or octahedral stress $= (\sigma_1 + \sigma_2 + \sigma_3)/3$
$\tau$	shear stress
u	porewater pressure
E	modulus of deformation
G	shear modulus of deformation
K	bulk modulus of compressibility

### III. SOIL PROPERTIES

#### (a) Index Properties

$\rho(\gamma)$	bulk density (bulk unit weight)*
$\rho_d(\gamma_d)$	dry density (dry unit weight)
$\rho_w(\gamma_w)$	density (unit weight) of water
$\rho_s(\gamma_s)$	density (unit weight) of solid particles
$\gamma'$	unit weight of submerged soil ( $\gamma' = \gamma - \gamma_w$ )
$D_R$	relative density (specific gravity) of solid particles ( $D_R = \rho_s / \rho_w$ ) (formerly $G_s$ )
e	void ratio
n	porosity
S	degree of saturation

\* Density symbol is  $\rho$ . Unit weight symbol is  $\gamma$  where  $\gamma = \rho g$  (i.e. mass density multiplied by acceleration due to gravity)

#### (a) Index Properties (continued)

w	water content
$w_l$ or LL	liquid limit
$w_p$ or PL	plastic limit
$I_p$ or PI	plasticity index = $(w_l - w_p)$
$w_s$	shrinkage limit
$I_L$	liquidity index = $(w - w_p) / I_p$
$I_c$	consistency index = $(w_l - w) / I_p$
$e_{max}$	void ratio in loosest state
$e_{min}$	void ratio in densest state
$I_D$	density index = $(e_{max} - e) / (e_{max} - e_{min})$ (formerly relative density)

#### (b) Hydraulic Properties

h	hydraulic head or potential
q	rate of flow
v	velocity of flow
i	hydraulic gradient
k	hydraulic conductivity (coefficient of permeability)
j	seepage force per unit volume

#### (c) Consolidation (one-dimensional)

$C_c$	compression index (normally consolidated range)
$C_r$	recompression index (over-consolidated range)
$C_s$	swelling index
$C_{\alpha}$	secondary compression index
$m_v$	coefficient of volume change
$C_v$	coefficient of consolidation (vertical direction)
$C_h$	coefficient of consolidation (horizontal direction)
$T_v$	time factor (vertical direction)
U	degree of consolidation
$\sigma'_p$	pre-consolidation stress
OCR	over-consolidation ratio = $\sigma'_p / \sigma'_{vo}$

#### (d) Shear Strength

$\tau_p, \tau_r$	peak and residual shear strength
$\phi'$	effective angle of internal friction
$\delta$	angle of interface friction
$\mu$	coefficient of friction = $\tan \delta$
$c'$	effective cohesion
$c_u, s_u$	undrained shear strength ( $\phi = 0$ analysis)
p	mean total stress $(\sigma_1 + \sigma_3)/2$
$p'$	mean effective stress $(\sigma'_1 + \sigma'_3)/2$
q	$(\sigma_1 - \sigma_3)/2$ or $(\sigma'_1 - \sigma'_3)/2$
$q_u$	compressive strength $(\sigma_1 - \sigma_3)$
$S_t$	sensitivity

Notes: 1  
2

$\tau = c' + \sigma' \tan \phi'$   
shear strength = (compressive strength)/2

## LIST OF ABBREVIATIONS

The abbreviations commonly employed on Records of Boreholes, on figures and in the text of the report are as follows:

### I. SAMPLE TYPE

AS	Auger sample
BS	Block sample
CS	Chunk sample
DS	Denison type sample
FS	Foil sample
RC	Rock core
SC	Soil core
SS	Split-spoon
ST	Slotted tube
TO	Thin-walled, open
TP	Thin-walled, piston
WS	Wash sample

### II. PENETRATION RESISTANCE

#### Standard Penetration Resistance (SPT), N:

The number of blows by a 63.5 kg. (140 lb.) hammer dropped 760 mm (30 in.) required to drive a 50 mm (2 in.) drive open sampler for a distance of 300 mm (12 in.)

#### Dynamic Cone Penetration Resistance; $N_d$ :

The number of blows by a 63.5 kg (140 lb.) hammer dropped 760 mm (30 in.) to drive uncased a 50 mm (2 in.) diameter, 60° cone attached to "A" size drill rods for a distance of 300 mm (12 in.).

**PH:** Sampler advanced by hydraulic pressure

**PM:** Sampler advanced by manual pressure

**WH:** Sampler advanced by static weight of hammer

**WR:** Sampler advanced by weight of sampler and rod

#### Piezo-Cone Penetration Test (CPT)

A electronic cone penetrometer with a 60° conical tip and a project end area of 10 cm<sup>2</sup> pushed through ground at a penetration rate of 2 cm/s. Measurements of tip resistance ( $Q_t$ ), porewater pressure (PWP) and friction along a sleeve are recorded electronically at 25 mm penetration intervals.

### III. SOIL DESCRIPTION

#### (a) Non-Cohesive (Cohesionless) Soils

Compactness	N
Condition	Blows/300 mm or Blows/ft
Very loose	0 to 4
Loose	4 to 10
Compact	10 to 30
Dense	30 to 50
Very dense	over 50

#### (b) Cohesive Soils Consistency

	$C_u, S_u$	
	kPa	psf
Very soft	0 to 12	0 to 250
Soft	12 to 25	250 to 500
Firm	25 to 50	500 to 1,000
Stiff	50 to 100	1,000 to 2,000
Very stiff	100 to 200	2,000 to 4,000
Hard	over 200	over 4,000

### IV. SOIL TESTS

w	water content
$w_p$	plastic limit
$w_l$	liquid limit
C	consolidation (oedometer) test
CHEM	chemical analysis (refer to text)
CID	consolidated isotropically drained triaxial test <sup>1</sup>
CIU	consolidated isotropically undrained triaxial test with porewater pressure measurement <sup>1</sup>
$D_R$	relative density (specific gravity, $G_s$ )
DS	direct shear test
M	sieve analysis for particle size
MH	combined sieve and hydrometer (H) analysis
MPC	Modified Proctor compaction test
SPC	Standard Proctor compaction test
OC	organic content test
$SO_4$	concentration of water-soluble sulphates
UC	unconfined compression test
UU	unconsolidated undrained triaxial test
V	field vane (LV-laboratory vane test)
$\gamma$	unit weight

**Note:** 1 Tests which are anisotropically consolidated prior to shear are shown as CAD, CAU.

### V. MINOR SOIL CONSTITUENTS

Per cent by Weight	Modifier	Example
0 to 5	Trace	Trace sand
5 to 12	Trace to Some (or Little)	Trace to some sand
12 to 20	Some	Some sand
20 to 30	(ey) or (y)	Sandy
over 30	And (non-cohesive (cohesionless)) or With (cohesive)	Sand and Gravel Silty Clay with sand / Clayey Silt with sand

PROJECT 1669996		RECORD OF BOREHOLE No CCTV-1				SHEET 1 OF 1		METRIC									
G.W.P. 2369-15-00		LOCATION N 4840702.0; E 285577.9 MTM NAD ZONE (LAT. 43.706029; LONG. -79.738523)				ORIGINATED BY SE											
DIST Central HWY 410		BOREHOLE TYPE 152 mm O.D. Hollow Stem Augers; CME 55 Track Mounted Drill Rig				COMPILED BY EN											
DATUM Geodetic		DATE March 18, 2019				CHECKED BY NK											
SOIL PROFILE			SAMPLES			GROUND WATER CONDITIONS	ELEVATION SCALE	DYNAMIC CONE PENETRATION RESISTANCE PLOT					PLASTIC LIMIT W <sub>p</sub>	NATURAL MOISTURE CONTENT W	LIQUID LIMIT W <sub>L</sub>	UNIT WEIGHT γ	REMARKS & GRAIN SIZE DISTRIBUTION (%)
ELEV DEPTH	DESCRIPTION	STRAT PLOT	NUMBER	TYPE	"N" VALUES			SHEAR STRENGTH kPa									
216.2	GROUND SURFACE							20	40	60	80	100					
215.9	ASPHALT (280 mm)						216										
0.3	Sandy clayey silt, some gravel (FILL) Stiff to hard Brown Moist		-	SS	13		215										
			1	SS	26												
			2	SS	8		214										
	- Plastic refuse encountered at 2.3 m, no sample recovered		3	SS	38												
213.2	SILT, some sand, some gravel, trace clay Compact to very dense Grey Wet		4	SS	21		213										
3.0			5	SS	59		212										
			6	SS	121		211										
210.6	Gravelly Silty SAND, shale fragments at 5.2 m Very dense Grey Moist - Auger grinding at 6.1 m to 7.6 m		7	SS	100/0.05		210										
5.6							209										
208.4	END OF BOREHOLE		8	SS	100/0.15												
7.8	NOTES:  1. Borehole caved to 3.0 m on removal of augers.  2. Water level in open borehole at 2.6 m below ground surface on removal of augers.																

PROJECT 1669996		RECORD OF BOREHOLE No CCTV-3				SHEET 1 OF 1		METRIC									
G.W.P. 2369-15-00		LOCATION N 4836539.6; E 288731.1 MTM NAD ZONE (LAT. 43.668635; LONG. -79.699269)				ORIGINATED BY SE											
DIST Central HWY 410		BOREHOLE TYPE 152 mm O.D. Hollow Stem Augers; CME 55 Track Mounted Drill Rig				COMPILED BY EN											
DATUM Geodetic		DATE March 19 and 21, 2019				CHECKED BY NK											
SOIL PROFILE			SAMPLES			GROUND WATER CONDITIONS	ELEVATION SCALE	DYNAMIC CONE PENETRATION RESISTANCE PLOT					PLASTIC LIMIT W <sub>p</sub>	NATURAL MOISTURE CONTENT W	LIQUID LIMIT W <sub>L</sub>	UNIT WEIGHT γ	REMARKS & GRAIN SIZE DISTRIBUTION (%)
ELEV DEPTH	DESCRIPTION	STRAT PLOT	NUMBER	TYPE	"N" VALUES			SHEAR STRENGTH kPa									
194.6	GROUND SURFACE							20	40	60	80	100					
194.3	ASPHALT (280 mm)																
0.3	Sand and gravel, some silt (FILL) Dense Brown Moist		-	SS	41		194										
			1	SS	31												
193.2	CLAYEY SILT, some sand to Sandy CLAYEY SILT, trace to some gravel (TILL) Stiff to hard Brown Moist		2	SS	14		193										5 22 46 27
			3	SS	15		192										
			4	SS	20		191										
			5	SS	18/0.25		190										13 19 45 23
	- Auger grinding at 4.4 m		6	SS	27/0.23		189										
	- Auger grinding at 5.0 m																
188.5	- Auger grinding at 6.1 m		7	SS	00/0.00												
188.1	SHALE (BEDROCK)																
6.5	- Auger grinding from 6.1 m to 6.5 m AUGER REFUSAL END OF BOREHOLE																
NOTES:																	
1. Water level at a depth of 3.96 m below ground surface (Elev. 190.6 m) on completion of drilling (left overnight).																	
2. Borehole caved to a depth of 6.2 m below ground surface on removal of augers.																	

PROJECT 1669996		<b>RECORD OF BOREHOLE No CCTV-4</b>				SHEET 1 OF 1		<b>METRIC</b>	
G.W.P. 2369-15-00		LOCATION N 4835152.1; E 290066.5 MTM NAD ZONE (LAT. 43.656178; LONG. -79.682667)				ORIGINATED BY JP			
DIST Central HWY 410		BOREHOLE TYPE 203 mm O.D. Hollow Stem Augers; CME 55 Track Mounted Drill Rig				COMPILED BY EN			
DATUM Geodetic		DATE March 25, 2019				CHECKED BY NK			

SOIL PROFILE			SAMPLES			GROUND WATER CONDITIONS	ELEVATION SCALE	DYNAMIC CONE PENETRATION RESISTANCE PLOT					PLASTIC LIMIT NATURAL MOISTURE CONTENT LIQUID LIMIT			UNIT WEIGHT $\gamma$	REMARKS & GRAIN SIZE DISTRIBUTION (%)
ELEV DEPTH	DESCRIPTION	STRAT PLOT	NUMBER	TYPE	"N" VALUES			SHEAR STRENGTH kPa					W <sub>p</sub>	W	W <sub>L</sub>		
							20	40	60	80	100						
185.1	GROUND SURFACE																
0.0	ASPHALT (330 mm)																
184.8																	
0.3	Sand and gravel, some silt (FILL)		-	SS	99												
184.3	Very dense Brown/black Moist		1	SS	12												
0.8																	
183.7	Sandy gravelly clayey silt, some clay pocket (FILL)																
1.5	Stiff Mottled brown and grey Moist		2	SS	13												
	CLAYEY SILT, some sand, trace gravel																
	Stiff to very stiff Mottled brown and grey Moist		3	SS	22												
182.1																	
3.0	Sandy CLAYEY SILT, some gravel (TILL)		4	SS	69												
	Hard Grey Moist																
	- Auger grinding at 3.8 m		5	SS	27												
180.6																	
4.5	SILT and SAND, trace to some clay, trace to some gravel (TILL)		6	SS	26												
	Compact to very dense Grey Moist																
			7	SS	35												
			8	SS	79												
176.9																	
8.2	END OF BOREHOLE																
	NOTES:																
	1. Borehole caved to a depth of 7.0 m below ground surface on removal of augers.																
	2. Open borehole dry on completion of drilling and removal of augers.																




PROJECT 1669996		RECORD OF BOREHOLE No CCTV-5				SHEET 1 OF 1		METRIC						
G.W.P. 2369-15-00		LOCATION N 4834657.9; E 290565.8 MTM NAD ZONE (LAT. 43.651737; LONG. -79.676462)				ORIGINATED BY SE								
DIST Central HWY 410		BOREHOLE TYPE 152 mm O.D. Hollow Stem Augers; CME 55 Track Mounted Drill Rig				COMPILED BY EN								
DATUM Geodetic		DATE March 15, 2019				CHECKED BY NK								
SOIL PROFILE			SAMPLES			GROUND WATER CONDITIONS	ELEVATION SCALE	DYNAMIC CONE PENETRATION RESISTANCE PLOT		PLASTIC LIMIT W <sub>p</sub>	NATURAL MOISTURE CONTENT W	LIQUID LIMIT W <sub>L</sub>	UNIT WEIGHT γ	REMARKS & GRAIN SIZE DISTRIBUTION (%)
ELEV DEPTH	DESCRIPTION	STRAT PLOT	NUMBER	TYPE	"N" VALUES			SHEAR STRENGTH kPa						
185.2	GROUND SURFACE							20 40 60 80 100	20 40 60 80 100	10 20 30				
8.9	TOPSOIL (50 mm)													
	Sandy CLAYEY SILT to CLAYEY SILT with SAND, trace to some gravel (TILL) Stiff to hard Mottled brown to grey below 4.0 m Moist		-	SS	8		185							
			1	SS	22		184							
			2	SS	23		183							
			3	SS	37		182							
			4	SS	34		181							
			5	SS	23		180							
			6	SS	17		179							
179.6	CLAYEY SILT, some sand, trace gravel Stiff Grey Moist		7	SS	9		178							
178.0	CLAYEY SILT with SAND, trace gravel (TILL) Hard Grey Moist		8A	SS	36		177							
177.0	END OF BOREHOLE		8B											
8.2	NOTE: 1. Open borehole dry upon completion of drilling and removal of augers.													


PROJECT 1669996		RECORD OF BOREHOLE No CCTV-6				SHEET 1 OF 1		METRIC						
G.W.P. 2369-15-00		LOCATION N 4834246.7; E 290957.8 MTM NAD ZONE (LAT. 43.648042; LONG. -79.671594)				ORIGINATED BY SE								
DIST Central HWY 410		BOREHOLE TYPE 152 mm O.D. Hollow Stem Augers; CME 55 Track Mounted Drill Rig				COMPILED BY EN								
DATUM Geodetic		DATE March 21, 2019				CHECKED BY NK								
SOIL PROFILE			SAMPLES			GROUND WATER CONDITIONS	ELEVATION SCALE	DYNAMIC CONE PENETRATION RESISTANCE PLOT		PLASTIC LIMIT W <sub>p</sub>	NATURAL MOISTURE CONTENT W	LIQUID LIMIT W <sub>L</sub>	UNIT WEIGHT γ	REMARKS & GRAIN SIZE DISTRIBUTION (%)
ELEV DEPTH	DESCRIPTION	STRAT PLOT	NUMBER	TYPE	"N" VALUES			SHEAR STRENGTH kPa						
184.0	GROUND SURFACE							20 40 60 80 100	20 40 60 80 100	10 20 30				
0.0	ASPHALT (250 mm)													
0.3	Sand and gravel, some silt (FILL) Very dense to compact Brown Moist - Contains asphalt and brick fragments		-	SS	86									
182.8	- Slight hydrocarbon odour		1A	SS	15									
1.2	Sandy CLAYEY SILT to CLAYEY SILT with SAND, trace gravel to gravelly (TILL) Very stiff to hard Brown to grey below 4.4 m Moist		1B											
			2	SS	25									
			3	SS	46									
			4	SS	45									
			5	SS	64									
			6	SS	26									
			7	SS	19									
	- Auger grinding at 7.0 m													
176.4														
7.8	SILT and SAND, some clay, some gravel, contains shale fragments (TILL) Very dense Grey Moist END OF BOREHOLE		8	SS	100/0.15									
NOTES: 1. Water level in the open borehole at a depth of 7.8 m below ground surface on removal of augers. 2. Borehole caved to a depth of 6.5 m below ground surface on removal of augers.														

PROJECT 1669996		RECORD OF BOREHOLE No HML-1				SHEET 1 OF 1		METRIC									
G.W.P. 2369-15-00		LOCATION N 4834776.0; E 290272.9 MTM NAD ZONE (LAT. 43.652794; LONG. -79.680096)				ORIGINATED BY SE											
DIST Central HWY 410		BOREHOLE TYPE 152 mm O.D. Hollow Stem Augers; CME 55 Track Mounted Drill Rig				COMPILED BY EN											
DATUM Geodetic		DATE March 6, 2019				CHECKED BY NK											
SOIL PROFILE			SAMPLES			GROUND WATER CONDITIONS	ELEVATION SCALE	DYNAMIC CONE PENETRATION RESISTANCE PLOT					PLASTIC LIMIT W <sub>p</sub>	NATURAL MOISTURE CONTENT W	LIQUID LIMIT W <sub>L</sub>	UNIT WEIGHT γ	REMARKS & GRAIN SIZE DISTRIBUTION (%)
ELEV DEPTH	DESCRIPTION	STRAT PLOT	NUMBER	TYPE	"N" VALUES			SHEAR STRENGTH kPa									
185.5	GROUND SURFACE							20	40	60	80	100					
0.0	TOPSOIL (200 mm)																
0.2	Clayey silt, some sand, some gravel (FILL) Very stiff Brown with oxidation staining Moist		1	SS	22		185										
184.1							184										
1.5	CLAYEY SILT, some sand to with SAND, trace gravel to gravelly, shale fragments between 4.4 m and 5.2 m (TILL) Very stiff to hard Brown to grey below 5.6 m Moist - Some oxidation staining above 2.1 m		2	SS	23												
			3	SS	30		183										
			4	SS	16		182										
			5	SS	51		181										
			6	SS	57												
	- Auger grinding at 5.2 m						180										
			7	SS	65		179										
							178										
177.3	- Auger grinding at 8.1 m		8	SS	72												
8.2	AUGER REFUSAL SPLIT SPOON REFUSAL END OF BOREHOLE  NOTE: 1. Open borehole dry on completion of drilling and removal of augers.																


GTA-MTO 001 S:\CLIENTS\MTOWHY\_410\_COURTNEY PARK02\_DATA\GINT\HWY\_410\_COURTNEY PARK.GPJ GAL-GTA.GDT 04/25/19



+<sup>3</sup>, ×<sup>3</sup>: Numbers refer to Sensitivity      ○<sup>3</sup>% STRAIN AT FAILURE



+<sup>3</sup>, ×<sup>3</sup>: Numbers refer to Sensitivity      ○<sup>3</sup>% STRAIN AT FAILURE



+<sup>3</sup>, ×<sup>3</sup>: Numbers refer to Sensitivity      ○<sup>3</sup>% STRAIN AT FAILURE

PROJECT		1669996		RECORD OF BOREHOLE No OH-4		SHEET 1 OF 1		METRIC					
G.W.P.		2369-15-00		LOCATION		N 4835139.5; E 290000.4 MTM NAD ZONE (LAT. 43.656061; LONG. -79.683485)		ORIGINATED BY SE					
DIST		Central HWY 410		BOREHOLE TYPE		152 mm O.D. Hollow Stem Augers; CME 55 Track Mounted Drill Rig		COMPILED BY EN					
DATUM		Geodetic		DATE		March 10, 2019		CHECKED BY NK					
SOIL PROFILE			SAMPLES			GROUND WATER CONDITIONS	ELEVATION SCALE	DYNAMIC CONE PENETRATION RESISTANCE PLOT		PLASTIC LIMIT NATURAL MOISTURE CONTENT LIQUID LIMIT		UNIT WEIGHT $\gamma$	REMARKS & GRAIN SIZE DISTRIBUTION (%)
ELEV DEPTH	DESCRIPTION	STRAT PLOT	NUMBER	TYPE	"N" VALUES			20 40 60 80 100	20 40 60 80 100	W <sub>p</sub> W W <sub>L</sub>	WATER CONTENT (%)		
185.0	GROUND SURFACE												
0.0	ASPHALT (330 mm)												
184.7													
0.3	Sand and gravel, some silt (FILL) Compact Brown Moist												
184.1			1A	SS	13								
0.9	CLAYEY SILT with SAND, some gravel (TILL) Stiff to hard Brown with oxidation staining Moist		1B										
			2	SS	28								
			3	SS	28								
			4	SS	30								
181.3													
3.7	SILT and SAND, trace to some clay, trace gravel (TILL) Dense to very dense Grey Moist		5	SS	53								
			6	SS	41								
179.4													
5.6	CLAYEY SILT, some sand Hard Grey Moist		7	SS	33								
176.9			8A	SS	35								
8.1	END OF BOREHOLE		8B										
NOTES:													
1. Borehole caved to depth of 6.9 m on removal of augers.													
2. Water level in open borehole at a depth of 6.8 m below ground surface (Elev. 178.4 m) on completion of soil drilling.													


PROJECT 1669996		RECORD OF BOREHOLE No OH-5		SHEET 1 OF 1		METRIC													
G.W.P. 2369-15-00		LOCATION N 4834600.2; E 290262.0 MTM NAD ZONE (LAT. 43.651211; LONG. -79.680227)		ORIGINATED BY SE															
DIST Central HWY 410		BOREHOLE TYPE 152 mm O.D. Hollow Stem Augers; CME 55 Track Mounted Drill Rig		COMPILED BY EN															
DATUM Geodetic		DATE March 5 and 6, 2019		CHECKED BY NK															
SOIL PROFILE			SAMPLES			DYNAMIC CONE PENETRATION RESISTANCE PLOT			PLASTIC LIMIT NATURAL MOISTURE CONTENT LIQUID LIMIT			UNIT WEIGHT			REMARKS & GRAIN SIZE DISTRIBUTION (%)				
ELEV DEPTH	DESCRIPTION	STRAT PLOT	NUMBER	TYPE	"N" VALUES	GROUND WATER CONDITIONS	ELEVATION SCALE	SHEAR STRENGTH kPa ○ UNCONFINED + FIELD VANE ● QUICK TRIAXIAL × REMOULDED					WATER CONTENT (%) W <sub>p</sub> — W — W <sub>L</sub>			γ			GR SA SI CL
187.9	GROUND SURFACE							20 40 60 80 100											
0.9	TOPSOIL (50 mm )		1	SS	4														
187.2	Clayey silt, some sand, some organics (FILL) Firm Brown Moist		2	SS	17		187												
0.7	Sandy CLAYEY SILT, trace to some gravel (TILL) Very stiff to hard Brown to grey below 4.5 m Moist		3	SS	27		186												
			4	SS	41		185										3 22 52 23		
			5	SS	52		184												
			6	SS	30		183												
			7	SS	18		182												
			8	SS	23		181										18 23 42 17		
180.4	- Auger grinding at 7.3 m - Water seepage at 7.3 m																		
7.5	AUGER REFUSAL SPLIT SPOON REFUSAL END OF BOREHOLE																		
NOTES:																			
1. Borehole caved to 6.4 m on removal of augers.																			
2. Open borehole dry on completion of drilling.																			

GTA-MTO 001 S:\CLIENTS\IMTOHWY\_410\_COURTNEY PARK\02\_DATA\GINT\HWY\_410\_COURTNEY PARK.GPJ GAL-GTA.GDT 04/25/19



PROJECT 1669996		RECORD OF BOREHOLE No OH-6				SHEET 1 OF 1		METRIC								
G.W.P. 2369-15-00		LOCATION N 4834615.7; E 290287.5 MTM NAD ZONE (LAT. 43.651351; LONG. -79.679911)				ORIGINATED BY SE										
DIST Central HWY 410		BOREHOLE TYPE 152 mm O.D. Hollow Stem Augers; CME 55 Track Mounted Drill Rig				COMPILED BY EN										
DATUM Geodetic		DATE March 11, 2019				CHECKED BY NK										
SOIL PROFILE			SAMPLES			GROUND WATER CONDITIONS	ELEVATION SCALE	DYNAMIC CONE PENETRATION RESISTANCE PLOT				PLASTIC LIMIT W <sub>p</sub>	NATURAL MOISTURE CONTENT W	LIQUID LIMIT W <sub>L</sub>	UNIT WEIGHT γ	REMARKS & GRAIN SIZE DISTRIBUTION (%)
ELEV DEPTH	DESCRIPTION	STRAT PLOT	NUMBER	TYPE	"N" VALUES			SHEAR STRENGTH kPa								
192.7	GROUND SURFACE															
0.0	ASPHALT (305 mm)															
0.3	Sand and gravel, some silt (FILL) Very dense Brown Moist		1	SS	87											
191.8																
0.9	Gravelly sandy silty clay (FILL) Stiff to very stiff Grey to mottled brown Moist		2	SS	14											33 17 37 13
			3	SS	13											
			4	SS	10											
			5	SS	28											30 23 32 15
	- Auger grinding at 3.7 m															
			6	SS	13											
188.2	- Auger grinding at 4.4 m															
4.5	Sandy CLAYEY SILT, trace to some gravel, trace rootlets to 5.1 m (TILL) Stiff to hard Brown to grey below 7.2 m Moist		7	SS	14											
			8	SS	41											
185			9	SS	27											10 28 39 23
184.5	END OF BOREHOLE															
8.2	NOTES:  1. Borehole caved to a depth of 6.7 m below ground surface on removal of augers.  2. Open borehole dry on completion of drilling and removal of augers.															

PROJECT 1669996		RECORD OF BOREHOLE No VMS-1				SHEET 1 OF 1		METRIC								
G.W.P. 2369-15-00		LOCATION N 4838493.1; E 287654.8 MTM NAD ZONE (LAT. 43.686192; LONG. -79.712675)				ORIGINATED BY SE										
DIST Central HWY 410		BOREHOLE TYPE 152 mm O.D. Hollow Stem Augers; CME 55 Track Mounted Drill Rig				COMPILED BY EN										
DATUM Geodetic		DATE March 19, 2019				CHECKED BY NK										
SOIL PROFILE			SAMPLES			GROUND WATER CONDITIONS	ELEVATION SCALE	DYNAMIC CONE PENETRATION RESISTANCE PLOT				PLASTIC LIMIT W <sub>p</sub>	NATURAL MOISTURE CONTENT W	LIQUID LIMIT W <sub>L</sub>	UNIT WEIGHT γ	REMARKS & GRAIN SIZE DISTRIBUTION (%)
ELEV DEPTH	DESCRIPTION	STRAT PLOT	NUMBER	TYPE	"N" VALUES			SHEAR STRENGTH kPa								
196.4	GROUND SURFACE															
0.0	ASPHALT (300 mm)															
196.1																
0.3	Sand and gravel, some silt (FILL) Compact to dense Brown Moist		-	SS	39		196									
195.2			1A	SS	21											
1.2	Sandy CLAYEY SILT, trace to some gravel (TILL) Very stiff to hard Brown to grey below 3.9 m Moist		1B				195									
			2	SS	33											
			3	SS	43		194									
			4	SS	40		193									
			5	SS	53		192									
			6	SS	61		191									
			7A	SS	68		190									
190.1	SILT and SAND Very dense Grey Wet		7B													
189.7	Sandy CLAYEY SILT, trace to some gravel (TILL) Very stiff to hard Brown to grey below 3.9 m Moist		8	SS	42/0.25		189									
188.4																
8.0	END OF BOREHOLE															
NOTES: 1. Borehole caved to depth of 6.1 m on removal of augers. 2. Water level in open borehole at a depth of 7.5 m below ground surface (Elev. 188.9 m) on completion of drilling.																



+<sup>3</sup>, ×<sup>3</sup>: Numbers refer to Sensitivity      ○<sup>3</sup>% STRAIN AT FAILURE


**APPENDIX C**

**Geotechnical Laboratory Test  
Results from 2019 Investigation**

# GRAIN SIZE DISTRIBUTION

Gravelly Sandy Silty Clay Fill

FIGURE C-1



SILT AND CLAY SIZES		FINE	MEDIUM	COARSE	FINE	COARSE	COBBLE SIZE
FINE GRAINED		SAND SIZE			GRAVEL SIZE		

## LEGEND


SYMBOL	Borehole	SAMPLE	ELEVATION(m)
●	OH-6	2	191.5
■	OH-6	4	190.1

Project Number: 1669996

Checked By: NK

**Golder Associates**

Date: 24-Apr-19



Ministry of Transportation

Ontario

# PLASTICITY CHART Gravelly Sandy Silty Clay Fill

Figure No. C-2


Project No. 1669996 (2200)

Checked By: NK

# GRAIN SIZE DISTRIBUTION

Silt

FIGURE C-3



SILT AND CLAY SIZES		FINE	MEDIUM	COARSE	FINE	COARSE	COBBLE
FINE GRAINED		SAND SIZE			GRAVEL SIZE		SIZE

## LEGEND

SYMBOL	Borehole	SAMPLE	ELEVATION(m)
•	CCTV-1	6	211.4

Project Number: 1669996

Checked By: NK


**Golder Associates**

Date: 24-Apr-19

# GRAIN SIZE DISTRIBUTION

Clayey Silt

FIGURE C-4



SILT AND CLAY SIZES	FINE	MEDIUM	COARSE	FINE	COARSE	COBBLE
FINE GRAINED	SAND SIZE			GRAVEL SIZE		SIZE

## LEGEND

SYMBOL	Borehole	SAMPLE	ELEVATION(m)
●	CCTV-4	3	182.5
■	OH-4	7	178.6
◆	CCTV-5	7	178.8


Project Number: 1669996

Checked By: NK

**Golder Associates**

Date: 24-Apr-19





Ministry of Transportation

Ontario

## PLASTICITY CHART

### Clayey Silt

Figure No. C-5


Project No. 1669996 (2200)

Checked By: NK

# GRAIN SIZE DISTRIBUTION

Clayey Silt to Clayey Silt with Sand Till

FIGURE C-6A



SILT AND CLAY SIZES	FINE	MEDIUM	COARSE	FINE	COARSE	COBBLE
FINE GRAINED	SAND SIZE			GRAVEL SIZE		SIZE

## LEGEND

SYMBOL	Borehole	SAMPLE	ELEVATION(m)
●	CCTV-3	2	192.8
■	CCTV-6	3	181.4
◆	CCTV-5	4	181.8
▲	CCTV-3	5	190.6
▽	OH-2	5	184.9
○	CCTV-6	7	177.6
□	CCTV-5	8A	177.4

Project Number: 1669996

Checked By: NK


**Golder Associates**

Date: 24-Apr-19

# GRAIN SIZE DISTRIBUTION

Silty Clay to Clayey Silt with Sand Till

FIGURE C-6B



SILT AND CLAY SIZES	FINE	MEDIUM	COARSE	FINE	COARSE	COBBLE
FINE GRAINED	SAND SIZE			GRAVEL SIZE		SIZE

## LEGEND

SYMBOL	Borehole	SAMPLE	ELEVATION(m)
●	OH-4	4	181.6
■	OH-5	4	185.3
◆	OH-3	5	181.6
▲	OH-2	7	183.4
▽	OH-3	7	179.5
○	OH-5	8	181.5
□	OH-6	9	184.8

Project Number: 1669996

Checked By: NK


**Golder Associates**

Date: 24-Apr-19

# GRAIN SIZE DISTRIBUTION

Clayey Silt to Clayey Silt with Sand Till

FIGURE C-6C



SILT AND CLAY SIZES	FINE	MEDIUM	COARSE	FINE	COARSE	COBBLE
FINE GRAINED	SAND SIZE			GRAVEL SIZE		SIZE

## LEGEND

SYMBOL	Borehole	SAMPLE	ELEVATION(m)
●	VMS-1	2	194.6
■	HML-1	3	182.9
◆	OH-1	5	186.1
▲	VMS-2	5	182.9
▽	VMS-1	6	191.5
○	VMS-2	7	181.4
□	HML-1	7	179.1

Project Number: 1669996

Checked By: NK


**Golder Associates**

Date: 24-Apr-19

# GRAIN SIZE DISTRIBUTION

Clayey Silt Till to Silt and Sand Till

FIGURE C-6D



SILT AND CLAY SIZES	FINE	MEDIUM	COARSE	FINE	COARSE	COBBLE
FINE GRAINED	SAND SIZE			GRAVEL SIZE		SIZE

## LEGEND


SYMBOL	Borehole	SAMPLE	ELEVATION(m)
●	CCTV-4	5	181.0
■	OH-4	6	180.1
◆	OH-1	7	184.7
▲	CCTV-4	7	178.7

Project Number: 1669996

Checked By: NK

**Golder Associates**

Date: 24-Apr-19



Ministry of Transportation


# PLASTICITY CHART Clayey Silt to Clayey Silt with Sand Till

Ontario

Figure No. C-7A

Project No. 1669996 (2200)

Checked By: NK



Ministry of Transportation


Ontario

# PLASTICITY CHART Silty Clay to Clayey Silt with Sand Till

Figure No. C-7B

Project No. 1669996 (2200)

Checked By: NK



Ministry of Transportation

Ontario

# PLASTICITY CHART Sandy Clayey Silt to Clayey Silt with Sand Till

Figure No. C-7C

Project No. 1669996 (2200)

Checked By: NK



**APPENDIX D**

# Analytical Chemical Test Results

Your Project #: 1669996  
Site Location: HIGHWAY 410  
Your C.O.C. #: 711260-01-01

**Attention: Nikol Kochmanova**

Golder Associates Ltd  
6925 Century Ave  
Suite 100  
Mississauga, ON  
CANADA L5N 7K2

**Report Date: 2019/04/06**  
Report #: R5659885  
Version: 1 - Final

**CERTIFICATE OF ANALYSIS**

**MAXXAM JOB #: B984871**

**Received: 2019/04/02, 10:06**

Sample Matrix: Soil  
# Samples Received: 8

Analyses	Quantity	Date Extracted	Date Analyzed	Laboratory Method	Reference
Chloride (20:1 extract)	8	2019/04/04	2019/04/05	CAM SOP-00463	SM 4500-Cl E m
Conductivity	8	2019/04/05	2019/04/05	CAM SOP-00414	OMOE E3530 v1 m
pH CaCl2 EXTRACT	8	2019/04/04	2019/04/04	CAM SOP-00413	EPA 9045 D m
Resistivity of Soil	8	2019/04/02	2019/04/05	CAM SOP-00414	SM 23 2510 m
Sulphate (20:1 Extract)	8	2019/04/04	2019/04/05	CAM SOP-00464	EPA 375.4 m

**Remarks:**

Maxxam Analytics' laboratories are accredited to ISO/IEC 17025:2005 for specific parameters on scopes of accreditation. Unless otherwise noted, procedures used by Maxxam are based upon recognized Provincial, Federal or US method compendia such as CCME, MDDELCC, EPA, APHA.

All work recorded herein has been done in accordance with procedures and practices ordinarily exercised by professionals in Maxxam's profession using accepted testing methodologies, quality assurance and quality control procedures (except where otherwise agreed by the client and Maxxam in writing). All data is in statistical control and has met quality control and method performance criteria unless otherwise noted. All method blanks are reported; unless indicated otherwise, associated sample data are not blank corrected. Where applicable, unless otherwise noted, Measurement Uncertainty has not been accounted for when stating conformity to the referenced standard.

Maxxam Analytics' liability is limited to the actual cost of the requested analyses, unless otherwise agreed in writing. There is no other warranty expressed or implied. Maxxam has been retained to provide analysis of samples provided by the Client using the testing methodology referenced in this report. Interpretation and use of test results are the sole responsibility of the Client and are not within the scope of services provided by Maxxam, unless otherwise agreed in writing. Maxxam is not responsible for the accuracy or any data impacts, that result from the information provided by the customer or their agent.

Solid sample results, except biota, are based on dry weight unless otherwise indicated. Organic analyses are not recovery corrected except for isotope dilution methods.

Results relate to samples tested. When sampling is not conducted by Maxxam, results relate to the supplied samples tested.

This Certificate shall not be reproduced except in full, without the written approval of the laboratory.

Reference Method suffix "m" indicates test methods incorporate validated modifications from specific reference methods to improve performance.

\* RPDs calculated using raw data. The rounding of final results may result in the apparent difference.

Your Project #: 1669996  
Site Location: HIGHWAY 410  
Your C.O.C. #: 711260-01-01

**Attention: Nikol Kochmanova**

Golder Associates Ltd  
6925 Century Ave  
Suite 100  
Mississauga, ON  
CANADA L5N 7K2

**Report Date: 2019/04/06**  
Report #: R5659885  
Version: 1 - Final

**CERTIFICATE OF ANALYSIS**

**MAXXAM JOB #: B984871**  
**Received: 2019/04/02, 10:06**

Encryption Key

Please direct all questions regarding this Certificate of Analysis to your Project Manager.  
Ema Gitej, Senior Project Manager  
Email: EGitej@maxxam.ca  
Phone# (905)817-5829

=====

Maxxam has procedures in place to guard against improper use of the electronic signature and have the required "signatories", as per section 5.10.2 of ISO/IEC 17025:2005(E), signing the reports. For Service Group specific validation please refer to the Validation Signature Page.

### RESULTS OF ANALYSES OF SOIL

Maxxam ID		JIO278		JIO279		JIO280	JIO281	JIO282		
Sampling Date		2019/03/12		2019/03/11		2019/03/10	2019/03/10	2019/03/11		
COC Number		711260-01-01		711260-01-01		711260-01-01	711260-01-01	711260-01-01		
	UNITS	OH-1 SA5	RDL	OH-2 SA2	RDL	OH-3 SA4	OH-4 SA3	OH-6 SA4	RDL	QC Batch

Calculated Parameters										
Resistivity	ohm-cm	1700		480		3900	1200	570		6050148
Inorganics										
Soluble (20:1) Chloride (Cl-)	ug/g	<20	20	770	20	44	430	820	20	6053319
Conductivity	umho/cm	579	2	2100	2	255	869	1760	2	6055159
Available (CaCl2) pH	pH	7.87		7.84		7.85	7.85	7.44		6051675
Soluble (20:1) Sulphate (SO4)	ug/g	590	20	1100	60	51	61	440	20	6053340
RDL = Reportable Detection Limit										
QC Batch = Quality Control Batch										

Maxxam ID		JIO283	JIO284	JIO285			JIO285	
Sampling Date		2019/03/17	2019/03/19	2019/03/24			2019/03/24	
COC Number		711260-01-01	711260-01-01	711260-01-01			711260-01-01	
	UNITS	CV-1 SA3	VMS-1 SA3	VMS-2 SA6	RDL	QC Batch	VMS-2 SA6 Lab-Dup	QC Batch

Calculated Parameters								
Resistivity	ohm-cm	1700	2400	4700		6050148		
Inorganics								
Soluble (20:1) Chloride (Cl-)	ug/g	35	100	30	20	6053319		
Conductivity	umho/cm	591	412	214	2	6055159		
Available (CaCl2) pH	pH	7.88	7.84	7.69		6051675	7.68	6051675
Soluble (20:1) Sulphate (SO4)	ug/g	480	140	50	20	6053340		
RDL = Reportable Detection Limit								
QC Batch = Quality Control Batch								
Lab-Dup = Laboratory Initiated Duplicate								

## TEST SUMMARY

**Maxxam ID:** JIO278  
**Sample ID:** OH-1 SA5  
**Matrix:** Soil

**Collected:** 2019/03/12  
**Shipped:**  
**Received:** 2019/04/02

Test Description	Instrumentation	Batch	Extracted	Date Analyzed	Analyst
Chloride (20:1 extract)	KONE/EC	6053319	2019/04/04	2019/04/05	Deonarine Ramnarine
Conductivity	AT	6055159	2019/04/05	2019/04/05	Kazzandra Adeva
pH CaCl2 EXTRACT	AT	6051675	2019/04/04	2019/04/04	Gnana Thomas
Resistivity of Soil		6050148	2019/04/05	2019/04/05	Automated Statchk
Sulphate (20:1 Extract)	KONE/EC	6053340	2019/04/04	2019/04/05	Deonarine Ramnarine

**Maxxam ID:** JIO279  
**Sample ID:** OH-2 SA2  
**Matrix:** Soil

**Collected:** 2019/03/11  
**Shipped:**  
**Received:** 2019/04/02

Test Description	Instrumentation	Batch	Extracted	Date Analyzed	Analyst
Chloride (20:1 extract)	KONE/EC	6053319	2019/04/04	2019/04/05	Deonarine Ramnarine
Conductivity	AT	6055159	2019/04/05	2019/04/05	Kazzandra Adeva
pH CaCl2 EXTRACT	AT	6051675	2019/04/04	2019/04/04	Gnana Thomas
Resistivity of Soil		6050148	2019/04/05	2019/04/05	Automated Statchk
Sulphate (20:1 Extract)	KONE/EC	6053340	2019/04/04	2019/04/05	Deonarine Ramnarine

**Maxxam ID:** JIO280  
**Sample ID:** OH-3 SA4  
**Matrix:** Soil

**Collected:** 2019/03/10  
**Shipped:**  
**Received:** 2019/04/02

Test Description	Instrumentation	Batch	Extracted	Date Analyzed	Analyst
Chloride (20:1 extract)	KONE/EC	6053319	2019/04/04	2019/04/05	Deonarine Ramnarine
Conductivity	AT	6055159	2019/04/05	2019/04/05	Kazzandra Adeva
pH CaCl2 EXTRACT	AT	6051675	2019/04/04	2019/04/04	Gnana Thomas
Resistivity of Soil		6050148	2019/04/05	2019/04/05	Automated Statchk
Sulphate (20:1 Extract)	KONE/EC	6053340	2019/04/04	2019/04/05	Deonarine Ramnarine

**Maxxam ID:** JIO281  
**Sample ID:** OH-4 SA3  
**Matrix:** Soil

**Collected:** 2019/03/10  
**Shipped:**  
**Received:** 2019/04/02

Test Description	Instrumentation	Batch	Extracted	Date Analyzed	Analyst
Chloride (20:1 extract)	KONE/EC	6053319	2019/04/04	2019/04/05	Deonarine Ramnarine
Conductivity	AT	6055159	2019/04/05	2019/04/05	Kazzandra Adeva
pH CaCl2 EXTRACT	AT	6051675	2019/04/04	2019/04/04	Gnana Thomas
Resistivity of Soil		6050148	2019/04/05	2019/04/05	Automated Statchk
Sulphate (20:1 Extract)	KONE/EC	6053340	2019/04/04	2019/04/05	Deonarine Ramnarine

**Maxxam ID:** JIO282  
**Sample ID:** OH-6 SA4  
**Matrix:** Soil

**Collected:** 2019/03/11  
**Shipped:**  
**Received:** 2019/04/02

Test Description	Instrumentation	Batch	Extracted	Date Analyzed	Analyst
Chloride (20:1 extract)	KONE/EC	6053319	2019/04/04	2019/04/05	Deonarine Ramnarine
Conductivity	AT	6055159	2019/04/05	2019/04/05	Kazzandra Adeva

## TEST SUMMARY

**Maxxam ID:** JIO282  
**Sample ID:** OH-6 SA4  
**Matrix:** Soil

**Collected:** 2019/03/11  
**Shipped:**  
**Received:** 2019/04/02

Test Description	Instrumentation	Batch	Extracted	Date Analyzed	Analyst
pH CaCl2 EXTRACT	AT	6051675	2019/04/04	2019/04/04	Gnana Thomas
Resistivity of Soil		6050148	2019/04/05	2019/04/05	Automated Statchk
Sulphate (20:1 Extract)	KONE/EC	6053340	2019/04/04	2019/04/05	Deonarine Ramnarine

**Maxxam ID:** JIO283  
**Sample ID:** CV-1 SA3  
**Matrix:** Soil

**Collected:** 2019/03/17  
**Shipped:**  
**Received:** 2019/04/02

Test Description	Instrumentation	Batch	Extracted	Date Analyzed	Analyst
Chloride (20:1 extract)	KONE/EC	6053319	2019/04/04	2019/04/05	Deonarine Ramnarine
Conductivity	AT	6055159	2019/04/05	2019/04/05	Kazzandra Adeva
pH CaCl2 EXTRACT	AT	6051675	2019/04/04	2019/04/04	Gnana Thomas
Resistivity of Soil		6050148	2019/04/05	2019/04/05	Automated Statchk
Sulphate (20:1 Extract)	KONE/EC	6053340	2019/04/04	2019/04/05	Deonarine Ramnarine

**Maxxam ID:** JIO284  
**Sample ID:** VMS-1 SA3  
**Matrix:** Soil

**Collected:** 2019/03/19  
**Shipped:**  
**Received:** 2019/04/02

Test Description	Instrumentation	Batch	Extracted	Date Analyzed	Analyst
Chloride (20:1 extract)	KONE/EC	6053319	2019/04/04	2019/04/05	Deonarine Ramnarine
Conductivity	AT	6055159	2019/04/05	2019/04/05	Kazzandra Adeva
pH CaCl2 EXTRACT	AT	6051675	2019/04/04	2019/04/04	Gnana Thomas
Resistivity of Soil		6050148	2019/04/05	2019/04/05	Automated Statchk
Sulphate (20:1 Extract)	KONE/EC	6053340	2019/04/04	2019/04/05	Deonarine Ramnarine

**Maxxam ID:** JIO285  
**Sample ID:** VMS-2 SA6  
**Matrix:** Soil

**Collected:** 2019/03/24  
**Shipped:**  
**Received:** 2019/04/02

Test Description	Instrumentation	Batch	Extracted	Date Analyzed	Analyst
Chloride (20:1 extract)	KONE/EC	6053319	2019/04/04	2019/04/05	Deonarine Ramnarine
Conductivity	AT	6055159	2019/04/05	2019/04/05	Kazzandra Adeva
pH CaCl2 EXTRACT	AT	6051675	2019/04/04	2019/04/04	Gnana Thomas
Resistivity of Soil		6050148	2019/04/05	2019/04/05	Automated Statchk
Sulphate (20:1 Extract)	KONE/EC	6053340	2019/04/04	2019/04/05	Deonarine Ramnarine

**Maxxam ID:** JIO285 Dup  
**Sample ID:** VMS-2 SA6  
**Matrix:** Soil

**Collected:** 2019/03/24  
**Shipped:**  
**Received:** 2019/04/02

Test Description	Instrumentation	Batch	Extracted	Date Analyzed	Analyst
pH CaCl2 EXTRACT	AT	6051675	2019/04/04	2019/04/04	Gnana Thomas

### GENERAL COMMENTS

Each temperature is the average of up to three cooler temperatures taken at receipt

Package 1	1.3°C
-----------	-------

**Results relate only to the items tested.**

## QUALITY ASSURANCE REPORT

Golder Associates Ltd  
Client Project #: 1669996  
Site Location: HIGHWAY 410  
Sampler Initials: SE

QC Batch	Parameter	Date	Matrix Spike		SPIKED BLANK		Method Blank		RPD	
			% Recovery	QC Limits	% Recovery	QC Limits	Value	UNITS	Value (%)	QC Limits
6051675	Available (CaCl <sub>2</sub> ) pH	2019/04/04			100	97 - 103			0.16	N/A
6053319	Soluble (20:1) Chloride (Cl <sup>-</sup> )	2019/04/05	NC	70 - 130	103	70 - 130	<20	ug/g	3.0	35
6053340	Soluble (20:1) Sulphate (SO <sub>4</sub> )	2019/04/05	NC	70 - 130	106	70 - 130	<20	ug/g	12	35
6055159	Conductivity	2019/04/05			102	90 - 110	<2	umho/cm	2.3	10

N/A = Not Applicable

Duplicate: Paired analysis of a separate portion of the same sample. Used to evaluate the variance in the measurement.

Matrix Spike: A sample to which a known amount of the analyte of interest has been added. Used to evaluate sample matrix interference.

Spiked Blank: A blank matrix sample to which a known amount of the analyte, usually from a second source, has been added. Used to evaluate method accuracy.

Method Blank: A blank matrix containing all reagents used in the analytical procedure. Used to identify laboratory contamination.

NC (Matrix Spike): The recovery in the matrix spike was not calculated. The relative difference between the concentration in the parent sample and the spike amount was too small to permit a reliable recovery calculation (matrix spike concentration was less than the native sample concentration)



### VALIDATION SIGNATURE PAGE

The analytical data and all QC contained in this report were reviewed and validated by the following individual(s).



Anastassia Hamanov, Scientific Specialist

---

Maxxam has procedures in place to guard against improper use of the electronic signature and have the required "signatories", as per section 5.10.2 of ISO/IEC 17025:2005(E), signing the reports. For Service Group specific validation please refer to the Validation Signature Page.

<b>INVOICE TO:</b>		<b>REPORT TO:</b>		<b>PROJECT INFORMATION:</b>		<b>Laboratory Use Only:</b>	
Company Name: #1326 Golder Associates Ltd		Company Name: <u>N. Kol Kochmanov</u>		Quotation #: B80683		Maxxam Job #:	
Attention: Accounts Payable		Attention: <u>N. Kol Kochmanov</u>		P.O. #: <u>1663496</u>		Bottle Order #:	
Address: 6925 Century Ave Suite 100		Address: <u>Highway 410</u>		Project Name: <u>Highway 410</u>		COC #:	
Mississauga ON L5N 7K2				Site #: <u>SE/THP</u>		Project Manager:	
Tel: (905) 567-4444 Fax: (905) 567-6561		Tel: <u>nikol-kochmanov@golder.com</u>		Sampled By: <u>SE/THP</u>		C#711260-01-01	
Email: AP_CustomerService@golder.com						Ema Gitej	

MOE REGULATED DRINKING WATER OR WATER INTENDED FOR HUMAN CONSUMPTION MUST BE SUBMITTED ON THE MAXXAM DRINKING WATER CHAIN OF CUSTODY

Regulation 153 (2011)			Other Regulations		Special Instructions		Field Filtered (please circle):	Metals / Hg / Cr / V	Corrosivity p/p (pH, Cl, SO4, EC/Resistivity)	ANALYSIS REQUESTED (PLEASE BE SPECIFIC)										Turnaround Time (TAT) Required:	
Table 1	Table 2	Table 3	Table	CCME	Reg 558	MISA				PWQO	Other										
<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>											# of Bottles		Comments
1				OH-1 SA5	Mar 12, 19	PM	Soil	✓										1			
2				OH-2 SA2	Mar 11, 19	PM	Soil	✓										1			
3				OH-3 SA4	Mar 10, 19	PM	Soil	✓										1			
4				OH-4 SA3	Mar 10, 19	PM	Soil	✓										1			
5				OH-6 SA4	Mar 11, 19	PM	Soil	✓										1			
6				CV-1 SA3	Mar 17, 19	PM	Soil	✓										1			
7				VMS-1 SA3	Mar 19, 19	PM	Soil	✓										1			
8				VMS-2 SA6	Mar 24, 19	PM	Soil	✓										1			
9																					
10																					

02-Apr-19 10:06

Ema Gitej



B984871

CA2 ENV-1089

* RELINQUISHED BY: (Signature/Print)		Date: (YY/MM/DD)		Time		RECEIVED BY: (Signature/Print)		Date: (YY/MM/DD)		Time		# jars used and not submitted		Laboratory Use Only	
<u>Eric Naylor</u>		19/04/02		10:05		<u>Eric Naylor</u>		19/04/02		10:06				Time Sensitive	
														Temperature (°C) on Reel	
														2/1/1	
														Custody Seal Present Intact	
														Yes No	

\* UNLESS OTHERWISE AGREED TO IN WRITING, WORK SUBMITTED ON THIS CHAIN OF CUSTODY IS SUBJECT TO MAXXAM'S STANDARD TERMS AND CONDITIONS. SIGNING OF THIS CHAIN OF CUSTODY DOCUMENT IS ACKNOWLEDGMENT AND ACCEPTANCE OF OUR TERMS WHICH ARE AVAILABLE FOR VIEWING AT WWW.MAXXAM.CA/TERMS.

\* IT IS THE RESPONSIBILITY OF THE RELINQUISHER TO ENSURE THE ACCURACY OF THE CHAIN OF CUSTODY RECORD. AN INCOMPLETE CHAIN OF CUSTODY MAY RESULT IN ANALYTICAL TAT DELAYS.

\*\* SAMPLE CONTAINER, PRESERVATION, HOLD TIME AND PACKAGE INFORMATION CAN BE VIEWED AT HTTP://MAXXAM.CA/WP-CONTENT/UPLOADS/ONTARIO-COC.PDF.

SAMPLES MUST BE KEPT COOL (< 10° C) FROM TIME OF SAMPLING UNTIL DELIVERY TO MAXXAM

White: Maxxa Yellow: Client



**[golder.com](http://golder.com)**