



THURBER ENGINEERING LTD.

**FINAL
FOUNDATION INVESTIGATION REPORT
REHABILITATION OF BRIDGE STRUCTURE No. 43X-0155/B0
MOORE CREEK BRIDGE HIGHWAY 523
LYELL TOWNSHIP
W.P. 5274-14-01
AGREEMENT NO.: 5015-E-0043**

GEOCRES NUMBER: 31F-199

**SUBMITTED TO
MCINTOSH PERRY CONSULTING ENGINEERS**

Location:

Latitude: 45.488553°
Longitude: -77.973778°

April 2019
Thurber File: 16284

Table of Contents

PART 1: FACTUAL INFORMATION

1	INTRODUCTION	1
2	SITE DESCRIPTION	1
3	SITE INVESTIGATION AND FIELD TESTING.....	2
3.1	Laboratory Testing.....	3
4	DESCRIPTION OF SUBSURFACE CONDITIONS	3
4.1	Overview / General	3
4.2	Asphalt.....	3
4.3	Fill	3
4.3.1	Sand Fill	3
4.3.2	Rock Fill.....	4
4.3.3	Gravel Fill	4
4.4	Silty Sand (SM) to Silt (ML)	4
4.5	Silty Sand with Gravel	5
4.6	Bedrock	5
4.7	Groundwater	5
4.8	Results of Analytical Tests	6
5	MISCELLANEOUS	7

APPENDICES

Appendix A	Drawings
Appendix B	Record of Borehole Sheets
Appendix C	Laboratory Test Results
Appendix D	Selected Photographs of Bridge Location

FINAL
FOUNDATION INVESTIGATION REPORT
REHABILITATION OF BRIDGE STRUCTURE No. 43X-0155/B0
MOORE CREEK BRIDGE HIGHWAY 523
LYELL TOWNSHIP
W.P. 5274-14-01
AGREEMENT NO.: 5015-E-0043

GEOCRES NUMBER: 31F-199

PART 1: FACTUAL INFORMATION

1 INTRODUCTION

This report presents the factual data obtained from a foundation investigation conducted by Thurber Engineering Ltd. (Thurber) for the proposed rehabilitation of the Moore Creek Bridge located on Highway 523, within Lyell Township. Thurber carried out the investigation as a subconsultant to McIntosh Perry Consulting Engineers (MPCE) as part of Agreement No. 5015-E-0043.

The purpose of this investigation was to explore the subsurface conditions at the site and, based on this data, provide a borehole location plan, record of boreholes, a stratigraphic profile, laboratory test results and a written description of the subsurface conditions. A base plan survey drawing was provided by MPCE for the preparation of this report.

An earlier foundation investigation report that has been obtained from the Geocres Library in preparation of this report is as follows:

Foundation Investigation Report, Sec. Hwy. #523 Line 'A' and Moore Ck., District of Nipissing, Twp. Of Lyell, District #10 (Bancroft), W.J. 61-F-21, W.P. 256-62 (Geocres 31F00-009), dated April 1965.

The historic boreholes were drilled prior to the re-alignment of Highway 523 and therefore do not reflect current conditions at the existing bridge. Furthermore, the position of the boreholes from the historical report relative to the boreholes completed as part of the current investigation are not known. Therefore, the historic boreholes have been included in Appendix A for information purposes only and have not been included in the description of the subsurface conditions within this report.

2 SITE DESCRIPTION

The existing structure (No. 43X-0155/B0) is located on Highway 523, approximately 1.8 km south of the junction of Highway 60 near Madawaska, Ontario. It is noted that for project orientation purposes, Highway 523 within the project limits, will be described with a north-south alignment. The location of the bridge is shown on the inset Key Plan on Drawing No. 1 in Appendix A.

Within the project limits, Highway 523 is a two-lane highway. Steel guide rails are located on both sides of the highway for a short distance from the bridge. The guide rails north of the bridge transition to a steel 3-cabled guide rail.

The existing bridge, as described in the RFP, is a 30 m single span bridge with a reinforced cast-in-place concrete deck constructed in 1986. The road width is reported to be 8.5 m with an overall width of 9.5 m.

The embankment slopes located adjacent to the abutment are inclined at approximately 1.25 to 1.5H:1V with the surface consisting of mainly rock fill with granular infill material. The north approach embankment extends out into the water approximately 300 m from the shoreline. Based on the survey data, the elevation of the center line of roadway was reported to be approximately 317.1 m and 317.8 m at the north and south abutments, respectively.

Historical Contract Drawings from 1984 indicate that the previous alignment of Highway 523 was west of the current bridge alignment. Adjacent to the west side of the bridge alignment are remnants of a platform used to support a bailey bridge along the original alignment of Highway 523. The topography adjacent to the creek at the site is rolling forested lands with frequent bedrock outcrops. The land in the vicinity of the bridge is mainly single-family dwellings and cottages with the exception of a camp ground which is present southwest of the bridge site. Traffic volumes are understood to be 530 AADT (2013)

Site photographs showing the general conditions at the site during the time of the field investigation are presented in Appendix D.

3 SITE INVESTIGATION AND FIELD TESTING

Thurber contacted Ontario One Call in advance of the field investigation to provide utility locate clearances in the vicinity of the intended boreholes.

The field investigation for this site included advancing three boreholes drilled from May 4, 2017 to May 13, 2017. The northing, easting and elevation of the boreholes are shown on the Borehole Location and Soil Strata Drawing No. 1 in Appendix A and are summarized in Table 3-1.

Table 3-1: Borehole Summary

Borehole No.	Drilled Location	Northing (m)	Easting (m)	Ground Surface Elevation (m)	Depth below Existing Ground Surface (m)
17-1A	North Abutment – southbound lane	5 039 799.3	189 583.6	317.1	13.0
17-1B	North Abutment – southbound lane	5 039 800.1	189 582.9	317.1	24.4
17-2	South Abutment – northbound lane	5 039 783.5	189 629.5	317.8	5.6

All boreholes were advanced through the roadway embankment with a truck mounted CME 75 drill rig equipped with HW/NW casing. The subsurface stratigraphy encountered in the boreholes was recorded in the field by Thurber personnel. Where possible split spoon samples were collected at regular depth intervals in the boreholes via the completion of Standard Penetration Tests (SPT), following the methods described in ASTM Standard D1586. Borehole 17-1B was advanced beyond the sampled depth of 21.7 m while completing a Dynamic Cone Penetration

Test (DCPT). All soil samples recovered from the boreholes were transported to Thurber's Ottawa geotechnical laboratory for further examination and testing.

All boreholes were backfilled with a low-permeability mixture of auger cuttings and bentonite pellets in general accordance with Ontario MOE Regulation 903. Boreholes advanced within paved areas were capped with cuttings followed by 150 mm of cold patch asphalt to reinstate the travelling surface.

The as-drilled locations and ground surface elevation of the boreholes were surveyed by MPCE in July 2017.

3.1 Laboratory Testing

Geotechnical laboratory testing consisted of natural moisture content determination and visual identification of all retained soil samples in accordance with the current MTO standards. Grain size distribution analyses testing was also carried out on selected samples to MTO and ASTM standards. Chemical analysis for determination of pH, resistivity, soluble sulphate and chloride concentrations was carried out on two soil samples.

The results of the geotechnical tests are summarized on the Record of Borehole sheets included in Appendix B and all laboratory results are presented on the figures included in Appendix C.

4 DESCRIPTION OF SUBSURFACE CONDITIONS

4.1 Overview / General

Reference is made to the Record of Borehole sheets in Appendix B for details of the soil stratigraphy encountered in the boreholes. A stratigraphic profile for the bridge area is presented on Drawing No. 1 in Appendix A for illustrative purposes. An overall description of the stratigraphy is given in the following paragraphs; however, the factual data presented in the Record of Boreholes governs any interpretation of the site conditions. It must be recognized that soil and groundwater conditions may vary between and beyond sampled locations.

The stratigraphy in the area of the boreholes through the embankment is generally characterized by the asphalt pavement structure with granular fill and rockfill embankment overlying native silty sand or silt above bedrock.

4.2 Asphalt

All three boreholes were advanced through the Highway 523 pavement structure and encountered asphalt ranging from 75 mm to 130 mm in thickness.

4.3 Fill

4.3.1 Sand Fill

A granular fill layer consisting predominantly of sand with silt and gravel to silty sand with gravel was encountered below the asphalt in boreholes on both sides of the bridge. Cobbles were noted within the granular fill in Borehole 17-2. This fill layer has a thickness ranging from 0.5 m to 2.5 m (base elevation of 315.2 m to 316.5 m). The SPT 'N' values ranged from 41 blows to greater

than 100 blows for 250 mm of penetration; indicating a dense to very dense condition. The higher blow counts could be attributed to the cobbles observed within the fill.

The results of a grain size analysis conducted on one sample of granular fill is summarized in Table 4-1 and illustrated on Figure C1 in Appendix C.

Table 4-1: Gradation Results for Granular Fill

Soil Particle	%
Gravel	39
Sand	51
Silt and Clay	10

4.3.2 Rock Fill

A layer consisting predominantly of rock fill was encountered beneath the granular fill in Boreholes 17-1 and 17-1B. Boreholes were advanced through the rockfill using casing and coring techniques. Sampling was attempted, however due to the nature of this material sample recovery was poor. The voids between rockfill pieces contained a granular material. Wood fragments were encountered in Borehole 17-1 at a depth near 3.0 m. The rockfill layer has a top elevation of 316.3 m to 316.5 m, and a thickness ranging from 6.7 m to 7.1 m. The SPT 'N' values varied from 13 blows to greater than 100 blows for 75 mm of penetration; indicating a compact to very dense condition. The lower N-values were obtained within the granular infill.

Rockfill pieces were cored and indicated particles with diameters ranging from 50 mm to 530 mm. Boulders estimated as large as 1.5 m in diameter were observed on the side slopes of the embankment in the area of the bridge.

4.3.3 Gravel Fill

A second granular fill layer consisting predominantly of gravel with sand was encountered below the rockfill within Boreholes 17-1 and 17-1B. This layer had a thickness ranging from 2.9 m to 3.2 m (bottom elevation of 306.4 m to 306.6 m). The SPT 'N' values typically ranged from 16 to 26 blows indicated a compact relative density. An N-value as high as 100 blows for 250 mm of penetration was encountered and may be attributed to boulders within this fill layer. Sample recovery was found to be very poor within this layer.

The moisture content of the granular fill samples tested ranged from 5% to 11%.

4.4 Silty Sand (SM) to Silt (ML)

A native layer of silty sand to silt was encountered below the fill layers in Boreholes 17-1 and 17-1B. A boulder was observed in this unit in Borehole 17-1, this boulder caused the termination of Borehole 17-1 within this layer. The surface of this deposit ranged in elevation from 306.4 m to 306.6 m and had a thickness of 10.4 m in Borehole 17-1B. The SPT 'N' values ranged from 4 to 25 blows per 0.3 m of penetration; indicating a loose to compact condition.

The moisture content for the samples tested ranged from 19% to 45%. The results of grain size analysis conducted on three samples of this material are summarized in Table 4-2 and are illustrated on Figure C2 in Appendix C.

Table 4-2: Gradation Results for Silty Sand (SM) to Silt (ML)

Soil Particle	%	
Gravel	0 to 3	
Sand	10 to 87	
Silt	66 to 89	10
Clay	1 to 2	

4.5 Silty Sand with Gravel

Underlying the silty sand layer, a native layer of silty sand with gravel was encountered in Borehole 17-1B. The surface of this deposit was found to be 296.2 m in elevation. This layer was inferred using a DCPT to have a thickness of 3.5 m. An SPT 'N' value of 9 blows was obtained from one split spoon within the layer indicating a loose condition.

The moisture content for the sample tested was 11%. Sample recovery was too poor for gradation analysis.

4.6 Bedrock

The overburden materials were underlain by very hard granite bedrock. Borehole 17-2 confirmed bedrock by coring 3.0 m as bedrock is shallow at the north abutment. The bedrock and inferred bedrock surface ranges from elevation 292.7 to 315.2 m as summarized in the table below:

Table 4-3 Summary of Bedrock Elevation

Location	Borehole No.	Depth Below Existing Ground Surface (m)	Top of Bedrock Elevation (m)
North Abutment	17-1B	24.4*	292.7*
South Abutment	17-2	2.6	315.2

Note: () inferred through use of a DCPT*

The Total Core Recovery (TCR) was 100%, the Solid Core Recovery (SCR) ranged from 63 to 81% and the Rock Quality Designation (RQD) ranged from 54 to 72%. Based on the RQD value the bedrock is classified as fair to good quality.

4.7 Groundwater

Borehole 17-2 was noted to be dry on completion of drilling. A representative water level could not be taken in Boreholes 17-1 and 17-1B due to water remaining within the casing from coring.

The water level in Moore Creek was surveyed by MPCE in May 2017 at an elevation of 313.4 m at the time of Thurber's field investigation.

These observations are considered short-term readings and seasonal fluctuations of the groundwater level are to be expected. In particular, the groundwater level may be at a higher elevation after the spring snowmelt or after periods of heavy and/or prolonged precipitation. Due

to the open nature of the rockfill approach embankments, it is expected that the groundwater level will respond rapidly to the water level changes in Moore Creek.

4.8 Results of Analytical Tests

Two samples of soil recovered from within the boreholes were selected and submitted for analytical testing including pH, conductivity, resistivity, chloride and sulphate. The results are summarized below and presented in the Certificate of Analysis included in Appendix C.

Table 4-4: Analytical Results Summary

Borehole	Sample	Depth (m)	pH	Conductivity ($\mu\text{S}/\text{cm}$)	Resistivity ($\text{Ohm}\cdot\text{cm}$)	Chloride ($\mu\text{g}/\text{g}$)	Sulphate ($\mu\text{g}/\text{g}$)
17-1	SS7	11.0	5.3	388	2580	7	332
17-2	SS2	1.2	7.3	167	5990	23	46

5 MISCELLANEOUS

Thurber obtained utility clearances prior to drilling and positioned the borehole locations relative to existing site features. MPCE surveyed the borehole locations and ground surface elevations. George Downing Estate Drilling Ltd. of Hawkesbury, Ontario supplied and operated the drilling equipment to carry out the drilling, sampling, in-situ testing and borehole decommissioning. The drilling, and sampling operations in the field were supervised on a full time basis by Mr. Jeffery Morrison, E.I.T. of Thurber. Laboratory testing was carried out in Thurber's MTO-approved laboratory in Ottawa.

Overall project management and direction of the field program was provided by Mr. Stephen Peters, P.Eng. Interpretation of the field data and preparation of this report was completed by Mr. Christopher Murray, M.Sc., P.Eng.. The report was reviewed by Dr. Fred Griffiths, P.Eng. and Dr. P.K. Chatterji, P.Eng., the Designated Principal Contact for MTO Foundations Projects.



Christopher Murray, M.Sc., P.Eng.
Geotechnical Engineer




Dr. Fred Griffiths, P.Eng.
Senior Associate
Senior Geotechnical Engineer




Dr. P.K. Chatterji, P.Eng.
MTO Review Principal
Senior Geotechnical Engineer

APPENDIX A
DRAWINGS



PLAN
SCALE 1:500



PROFILE ALONG C HWY 523

SCALE 1:500
H 1:500
V 1:250

METRIC
DIMENSIONS ARE IN METRES
AND/OR MILLIMETRES
UNLESS OTHERWISE SHOWN

CONT No
WP No 5274-14-01

HIGHWAY 523
MOORE CREEK BRIDGE
REHABILITATION
BOREHOLE LOCATIONS AND SOIL STRATA




SHEET

McINTOSH PERRY



THURBER ENGINEERING LTD.



KEYPLAN

LEGEND

	Borehole
	Borehole and Cone
N	Blows /0.3m (Std Pen Test, 475J/blow)
CONE	Blows /0.3m (60° Cone, 475J/blow)
PH	Pressure, Hydraulic
	Water Level
	Head Artesian Water
	Piezometer
90%	Rock Quality Designation (RQD)
A/R	Auger Refusal

NO	ELEVATION	NORTHING	EASTING
17-1	317.1	5 039 799.3	189 583.6
17-1B	317.1	5 039 800.1	189 582.9
17-2	317.8	5 039 783.5	189 629.5


-NOTES-

- The boundaries between soil strata have been established only at Borehole locations. Between Boreholes the boundaries are assumed from geological evidence.
- This drawing is for subsurface information only. Surface details and features are for conceptual illustration.


GEORES No. 31F-199




REVISIONS	DATE	BY	DESCRIPTION
DESIGN	SBP	CHK	PKC
DRAWN	AN	CHK	SBP
LOAD	DATE	APR 2019	
STRUCT	43X-0155/80	DWG	1



PLAN
1 : 150




ELEVATION
1 : 150



BENCHMARK:

302 BM 314.683 SPK/W N ROOT 2x300 Ø BIRCH



PROFILE OF HWY 523
N.T.S.

LEGEND:

- CONCRETE AND ASPHALT REMOVAL
- NEW ASPHALT
- NEW CONCRETE

SCOPE OF REHABILITATION WORK:

THE GENERAL SCOPE OF THE REHABILITATION WORK OUTLINED BELOW AND DESIGNATED ON THIS DRAWING SHALL BE CONSIDERED SIMILAR ON EACH SIDE OF THE CENTERLINE OF THE BRIDGE, UNLESS NOTED OTHERWISE. THIS IS NOT MEANT TO BE AN EXHAUSTIVE LIST OR INDICATE THE ORDER IN WHICH OPERATIONS SHOULD TAKE PLACE.

REMOVALS:

- REMOVE EXISTING ASPHALT AND WATERPROOFING FROM DECK.
- REMOVE DELAMINATED AND DETERIORATED CONCRETE FROM DECK AND APPROACH SLAB SURFACES.
- REMOVE PORTIONS OF TOP OF EXIST. BALLAST WALLS AND EXPANSION JOINT ASSEMBLIES.
- REMOVE EXPANSION JOINT CONCRETE DAMS AND JOINT ASSEMBLY.
- REMOVE PORTION OF EXIST. BARRIER WALLS.
- REMOVE DETERIORATED CONCRETE FROM DECK SOFFIT, WINGWALLS, ABUTMENT WALLS AND INTERIOR & EXTERIOR FASCIA OF BARRIER WALLS.
- REMOVE EXISTING ASPHALT FROM APPROACH SLAB.
- REMOVE EMPTY BELL DUCTS UNDER THE BRIDGE.
- OTHER AS SHOWN AND/OR SPECIFIED IN THE CONTRACT
- NOT INTENDED SEQUENCE OF REMOVALS.

NEW CONSTRUCTION:

- RECONSTRUCT PORTION OF TOP OF BALLAST WALLS.
- RECONSTRUCT EXPANSION JOINT CONCRETE DAMS AND INSTALL EXPANSION JOINT ASSEMBLY.
- RECONSTRUCT PORTIONS OF BARRIER WALLS.
- REPAIR DETERIORATED AREAS ON TOP OF DECK AND APPROACH SLAB.
- WATERPROOF AND PAVE THE DECK AND APPROACH SLABS TO THE LIMITS SHOWN ON THE DRAWINGS.
- REPAIR DETERIORATED AREAS AT DECK SOFFIT, WINGWALLS, ABUTMENT WALLS, AND INTERIOR & EXTERIOR FASCIA OF BARRIER WALLS. APPLY CONCRETE SEALER TO EAST WINGWALLS.
- COATING ENDS OF EXISTING GIRDERS.
- PLUG DECK DRAIN HOLES WITH CONCRETE.
- OTHER AS SHOWN AND/OR SPECIFIED IN THE CONTRACT
- NOT INTENDED SEQUENCE OF NEW CONSTRUCTION.

METRIC
DIMENSIONS ARE IN METRES
AND/OR MILLIMETRES
UNLESS OTHERWISE SHOWN

HWY 523
CONT. No. 2019-5006
WP No. 5274-14-00



MOORE CREEK BRIDGE
REHABILITATION
GENERAL ARRANGEMENT

SHEET
01

McINTOSH PERRY

GENERAL NOTES:

- CLASS OF CONCRETE: 30 MPa
CLEAR COVER TO REINFORCING STEEL:
-DECK TOP 70 ± 20
-DECK BOTTOM 40 ± 10
-REMAINDER 70 ± 20
UNLESS OTHERWISE NOTED
- REINFORCING STEEL:**
 - REINFORCING STEEL SHALL BE GRADE 400W.
 - UNLESS SHOWN OTHERWISE, TENSION LAP SPLICES FOR REINFORCING STEEL BARS SHALL BE CLASS B.
 - STAINLESS REINFORCING STEEL SHALL BE TYPE 316LN OR DUPLEX 2205 AND HAVE A MINIMUM YIELD STRENGTH OF 500 MPa, UNLESS OTHERWISE SPECIFIED,
 - BAR MARKS WITH PREFIX 'S' DENOTE STAINLESS STEEL BARS.
 - BAR HOOKS SHALL HAVE STANDARD HOOK DIMENSIONS USING MINIMUM BEND DIAMETERS, WHILE STIRRUPS AND TIES SHALL HAVE MINIMUM HOOK DIMENSIONS. ALL HOOKS SHALL BE IN ACCORDANCE WITH THE STRUCTURAL STANDARD DRAWING SS12-1, UNLESS INDICATED OTHERWISE.

CONSTRUCTION NOTES:

- CONTRACTOR SHALL OBTAIN LOCATES PRIOR TO PROCEEDING WITH CONSTRUCTION OPERATIONS.
- INFORMATION OF EXISTING STRUCTURE SHOWN WAS TAKEN FROM THE ORIGINAL DESIGN DRAWINGS. THE CONTRACTOR SHALL VERIFY ALL RELEVANT DIMENSIONS, ELEVATIONS, STATIONS AND DETAILS ON SITE AND REPORT ANY DISCREPANCIES TO THE DESIGN ENGINEER PRIOR TO PROCEEDING WITH REHABILITATION WORK.
- TYPICAL AREAS OF REPAIRS ARE INDICATED ON THE DRAWINGS WHERE REPAIR LIMITS ARE NOT SHOWN, LIMITS SHALL BE INDICATED BY THE CONTRACT ADMINISTRATOR.
- SAWCUT IN CONCRETE, WHERE DESIGNATED SHALL BE 25mm DEEP OR TO THE FIRST LAYER OF REINFORCING STEEL, WHICHEVER IS LESS. SAWCUT SURFACES AGAINST WHICH NEW CONCRETE WILL BE PLACED SHALL BE ROUGHENED.
- THE CONTRACTOR SHALL PROVIDE DEBRIS PLATFORMS AND NECESSARY CONTAINMENT MEASURES TO COLLECT FALLING CONCRETE AND CONSTRUCTION DEBRIS AND ENSURE THAT NO DEBRIS OR MATERIALS RESULTING FROM THE REMOVAL WORK FALLS ON WATERWAYS AND OTHER AREAS BELOW THE BRIDGES.

LIST OF ABBREVIATIONS:

T/CONC. DENOTES TOP OF CONCRETE
EL. DENOTES ELEVATION
BRGS DENOTES BEARINGS
ABUT. DENOTES ABUTMENT
TYP DENOTES TYPICAL
WP DENOTES WORKING POINT
STA. DENOTES STATION
NTS DENOTES NOT TO SCALE
T/FTG DENOTES TOP OF FOOTING

DRAWING LIST:

R1-1 GENERAL ARRANGEMENT
R1-2 CONSTRUCTION STAGING
R1-3 REMOVALS
R1-4 REPAIRS - DIMENSIONS
R1-5 REPAIRS - REINFORCEMENT
R1-6 STRIP SEAL EXPANSION JOINT - ASSEMBLY FOR BARRIER WALLS
R1-7 STRIP SEAL EXPANSION JOINT - TYPE 'C' DETAILS
R1-8 MISCELLANEOUS & STANDARD DETAILS

REVISIONS	DATE	BY	REV	DESCRIPTION
DESIGN	DS	CHK	TT	CODE CHBDC-14 LOAD CL-625-ONT DATE APR/18
DRAWN	HCG	CHK	DS	SITE 43X-0155/B0 STRUCT SCHEME DWG R1-01

DRAWING NOT TO BE SCALED
100mm ON ORIGINAL DRAWING

APPENDIX B
RECORD OF BOREHOLE SHEETS



SYMBOLS, ABBREVIATIONS AND TERMS USED ON TEST HOLE RECORDS

TERMINOLOGY DESCRIBING COMMON SOIL GENESIS

Topsoil	mixture of soil and humus capable of supporting vegetative growth
Peat	mixture of fragments of decayed organic matter
Till	unstratified glacial deposit which may include particles ranging in sizes from clay to boulder
Fill	material below the surface identified as placed by humans (excluding buried services)

TERMINOLOGY DESCRIBING SOIL STRUCTURE:

Desiccated	having visible signs of weathering by oxidization of clay materials, shrinkage cracks, etc.
Fissured	having cracks, and hence a blocky structure
Varved	composed of alternating layers of silt and clay
Stratified	composed of alternating successions of different soil types, e.g. silt and sand
Layer	> 75 mm in thickness
Seam	2 mm to 75 mm in thickness
Parting	< 2 mm in thickness

RECOVERY:

For soil samples, the recovery is recorded as the length of the soil sample recovered.

N-VALUE:

Numbers in this column are the field results of the Standard Penetration Test: the number of blows of a 63.5 kg hammer falling 0.76 m, required to drive a 50 mm O.D. split spoon sampler 0.3 m into undisturbed soil. For samples where insufficient penetration was achieved and N-value cannot be presented, the number of blows are reported over the sampler penetration in millimetres (e.g. 50/75).


DYNAMIC CONE PENETRATION TEST (DCPT):

Dynamic cone penetration tests are performed using a standard 60 degree apex cone connected to an "A" size drill rods with the same standard fall height and weight as the Standard Penetration Test. The DCPT value is the number of blows of the hammer required to drive the cone 0.3 m into the soil. The DCPT is used as a probe to assess soil variability.



STRATA PLOT:

Strata plots symbolize the soil and bedrock description. They are combinations of the following basic symbols. The dimensions within the strata symbols are not indicative of the particle size, layer thickness, etc.



Boulders
Cobbles
Gravel Sand Silt Clay Organics Asphalt Concrete Fill Bedrock

TEXTURING CLASSIFICATION OF SOILS

Classification	Particle Size
Boulders	Greater than 200 mm
Cobbles	75 – 200 mm
Gravel	4.75 – 75 mm
Sand	0.075 – 4.75 mm
Silt	0.002 – 0.075 mm
Clay	Less than 0.002 mm

TERMS DESCRIBING CONSISTENCY (COHESIVE SOILS ONLY)

Descriptive Term	Undrained Shear Strength (kPa)
Very Soft	12 or less
Soft	12 – 25
Firm	25 – 50
Stiff	50 – 100
Very Stiff	100 – 200
Hard	Greater than 200

NOTE: Clay sensitivity is defined as the ratio of the undisturbed strength over the remolded strength.

SAMPLE TYPES

SS	Split spoon samples
ST	Shelby tube or thin wall tube
DP	Direct push sample
PS	Piston sample
BS	Bulk sample
WS	Wash sample
HQ, NQ, BQ etc.	Rock core sample obtained with the use of standard size diamond coring equipment

TERMS DESCRIBING CONSISTENCY (COHESIONLESS SOILS ONLY)

Descriptive Term	SPT “N” Value
Very Loose	Less than 4
Loose	4 – 10
Compact	10 – 30
Dense	30 – 50
Very Dense	Greater than 50

MODIFIED UNIFIED SOIL CLASSIFICATION

Major Divisions		Group Symbol	Typical Description
COARSE GRAINED SOIL	GRAVEL AND GRAVELLY SOILS	GW	Well-graded gravels or gravel-sand mixtures, little or no fines.
		GP	Poorly-graded gravels or gravel-sand mixtures, little or no fines.
		GM	Silty gravels, gravel-sand-silt mixtures.
		GC	Clayey gravels, gravel-sand-clay mixtures.
	SAND AND SANDY SOILS	SW	Well-graded sands or gravelly sands, little or no fines.
		SP	Poorly-graded sands or gravelly sands, little or no fines.
		SM	Silty sands, sand-silt mixtures.
		SC	Clayey sands, sand-clay mixtures.
FINE GRAINED SOILS	SILT AND CLAY SOILS $W_L < 35\%$	ML	Inorganic silts, very fine sands, rock flour, silty or clayey fine sands or clayey silts with slight plasticity.
		CL	Inorganic clays of low to medium plasticity, gravelly clays, sandy clays, silty clays, lean clays.
		OL	Organic silts and organic silty-clays of low plasticity.
	SILT AND CLAY SOILS $35\% < W_L < 50\%$	MI	Inorganic compressible fine sandy silt with clay of medium plasticity, clayey silts.
		CI	Inorganic clays of medium plasticity, silty clays.
		OI	Organic silty clays of medium plasticity.
	SILT AND CLAY SOILS $W_L > 50\%$	MH	Inorganic silts, micaceous or diatomaceous fine sandy of silty soils, elastic silts.
		CH	Inorganic clays of high plasticity, fat clays.
		OH	Organic clays of high plasticity, organic silts.
HIGHLY ORGANIC SOILS		Pt	Peat and other organic soils.

Note - W_L = Liquid Limit



EXPLANATION OF ROCK LOGGING TERMS

ROCK WEATHERING CLASSIFICATION

Fresh (FR)	No visible signs of weathering.
Fresh Jointed (FJ)	Weathering limited to surface of major discontinuities.
Slightly Weathered (SW)	Penetrative weathering developed on open discontinuity surfaces, but only slight weathering of rock materials.
Moderately Weathered (MW)	Weathering extends throughout the rock mass, but the rock material is not friable.
Highly Weathered (HW)	Weathering extends throughout the rock mass and the rock is partly friable.
Completely Weathered (CW)	Rock is wholly decomposed and in a friable condition, but the rock texture and structures are preserved.

TERMS

Total Core Recovery: (TCR)	Core recovered as a percentage of total core run length.
Solid Core Recovery: (SCR)	Percent ratio of solid core of full cylindrical shape recovered. Expressed with respect to the total length of core run.
Rock Quality Designation: (RQD)	Total length of sound core recovered in pieces 0.1 m in length or larger, as a percentage of total core length
Unconfined Compressive Strength: (UCS)	Axial stress required to break the specimen.
Fracture Index: (FI)	Frequency of natural fractures per 0.3 m of core run.

DISCONTINUITY SPACING

Bedding	Bedding Plane Spacing
Very thickly bedded	Greater than 2 m
Thickly bedded	0.6 to 2 m
Medium bedded	0.2 to 0.6 m
Thinly bedded	60 mm to 0.2 m
Very thinly bedded	20 to 60 mm
Laminated	6 to 20 mm
Thinly laminated	Less than 6 mm

STRENGTH CLASSIFICATION

Rock Strength	Approximate Uniaxial Compressive Strength (MPa)
Extremely Strong	Greater than 250
Very Strong	100 – 250
Strong	50 – 100
Medium Strong	25 – 50
Weak	5 – 25
Very Weak	1 – 5
Extremely Weak	0.25 – 1

RECORD OF BOREHOLE No 17-1

1 OF 2

METRIC

WP# 5274-14-01 LOCATION Lat: 45.488605°, Long: -77.973999°
Moore Creek Bridge, MTM z9: N 5 039 799.3 E 189 583.6 ORIGINATED BY JM
HWY 523 BOREHOLE TYPE NW Casing COMPILED BY DJP
DATUM Geodetic DATE 2017.05.11 - 2017.05.11 CHECKED BY SP

SOIL PROFILE			SAMPLES			GROUND WATER CONDITIONS	ELEVATION SCALE	DYNAMIC CONE PENETRATION RESISTANCE PLOT				PLASTIC LIMIT NATURAL MOISTURE CONTENT LIQUID LIMIT			UNIT WEIGHT γ kN/m ³	REMARKS & GRAIN SIZE DISTRIBUTION (%) GR SA SI CL
ELEV DEPTH	DESCRIPTION	STRAT PLOT	NUMBER	TYPE	"N" VALUES			SHEAR STRENGTH kPa				WATER CONTENT (%)				
												W P W W L				
317.1							20 40 60 80 100									
0.0	130 mm ASPHALT															
0.1	SAND with Silt and Gravel Very Dense Brown		1	SS	59											
316.3	FILL															
0.7	ROCK FILL - Cobbles/Gravel from 0.7 m to 1.2 m		2	SS	31											
	- Cobbles/Gravel from 1.5 m to 2.0 m															
			3	SS	100/ 75mm											
	- Cobbles/Gravel from 2.7 m to 6.6 m															
	- Wood fragments plugging casing around 3.0 m															
	- 175 mm Boulder at 5.1 m															
	- 150 mm Boulder at 5.4 m															
	- Cobbles from 6.6 m to 7.8 m		4	SS	13											
309.3																
7.8	GRAVEL with Sand Compact Grey to Brown FILL		5	SS	26											
			6	SS	16											

Continued Next Page

+³, ×³: Numbers refer to
Sensitivity 20
15 10 5
(%) STRAIN AT FAILURE

RECORD OF BOREHOLE No 17-1

2 OF 2

METRIC

WP# 5274-14-01 LOCATION Lat: 45.488605°, Long: -77.973999°
Moore Creek Bridge, MTM z9: N 5 039 799.3 E 189 583.6 ORIGINATED BY JM
HWY 523 BOREHOLE TYPE NW Casing COMPILED BY DJP
DATUM Geodetic DATE 2017.05.11 - 2017.05.11 CHECKED BY SP

SOIL PROFILE			SAMPLES			GROUND WATER CONDITIONS	ELEVATION SCALE	DYNAMIC CONE PENETRATION RESISTANCE PLOT				UNIT WEIGHT γ kN/m ³	REMARKS & GRAIN SIZE DISTRIBUTION (%) GR SA SI CL
ELEV DEPTH	DESCRIPTION	STRAT PLOT	NUMBER	TYPE	"N" VALUES			SHEAR STRENGTH kPa					
								20 40 60 80 100					
	Continued From Previous Page												
306.4	GRAVEL with Sand Compact Grey to Brown FILL						307						
10.7	Silty SAND (SM) to SILT (ML) some Sand, trace Organics near surface Compact to Loose Brown		7	SS	18		306						
							305						
304.0	- 150 mm Boulder at 12.8 m		8	SS	4								
13.0	Boulder at 12.8 m caused casing to shear apart, Borehole abandoned at 13.0 m, Offset 1 m to Borehole 17-1B												

+³, ×³: Numbers refer to
Sensitivity 20
15 10 5
(%) STRAIN AT FAILURE

RECORD OF BOREHOLE No 17-1B

1 OF 3

METRIC

WP# 5274-14-01 LOCATION Lat: 45.488612°, Long: -77.974008°
Moore Creek Bridge, MTM z9: N 5 039 800.1 E 189 582.9 ORIGINATED BY JM
HWY 523 BOREHOLE TYPE HW Casing / NW Casing COMPILED BY DJP
DATUM Geodetic DATE 2017.05.12 - 2017.05.13 CHECKED BY SP

SOIL PROFILE			SAMPLES			GROUND WATER CONDITIONS	ELEVATION SCALE	DYNAMIC CONE PENETRATION RESISTANCE PLOT				PLASTIC LIMIT W _p	NATURAL MOISTURE CONTENT W	LIQUID LIMIT W _L	UNIT WEIGHT γ kN/m ³	REMARKS & GRAIN SIZE DISTRIBUTION (%) GR SA SI CL
ELEV DEPTH	DESCRIPTION	STRAT PLOT	NUMBER	TYPE	"N" VALUES			SHEAR STRENGTH kPa								
							20	40	60	80	100	20	40	60		
317.1																
0.0	130 mm ASPHALT						317									
0.1	SAND with Silt and Gravel															
316.5	Very Dense															
0.6	Brown															
	FILL															
	ROCK FILL															
	Frequent Cobbles						316									
							315									
							314									
							313									
							312									
							311									
	- 530 mm Boulder at 6.4 m						310									
309.8																
7.3	GRAVEL with Sand															
	Very Dense															
	Brown															
	FILL		1	SS	100/											
					250mm											
	- 200 mm Boulder at 8.0 m						309									
							308									

Continued Next Page

+³, ×³: Numbers refer to
Sensitivity

20
15
10
5
0
(%) STRAIN AT FAILURE

METRIC

[illegible]

+³, ×³: Numbers refer to Sensitivity

RECORD OF BOREHOLE No 17-1B

3 OF 3

METRIC

WP# 5274-14-01 LOCATION Lat: 45.488612°, Long: -77.974008°
Moore Creek Bridge, MTM z9: N 5 039 800.1 E 189 582.9 ORIGINATED BY JM
HWY 523 BOREHOLE TYPE HW Casing / NW Casing COMPILED BY DJP
DATUM Geodetic DATE 2017.05.12 - 2017.05.13 CHECKED BY SP

SOIL PROFILE			SAMPLES			GROUND WATER CONDITIONS	ELEVATION SCALE	DYNAMIC CONE PENETRATION RESISTANCE PLOT			UNIT WEIGHT γ kN/m ³	REMARKS & GRAIN SIZE DISTRIBUTION (%) GR SA SI CL	
ELEV DEPTH	DESCRIPTION	STRAT PLOT	NUMBER	TYPE	"N" VALUES			SHEAR STRENGTH kPa					
	Continued From Previous Page												
296.2	Silty SAND (SM) to SILT (ML) some Sand, trace Organics near surface Compact to Loose Brown to Grey		8	SS	8								
20.9	Silty SAND with Gravel Loose Grey		9	SS	9								
295.4	End of Sampled Borehole, Start of DCPT Inferred Silty SAND with Gravel												
21.7													
292.7													
24.4	End of DCPT at 24.4 m on Probable Bedrock												

+³, ×³: Numbers refer to Sensitivity
20
15
10
(%) STRAIN AT FAILURE

RECORD OF BOREHOLE No 17-2

1 OF 1

METRIC

WP# 5274-14-01 LOCATION Lat: 45.488471°, Long: -77.973408°
Moore Creek Bridge, MTM z9: N 5 039 783.5 E 189 629.5 ORIGINATED BY JM
HWY 523 BOREHOLE TYPE NW Casing / NQ Coring COMPILED BY DJP
DATUM Geodetic DATE 2017.05.04 - 2017.05.04 CHECKED BY SP

SOIL PROFILE			SAMPLES			GROUND WATER CONDITIONS	ELEVATION SCALE	DYNAMIC CONE PENETRATION RESISTANCE PLOT					UNIT WEIGHT γ kN/m ³	REMARKS & GRAIN SIZE DISTRIBUTION (%) GR SA SI CL
ELEV DEPTH	DESCRIPTION	STRAT PLOT	NUMBER	TYPE	"N" VALUES			SHEAR STRENGTH kPa						
								20 40 60 80 100						
								20 40 60 80 100						
317.8														
0.0	75mm ASPHALT													
0.1	Silty SAND with Gravel Dense to Very Dense Brown FILL - Cobbles from 0.7 m to 0.9 m		1	SS	41									39 51 10 (SI+CL)
	- Cobbles/Gravel from 1.5 m to 2.1 m		2	SS	65									
	- Cobbles from 2.3 m to 2.6 m		3	SS	100/ 250mm									
315.2														
2.6	Granite BEDROCK Moderately Weathered Pink/Grey Seams		1	RUN										RUN #1 TCR=100% SCR=81% RQD=72%
			2	RUN										RUN #2 TCR=100% SCR=63% RQD=54%
312.2														
5.6	End of Borehole at 5.6 m Borehole dry on completion													

DOUBLE LINE 16284 MOORE CREEK BRIDGE.GPJ 2012TEMPLATE(MTO).GDT 3/4/19

Borehole 17-2
Core Box 1 of 2
Elevation 94.3 m to 92.1 m



Borehole 17-2
Core Box 2 of 2
Elevation 92.1 m to 91.2 m



Foundation Investigation
Moore Creek Bridge
Structure No. 43-155
Lyell Township, Ontario

WP: 5274-14-01
Project No.: 16284

ABBREVIATIONS USED IN THIS REPORT

PENETRATION RESISTANCE

STANDARD PENETRATION RESISTANCE 'N' - THE NUMBER OF BLOWS REQUIRED TO ADVANCE A STANDARD SPLIT SPOON SAMPLER 12 INCHES INTO THE SUBSOIL, DRIVEN BY MEANS OF A 140 POUND HAMMER FALLING FREELY A DISTANCE OF 30 INCHES.

DYNAMIC PENETRATION RESISTANCE - THE NUMBER OF BLOWS REQUIRED TO ADVANCE A 2 INCH, 60 DEGREE CONE, FITTED TO THE END OF DRILL RODS, 12 INCHES INTO THE SUBSOIL. THE DRIVING ENERGY BEING 350 FOOT POUNDS PER BLOW.

DESCRIPTION OF SOIL

THE CONSISTENCY OF COHESIVE SOILS AND THE RELATIVE DENSITY OR DENSENESS OF COHESIONLESS SOILS ARE DESCRIBED IN THE FOLLOWING TERMS:-

<u>CONSISTENCY</u>	<u>'N' BLOWS / FT.</u>	<u>c LB. / SQ. FT.</u>	<u>DENSENESS</u>	<u>'N' BLOWS / FT.</u>
VERY SOFT	0 - 2	0 - 250	VERY LOOSE	0 - 4
SOFT	2 - 4	250 - 500	LOOSE	4 - 10
FIRM	4 - 8	500 - 1000	COMPACT	10 - 30
STIFF	8 - 15	1000 - 2000	DENSE	30 - 50
VERY STIFF	15 - 30	2000 - 4000	VERY DENSE	> 50
HARD	> 30	> 4000		

TYPE OF SAMPLE

S.S.	SPLIT SPOON	T.W.	THINWALL OPEN
W.S.	WASHED SAMPLE	T.P.	THINWALL PISTON
S.B.	SCRAPER BUCKET SAMPLE	O.S.	OESTERBERG SAMPLE
A.S.	AUGER SAMPLE	F.S.	FOIL SAMPLE
C.S.	CHUNK SAMPLE	R.C.	ROCK CORE
S.T.	SLOTTED TUBE SAMPLE		
	P.H. SAMPLE ADVANCED HYDRAULICALLY		
	P.M. SAMPLE ADVANCED MANUALLY		

SOIL TESTS

Qu	UNCONFINED COMPRESSION	L.V.	LABORATORY VANE
Q	UNDRAINED TRIAXIAL	F.V.	FIELD VANE
Qcu	CONSOLIDATED UNDRAINED TRIAXIAL	C	CONSOLIDATION
Qd	DRAINED TRIAXIAL	S	SENSITIVITY

ABBREVIATIONS USED IN THIS REPORT

SOIL PROPERTIES

γ	UNIT WEIGHT OF SOIL (BULK DENSITY)
γ_s	UNIT WEIGHT OF SOLID PARTICLES
γ_w	UNIT WEIGHT OF WATER
γ_d	UNIT DRY WEIGHT OF SOIL (DRY DENSITY)
γ'	UNIT WEIGHT OF SUBMERGED SOIL
G	SPECIFIC GRAVITY OF SOLID PARTICLES $G = \frac{\gamma_s}{\gamma_w}$
e	VOID RATIO
n	POROSITY
w	WATER CONTENT
S_r	DEGREE OF SATURATION
w_L	LIQUID LIMIT
w_P	PLASTIC LIMIT
I_P	PLASTICITY INDEX
s	SHRINKAGE LIMIT
I_L	LIQUIDITY INDEX = $\frac{w - w_P}{I_P}$
I_C	CONSISTENCY INDEX = $\frac{w_L - w}{I_P}$
e_{max}	VOID RATIO IN LOOSEST STATE
e_{min}	VOID RATIO IN DENSEST STATE
I_D	DENSITY INDEX = $\frac{e_{max} - e}{e_{max} - e_{min}}$
	RELATIVE DENSITY D_r IS ALSO USED
h	HYDRAULIC HEAD OR POTENTIAL
q	RATE OF DISCHARGE
v	VELOCITY OF FLOW
i	HYDRAULIC GRADIENT
k	COEFFICIENT OF PERMEABILITY
j	SEEPAGE FORCE PER UNIT VOLUME
m_v	COEFFICIENT OF VOLUME CHANGE = $\frac{-\Delta e}{(1+e)\Delta\sigma}$
C_v	COEFFICIENT OF CONSOLIDATION
C_c	COMPRESSION INDEX = $\frac{\Delta e}{\Delta \log_{10} \sigma}$
T_v	TIME FACTOR = $\frac{C_v t}{d^2}$ (d, DRAINAGE PATH)
U	DEGREE OF CONSOLIDATION
τ_f	SHEAR STRENGTH
c'	EFFECTIVE COHESION
ϕ'	EFFECTIVE ANGLE OF SHEARING RESISTANCE, OR FRICTION
c_u	APPARENT COHESION
ϕ_u	APPARENT ANGLE OF SHEARING RESISTANCE, OR FRICTION
μ	COEFFICIENT OF FRICTION
S_f	SENSITIVITY

GENERAL

π	= 3.1416
e	BASE OF NATURAL LOGARITHMS 2.7183
$\log_e a$ OR $\ln a$	NATURAL LOGARITHM OF a
$\log_{10} a$ OR $\log a$	LOGARITHM OF a TO BASE 10
t	TIME
g	ACCELERATION DUE TO GRAVITY
V	VOLUME
W	WEIGHT
M	MOMENT
F	FACTOR OF SAFETY

STRESS AND STRAIN

u	PORE PRESSURE
σ	NORMAL STRESS
σ'	NORMAL EFFECTIVE STRESS ($\bar{\sigma}$ IS ALSO USED)
τ	SHEAR STRESS
ϵ	LINEAR STRAIN
γ	SHEAR STRAIN
ν	POISSON'S RATIO (μ IS ALSO USED)
E	MODULUS OF LINEAR DEFORMATION (YOUNG'S MODULUS)
G	MODULUS OF SHEAR DEFORMATION
K	MODULUS OF COMPRESSIBILITY
η	COEFFICIENT OF VISCOSITY

EARTH PRESSURE

d	DISTANCE FROM TOP OF WALL TO POINT OF APPLICATION OF PRESSURE
δ	ANGLE OF WALL FRICTION
K	DIMENSIONLESS COEFFICIENT TO BE USED WITH VARIOUS SUFFIXES IN EXPRESSIONS REFERRING TO NORMAL STRESS ON WALLS
K_o	COEFFICIENT OF EARTH PRESSURE AT REST

FOUNDATIONS

B	BREADTH OF FOUNDATION
L	LENGTH OF FOUNDATION
D	DEPTH OF FOUNDATION BENEATH GROUND
N	DIMENSIONLESS COEFFICIENT USED WITH A SUFFIX APPLYING TO SPECIFIC GRAVITY, DEPTH AND COHESION ETC. IN THE FORMULA FOR BEARING CAPACITY
k_s	MODULUS OF SUBGRADE REACTION

SLOPES

H	VERTICAL HEIGHT OF SLOPE
D	DEPTH BELOW TOE OF SLOPE TO HARD STRATUM
β	ANGLE OF SLOPE TO HORIZONTAL

FOUNDATION SECTION

CHECKED BY K.G.S.

SOIL PROFILE			SAMPLES			ELEV. SCALE		DYNAMIC PENETRATION RESISTANCE BLOWS / FOOT		LIQUID LIMIT — WL PLASTIC LIMIT — WP WATER CONTENT — W		BULK DENSITY P.C.F.	REMARKS
ELEV. DEPTH	DESCRIPTION	STRAT. PLT	NUMBER	TYPE	BLOWS / FOOT			SHEAR STRENGTH P.S.F.	WP	W	WL		
1010.7	Ice level					1010							
1008.6	Ice												
1006.9	Water												
1005.9	Muck		1	SS	3								
4.8			2	SS	9	1000							
	Sandy silt to silty sand.		3	SS	10								
	Loose to very dense.		4	SS	5	990							
			5	SS	11	980							
			6	SS	23	970							
			7	SS	20	960							
949.2			8	SS	51	950							
61.8	End of borehole.					940							

DEPARTMENT OF HIGHWAYS - ONTARIO

RECORD OF BOREHOLE NO. 2

FOUNDATION SECTION

MATERIALS & TESTING DIVISION

JOB 65-F-22

LOCATION Moore Crk & Sec Hwy 523 Revised Line "A" Ch24/20-

ORIGINATED BY W.W.K.

W.P. 256-62

BORING DATE Feb. 7th, 1965

10'-0" Lt.

COMPILED BY W.W.K.

DATUM 1011.0

BOREHOLE TYPE Washboring - BX Casing.

CHECKED BY K.G.S.

SOIL PROFILE			SAMPLES			DYNAMIC PENETRATION RESISTANCE			LIQUID LIMIT — WL PLASTIC LIMIT — WP WATER CONTENT — W			BULK DENSITY P.C.F.	REMARKS			
ELEV. DEPTH	DESCRIPTION	STRAT. PLOT	NUMBER	TYPE	BLOWS / FOOT	ELEV. SCALE	BLOWS / FOOT			SHEAR STRENGTH P.S.F.				WATER CONTENT %		
1011.0	Ice level					1010										
1008.8	Ice															
1008.0	Water															
1006.4	Muck		1	SS	3											
4.6			2	SS	7	1000										
			3	SS	10											
	Sandy silt to silty sand.		4	SS	17		990									
	Loose to very dense.		5	SS	14		980									
		6	SS	12		970										
		7	SS	39		960										
		8	SS	59		950										
944.5	End of borehole.					940										

DEPARTMENT OF HIGHWAYS - ONTARIO
MATERIALS & TESTING DIVISION

RECORD OF BOREHOLE NO. 3

FOUNDATION SECTION

JOB 65-F-22 LOCATION Moore Crk & Sec Hwy 523 Revised Line "A" Ch24-50 on 6 ORIGINATED BY W.W.K.
W.P. 256-62 BORING DATE Feb. 8&9, 1965 COMPILED BY W.W.K.
DATUM 1011.5 BOREHOLE TYPE Washboring - BX Casin. CHECKED BY K.G.S.


SOIL PROFILE		SAMPLES			ELEV. SCALE	DYNAMIC PENETRATION RESISTANCE BLOWS / FOOT		LIQUID LIMIT — WL PLASTIC LIMIT — WP WATER CONTENT — W		BULK DENSITY P.C.F.	REMARKS
ELEV. DEPTH	DESCRIPTION	STRAT. PLOT	NUMBER	TYPE		BLOWS / FOOT	SHEAR STRENGTH P.S.F.		Wp — W — WL 20 40 60		
1011.5	Icelevel					1010					
1009.2	Ice										
1008.2	Water										
1006.7	Muck		1	SS	13						
4.8	Sandy silt to silty sand.		2	SS	2	1000					
			3	SS	6						
			4	SS	10	990					
			5	SS	12	980					
	Loose to very dense.	6	SS	17	970						
		7	SS	17	960						
950.0	End of borehole.	8	SS	57	950						
61.8						940					

DEPARTMENT OF HIGHWAYS - ONTARIO
MATERIALS & TESTING DIVISION

RECORD OF BOREHOLE NO. 4

FOUNDATION SECTION

JOB 65-F-22 LOCATION Moore Crk & Sec Hwy 523 Revised Line "A" Ch24/72 on E ORIGINATED BY W.W.K.
W.P. 256-62 BORING DATE Feb. 9&10, 1965 COMPILED BY W.W.K.
DATUM 1010.2 BOREHOLE TYPE Washboring - BX Casing CHECKED BY K.G.S.



MATERIALS & TESTING DIVISION

RECORD OF BOREHOLE NO. 5

FOUNDATION SECTION

JOB 65-F-22LOCATION Moore Crk & Sec Hwy 523 Revised Line "A" Ch 25/00 on EORIGINATED BY W.W.K.W.P. 256-62BORING DATE Feb. 11-24, 1965COMPILED BY W.W.K.DATUM 1007.5BOREHOLE TYPE Washboring BX CasingCHECKED BY K.G.S.

SOIL PROFILE			SAMPLES			ELEV. SCALE	DYNAMIC PENETRATION RESISTANCE				LIQUID LIMIT ——— w_L			BULK DENSITY	REMARKS
ELEV. DEPTH	DESCRIPTION	STRAT. PLOT	NUMBER	TYPE	BLOWS / FOOT		BLOWS / FOOT	SHEAR STRENGTH P.S.F.				PLASTIC LIMIT ——— w_p	WATER CONTENT ——— w		
							20 40 60 80 100								
1007.5	Ice level														
1005.5	Ice														
1003.5	Water														
1002.5	Muck														
5.5	Sandy silt to silty sand. Loose to very dense. Frequent boulders.		1	SS	1	1000									
			2	SS	4										
			3	SS	11	990									
			4	SS	105										
			for 3"												
			5	SS	34	980									
			6	SS	78										
972.8	Granite Bedrock														
34.7						970									
966.3															
41.2	End of borehole.					960									

DEPARTMENT OF HIGHWAYS - ONTARIO

MATERIALS & TESTING DIVISION

RECORD OF BOREHOLE NO. 6

FOUNDATION SECTION

JOB 65-F-22LOCATION Moore Crk & Sec Hwy 523 Revised Line "A" Ch25/26 on EORIGINATED BY W.W.K.W.P. 256-62BORING DATE Feb. 24&25, 1965COMPILED BY W.W.K.DATUM 1007.5BOREHOLE TYPE Washboring BX Casing.CHECKED BY K.G.S.

SOIL PROFILE

SAMPLES

DYNAMIC PENETRATION RESISTANCE

BLOWS / FOOT

20 40 60 80 100

SHEAR STRENGTH P.S.F.

LIQUID LIMIT ——— WL

PLASTIC LIMIT ——— WP

WATER CONTENT ——— W

WP ——— W ——— WL
 ————

WATER CONTENT %
 20 40 60

BULK
DENSITY
Y
P.C.F.

REMARKS

ELEV.
DEPTH

DESCRIPTION

STRAT. PLOT

NUMBER

TYPE

BLOWS / FOOT

ELEV. SCALE

1000

990

980

1007.5 Ice level

1006.0 Ice

1004.5 Water

1004.5 Muck

3.0 Sandy silt to silty
sand.
Compact.
Frequent boulders.

995.4

12.1 Granite Bedrock

989.9

17.6 End of borehole.

1 SS 20

2 SS 16

o

o

DEPARTMENT OF HIGHWAYS - ONTARIO

MATERIALS & TESTING DIVISION

RECORD OF BOREHOLE NO. 7

FOUNDATION SECTION

JOB 65-F-22LOCATION Moore Crk & Sec Hwy 523 Revised Line "A" Ch 25+52 on EORIGINATED BY W.W.K.W.P. 256-62BORING DATE Feb. 24, 1965.COMPILED BY W.W.K.DATUM 1009.8BOREHOLE TYPE BX Casing RunCHECKED BY K.G.S.

SOIL PROFILE			SAMPLES			ELEV. SCALE	DYNAMIC PENETRATION RESISTANCE						LIQUID LIMIT ——— w_L PLASTIC LIMIT ——— w_p WATER CONTENT ——— w w_p ——— w ——— w_L WATER CONTENT %			BULK DENSITY γ P.C.F.	REMARKS
ELEV. DEPTH	DESCRIPTION	STRAT. PLOT	NUMBER	TYPE	BLOWS / FOOT		SHEAR STRENGTH P.S.F.										
1009.8	Groundlevel																
0.0	Sandy silt to silty sand. Compact.																
1002.0	Frequent Boulders.																
7.8	Granite Bedrock					1000											
997.0																	
12.8	End of borehole.					990											

WL

El. 1007.5

Observed in casing.

▼ WL
El 1007.5
Observed
in casing.

DEPARTMENT OF HIGHWAYS - ONTARIO

MATERIALS & TESTING DIVISION

JOB 65-F-22

W. P. 256-62

DATUM 1025.3

LOCATION Moore Crk & Sec Hwy 523 Revised Line "A" Ch25/80 on E

BORING DATE Feb. 27, 1965

BOREHOLE TYPE EX Casing Run

FOUNDATION SECTION

ORIGINATED BY W.W.K.

COMPILED BY _____ W.W.K.

CHECKED BY _____ K.G.S.

SOIL PROFILE			SAMPLES			ELEV. SCALE	DYNAMIC PENETRATION RESISTANCE BLOWS / FOOT	LIQUID LIMIT ——— WL PLASTIC LIMIT ——— WP WATER CONTENT ——— W			BULK DENSITY P.C.F.	REMARKS
ELEV. DEPTH	DESCRIPTION	STRAT. PLOT	NUMBER	TYPE	BLOWS / FOOT		SHEAR STRENGTH P.S.F.	wp w WL 				
1025.3	Groundlevel											
	Sandy silt to silty sand. Compact					1020						
1021.1	Frequent boulders											
4.2	Granite Bedrock											
1015.4						1010						
9.9	End of borehole											

CHECKED BY _____ K.G.S.

RECORD OF BOREHOLE NO. 9


[illegible]

APPENDIX C
LABORATORY TEST RESULTS

Moore Creek Bridge

GRAIN SIZE DISTRIBUTION

FIGURE C1



SILT and CLAY	FINE	MEDIUM	COARSE	FINE	COARSE	COBBLE SIZE
FINE GRAINED	SAND			GRAVEL		

LEGEND

SYMBOL	BOREHOLE	DEPTH (m)	ELEV. (m)
●	17-2	0.38	317.44

Date April 2019
 WP# 5274-14-01




Prep'd CM
 Chkd. SP

Moore Creek Bridge

GRAIN SIZE DISTRIBUTION

FIGURE C2

Silty Sand to Silt some Sand



SILT and CLAY	FINE	MEDIUM	COARSE	FINE	COARSE	COBBLE SIZE
FINE GRAINED	SAND			GRAVEL		

LEGEND

SYMBOL	BOREHOLE	DEPTH (m)	ELEV. (m)
●	17-1B	10.97	306.10
⊠	17-1B	15.54	301.53
▲	17-1B	18.59	298.48

Date April 2019
 WP# 5274-14-01



Prep'd CM
 Chkd. SP

Certificate of Analysis
Client: Thurber Engineering Ltd.
Client PO: 16284

Report Date: 01-Jun-2017

Order Date: 26-May-2017

Project Description: Moores Creek Bridge

Client ID:	17-1, SS7, 35'-39'	17-2, SS2, 3'1"-5'1"	-	-
Sample Date:	12-May-17	04-May-17	-	-
Sample ID:	1721509-01	1721509-02	-	-
MDL/Units	Soil	Soil	-	-

Physical Characteristics

% Solids	0.1 % by Wt.	99.2	95.7	-	-
----------	--------------	------	------	---	---

General Inorganics

Conductivity	5 uS/cm	388	167	-	-
pH	0.05 pH Units	5.26	7.34	-	-
Resistivity	0.10 Ohm.m	25.8	59.9	-	-

Anions

Chloride	5 ug/g dry	7	23	-	-
Sulphate	5 ug/g dry	332	46	-	-

APPENDIX D
SELECTED PHOTOGRAPHS



Figure 1: Roadway Platform at Bridge 43X-0155/B0 looking South



Figure 2: Previous Bridge Alignment looking North from South Abutment



Figure 3: Looking towards South Abutment



Figure 4: Looking North from South Abutment